COMPUTER DESIGN

THE MAGAZINE OF DIGITAL ELECTRONICS

... GEORGE E. FREEMAN LIBRARY
STATE TECHNICAL INSTITUTE AT MEMPHIS
5983 Macon Cove at Interstate 40
Memphis, Tennessee 38134

NOVEMBER 1977

DESIGN GUIDELINES FOR A COMPUTER VOICE RESPONSE SYSTEM

COMPUTER QUEUING ANALYSIS ON A HANDHELD CALCULATOR

MAGNETIC TAPE FORMATTER DESIGN REDUCES HARDWARE/ SOFTWARE REQUIREMENTS



...me Vector 910-61:52--Retrofir
...-Ph 8.21--Sodium.014-Prot
SE Winds over Azores 76.4k

Introducing

HP's first general-purpose Logic State Analyzer designed for both controllable production testing and field service...and it's low cost.

Until now, production line testing of digital equipment has meant complex test gear, large sums for computerized equipment or time-consuming manual checks . . . perhaps all three. In the field, it's been traditional test gear without the measurement capabilities of logic state analyzers.

Now, with the low-cost 1602A, HP offers a general-purpose, Logic State Analyzer that's easy to use in a number of plant or field applications. Manufacturing can use it in automatic functional test systems or in board-level and incoming inspection testing. And its ease of use, light weight and portability makes it a natural for field service applications, too.

The 1602A, priced at $1800*, is compatible with many logic systems having data rates to 10 MHz. It monitors, stores and displays activity on system buses or control lines (up to 64, 16-bit words on a single instrument) to verify proper system function.

It's portable, adaptable to automatic control, low cost and so easy to operate it's almost self teaching. It can boost your production-line testing throughput and field-service troubleshooting efficiency. Get all the details from your HP field engineer.

For manual production line testing and for field service troubleshooting, the 1602A keyboard lets you define testing and display parameters with just a few keystrokes. The LED display then lets you compare line or bus activity with test specifications.

For automatic systems, an HP-IB** option lets you do setups and evaluation using a computing controller. When used with HP's 9830A or 9825A controllers, programming is simple. An operator just presses a few special-function keys, and the HP-IB's "Learn Mode" does the rest.

Edge-connector probes speed setup. When test points are built into your system's boards or board extenders, the probes are simply plugged in. Time-consuming and error-prone probe connections can be eliminated.

This instrument minimizes chances of error two ways: Extensive messages tell the operator that the 1602A is being used properly. And internal diagnostics verify proper operation.

* Domestic U.S.A. price only.
** HP's implementation of IEEE Standard 488-1975.

HEWLETT hp PACKARD

1507 Page Mill Road, Palo Alto, California 94304

For assistance call: Washington (301) 948-6370, Chicago (312) 255-9800, Atlanta (404) 955-1500, Los Angeles (213) 877-1282

087/12

CIRCLE 1 ON INQUIRY CARD

Models 9100/9300 Vacuum Column Tape Transports. We didn't have to make them this good.

Kennedy vacuum column digital tape transports have been the standard of the industry from their introduction. Some companies would have stopped and relaxed. We didn't. We added features such as our capacitive tape-location detector, for improved tape life; air bearings and tribaloy coated read-after-write heads to reduce tape wear and improve data integrity, and we've achieved the lowest noise level in the industry.

Performance is just as impressive, with tape speeds to 125 ips (75 ips on Model 9100) and operating features such as crystal controlled timing, read threshold scanning, read-after-write shortened skew gate, front-accessible test panel, quick-release hubs and simplified tape loading.

Data densities are 200/556 cpi or 556/800 on our 7-track unit and 800 cpi, 1600 cpi or 800/1600 cpi on the 9-track transport. The format is NRZI/PE.

We could have eliminated some of the features of Models 9100/9300, and still have a transport as good as the best. But we didn't. It's a Kennedy product and it has to be this good.

KENNEDY CO.

540 W. WOODBURY RD., ALTADENA, CALIF. 91001
(213) 798-0953

KENNEDY- QUALITY- COUNT ON IT

CIRCLE 2 ON INQUIRY CARD

THE SUPER NETWORK CHECKER OUTER, SERVICE RESTORER, PROBLEM SOLVER, FAULT ISOLATOR, AND FINGER POINTER ELIMINATOR.



Downtime in a data communication network is too costly to be a guessing game. And operating personnel shouldn't be concerned with questions like what's the problem, where's the problem, and when did it happen? Not when they're supposed to be getting your data through.

That's why we developed the System 180 Network Diagnostic Controller. It checks up on networks with up to 16 dedicated lines, with as many as 254 modems per line. If there's a problem at a remote site, it lets your central site personnel know immediately. Much of the time, it allows your personnel to take prompt action to restore service, even at unattended sites.

Our new 8-page brochure describes all the good things System 180 can do for your network. Send for your free copy.

Racal-Milgo™ — the new name for ICC

© 1977
Racal-Milgo, Inc., 8600 N.W. 41st Street, Miami, Florida 33166, Telephone (305) 592-8600

member of IDCMA

In Europe: Racal-Milgo Limited, Reading, Berks, England

CIRCLE 3 ON INQUIRY CARD

THE MAGAZINE OF DIGITAL ELECTRONICS

COMPUTER DESIGN

NOVEMBER 1977 • VOLUME 16 • NUMBER 11

FEATURES

73 **DESIGN GUIDELINES FOR A COMPUTER VOICE RESPONSE SYSTEM**
by Paul Thordarson
By understanding the various technologies necessary to make a computer "speak," designers are able to choose the best method for structuring machine-to-person voice communications

85 **COMPUTER QUEUING ANALYSIS ON A HANDHELD CALCULATOR**
by Ronald Zussman
Generalized multiserver queuing models are furnished to estimate computer performance and to locate system bottlenecks. This immediate and practical application of queuing theory allows iterative design decisions for optimum system effectiveness and convenience

99 **MAGNETIC TAPE FORMATTER DESIGN REDUCES HARDWARE/SOFTWARE REQUIREMENTS**
by A. Scott McPhillips
Replacing most of the existing hardware with a microcomputer and associated software, results in a magnetic tape formatter design which uses fewer parts, handles tape transports at all common speeds and densities, and provides an IEEE-488 standard interface

106 **PATTERN SENSITIVITY TECHNIQUES FOR TESTING CCD MEMORIES**
by Ivan D. Vancov
By exploiting the internal structure of the CCD memory, simple but conclusive parameter and pattern test programs have been devised. Tabulated results verify that opportune and cost-effective accuracy and sensitivity are obtained

120 **TWO-STEP PROCEDURE IMPROVES CRC MECHANISM**
by Patrick J. Fortune
A CRC error detection mechanism used with current bit-oriented data communications protocols to eliminate problems involved with detecting leading and trailing 0 bits is elucidated, as are the design and implementation concerns of its associated hardware

168 **DISKETTE DRIVE PROVIDES 4-SIDED, DOUBLE-DENSITY CAPABILITY**
With no increase in physical dimensions over standard dual diskette drives, this double-side, double-density unit has a maximum unformatted capacity of 25.6M bits

DEPARTMENTS

6 CALENDAR
12 LETTERS TO THE EDITOR
14 COMMUNICATION CHANNEL
27 DIGITAL TECHNOLOGY REVIEW
48 DIGITAL CONTROL AND AUTOMATION SYSTEMS
110 TECH BRIEFS
132 MICRO PROCESSOR/ COMPUTER DATA STACK
146 AROUND THE IC LOOP
172 PRODUCTS
215 LITERATURE
217 GUIDE TO PRODUCT INFORMATION
222 ADVERTISERS' INDEX
Reader Service Cards pages 225-228

BPA CIRCULATION OVER 55,000

Publisher's statement of qualified circulation—67,000

Copyright 1977, Computer Design Publishing Corp.

Tickets—Labels—Multiple Forms
VICTOR
has the printer for you.



129



130



155



MODEL 5000-463

A low cost, reliable printer, backed by Victor's one year warranty, offers the solution to your printing problems. The Victor line of sprocket-feed printers for labels, tickets or pre-printed forms provides outstanding legibility combined with proven reliability.

The 5000-463 series offers you three choices of interface: parallel; RS232C or TTY current loop. This allows the printer to be connected directly to most computers or microprocessors.

The printer prints 64 ASCII alphanumeric and symbolic characters. By sending the proper command code, characters can be expanded, printed in red or both for highlighting or headlining.

There are no moving parts when the unit is not printing which keeps the noise level down and increases reliability since the printer is not wearing itself out while sitting idle.

The dot matrix printing mechanism in the sprocket feed printer is similar to those used in almost 500,000 Victor print mechanisms in use today.

If you print any of these applications:

Pharmacy systems
Inventory control
Hospital supply systems
Ticket Printing
Label Printing

Then send this coupon today

John Tullio
Victor Business Products
3900 N. Rockwell Street
Chicago, Illinois 60618
312-539-8200

Send Technical Literature
☐ Sprocket Feed Printers
☐ All Victor's Print Mechanisms

Name_____

Company_____

City/State_____

Zip_____ Phone_____

VICTOR

STAFF

Publisher and Editorial Director
Robert Brotherston

Associate Publisher
Anthony Saltalamacchia

Editor
John A. Camuso

Managing Editor
Sydney F. Shapiro

Technical Editor
George V. Kotelly

Associate Editor
Peggy Killmon

Assistant Editor
Joanne O'Donnell

Editorial Assistant
Renée C. Gregorio

Editorial Advisory Board
Brian W. Pollard
Ralph J. Preiss
Rex Rice

Contributing Editors
Richard Ahrons
A. S. Buchman
H. S. Miller
Harold H. Seward

Production Manager
Judy Lober

Advertising Production
Linda M. Wright

Art Director
James Flora

Technical Illustrator
Charles Manchester

Circulation Manager
Alma Brotherston

Marketing Manager
Geoffrey Knight, Jr.

Assistant Marketing Manager
Megan Kern

Research Associate
Sidney Davis

Business Manager
David C. Ciommo

Vice President-Sales
Lindsay H. Caldwell

Editorial & Executive Offices
11 Goldsmith St
Littleton, MA 01460
Tel. (617) 486-8944
(617) 646-7872

Editorial manuscripts should be addressed to Editor, Computer Design, 11 Goldsmith St., Littleton, MA 01460. For details on the preparation and submission of manuscripts, request a copy of the "Computer Design Author's Guide."

Computer Design is published monthly. Copyright 1977 by Computer Design Publishing Corporation. Controlled circulation postage paid at Pontiac, Ill. No material may be reprinted without permission. Postmaster: CHANGE OF ADDRESS—FORM 3579 to be sent to Computer Design, Circulation Dept., P.O. Box A, Winchester, MA 01890. Subscription rate is $24.00 in U.S.A., Canada and Mexico, and $40.00 elsewhere. Microfilm copies of Computer Design are available and may be purchased from University Microfilms, a Xerox Company, 300 N. Zeeb Rd, Ann Arbor, MI 48106.

CIRCLE 19 ON INQUIRY CARD

QUIETIZED

MODEL 1560-AS
Combination reader/punch with serial asynchronous RS-232C compatible interface utilizing ASCII-DC codes to control devices.

COMPATIBILITY



MODEL 1060-AS
Punch with serial asynchronous RS-232C compatible interface.

EXPERIENCE

MODEL 1560-P
Combination reader/punch with parallel TTL level interface.

HI-QUALITY



MODEL 1060-P
Punch with parallel TTL level interface.

if you design or use data processing systems for communications, data collection, instrumentation, etc. here are the best reasons to go with

ROYTRON™

PROVEN DEPENDABLE

HI-SPEED SERIES PAPER TAPE UNITS

All Made in U.S.A.

OEM DISCOUNTS



MODEL 1250-AS
Reader with serial asynchronous RS-232C compatible interface.

RELIABILITY



MODEL 500
Basic Punch Mechanism operates at 60 cps. For OEM's who prefer to provide their own circuitry and housing.

DESIGNER'S DELIGHT

If you value your skins more than ours, we'll sell you the pieces.

Every unit at OEM quantity discount prices.

For full details, write or call us.

SWEDA INTERNATIONAL, INC.

Litton O.E.M. Products

34 Maple Avenue, Pine Brook, N.J. 07058/(201) 575-8100

IN U.K. — ADLER BUS. SYSTEMS/OEM PRODS., Airport House, Purley Way, Croyden, Surrey, England

IN FRANCE — SWEDA INTERNATIONAL/OEM, 103-107 Rue de Tocqueville, 75017 Paris, France

CIRCLE 5 ON INQUIRY CARD

CALENDAR

CONFERENCES

NOV 14-16—Distributed Data Processing Conf, Ramada O'Hare Inn, Chicago, Ill. INFORMATION: American Institute of Industrial Engineers (AIIE), Dept PR, PO Box 3727, Santa Monica, CA 90403. Tel: (213) 450-0500

NOV 15-17—6th Annual Meeting of Members of Computer-Aided Manufacturing—Internat'l (CAM-I), Americana Inn, Arlington, Tex. INFORMATION: C. H. Link, Exec Secretary and Gen'l Mgr, CAM-I, 611 Ryan Plaza Dr, Suite 1107, Arlington, TX 76011. Tel: (817) 265-5328

NOV 17 and JAN 19—Invitational Computer Conf, Houston Oaks, Houston, Tex; South Coast Plaza Hotel, Orange County, Calif. INFORMATION: B. J. Johnson & Associates, 2503 Eastbluff Dr, Suite 203, Newport Beach, CA 92660. Tel: (714) 644-6037

NOV 28—NBS and IEEE Personal Computing Conf, Nat'l Bureau of Stds, Gaithersburg, Md. INFORMATION: Paul Meissner, A219 Technology Bldg, Nat'l Bureau of Stds, Washington, DC 20234. Tel: (301) 921-3427

DEC 5-7—IEEE Internat'l Electron Devices Meeting, Washington Hilton Hotel, Washington, DC. INFORMATION: Susan Hinman, Courtesy Assoc, 1629 K St, NW, Washington, DC 20006. Tel: (202) 296-8100

DEC 5-7—Nat'l Telecommunications Conf (NTC), Marriott Hotel, Los Angeles, Calif. INFORMATION: NTC '77, PO Box 1250, Pasadena, CA 91109. Tel: (213) 354-2759

DEC 5-7—Winter Simulation Conf, Nat'l Bureau of Stds, Gaithersburg, Md. INFORMATION: Paul F. Roth, B250 Technology Bldg, Nat'l Bureau of Stds, Washington, DC 20234. Tel: (301) 921-3545

DEC 6-8—Mini/Micro Computer Conf, Anaheim Conv Ctr, Anaheim, Calif. INFORMATION: Robert D. Rankin, 5544 E LaPalma Ave, Anaheim, CA 92807. Tel: (714) 528-2400

DEC 15—Computer Networks Sym, Gaithersburg, Md. INFORMATION: Computer Networks, PO Box 639, Silver Spring, MD 20901. Tel: (301) 439-7007

JAN 19-21—U.S./Southeast Asia Telecommunications Conf, Singapore. INFORMATION: John Sodolski, Electronic Industries Assoc, Communications Div, Washington, DC 20006. Tel: (202) 457-4934

JAN 24-26—Reliability and Maintainability, Biltmore, Los Angeles, Calif. INFORMATION: D. F. Barber, PO Box 1401, Branch PO, Griffiss AFB, NY 13441

FEB 7-10—World Fair for Tech Exchange, Georgia World Congress Ctr, Atlanta, Ga. INFORMATION: Dr Dvorkovitz & Associates, PO Box 1748, Ormond Beach, FL 32074. Tel: (904) 677-7033

FEB 13-15—Aerospace and Electronic Systems Winter Conv (WINCON), Los Angeles, Calif. INFORMATION: Max Weiss, Aerospace Corp, PO Box 92957, Los Angeles, CA 90009. Tel: (213) 648-5000

FEB 15-17—IEEE Internat'l Solid-State Circuits Conf (ISSCC), San Francisco Hilton, San Francisco, Calif. INFORMATION: Lewis Winner, 152 W 42nd St, New York, NY 10036. Tel: (212) 279-3125

FEB 21-23—Datacom '78, Sheraton Park Hotel, Washington, DC. INFORMATION: Ed Bride, The Conference Co, 60 Austin St, Newtonville, MA 02160. Tel: (617) 964-4550

FEB 28-MAR 2—COMPCON Spring '78, San Francisco, Calif. INFORMATION: COMPCON Spring '78, PO Box 639, Silver Spring, MD 20901. Tel: (301) 439-7007

MAR 1-3—Control of Power Systems Conf and Exposition, Lincoln Plaza Hotel, Oklahoma City, Okla. INFORMATION: Dr M. E. Council, OG & E Prof, School of Electrical Engineering and Computing Sciences, U of Oklahoma, Norman, OK 73019. Tel: (405) 325-4721

MAR 5-8—TAPPI Internat'l Pulp and Paper Industry Exhibit, Conrad Hilton Hotel, Chicago, Ill. INFORMATION: Wayne Gross, c/o TAPPI, 1 Dunwoody Pk, Atlanta, GA 30341. Tel: (404) 394-6130

MAR 14-17—Printemps Informatique, U.S. Trade Ctr, Paris, France. INFORMATION: Helen Burroughs, U.S. Dept of Commerce, Office of Internat'l Mktg, France/Benelux, Rm 6318, Washington, DC 20230. Tel: (202) 377-4941

MAR 20-22—Industrial Electronics Control Instrumentation (IECI) Conf, Sheraton Hotel, Philadelphia, Pa. INFORMATION: Dr S. J. Vahaviolos, Engineering Research Ctr, Western Electric, PO Box 900, Princeton, NJ 08540

MAR 22-24—Internat'l Topical Conf on the Physics of SiO_2 and Its Interfaces, IBM Thomas J. Watson Research Ctr, Yorktown Heights, NY. INFORMATION: Dr Sokrates T. Pantelides, Conf Chm, IBM Thomas J. Watson Research Ctr, PO Box 218, Yorktown Heights, NY 10598. Tel: (914) 945-3000, (914) 945-1207

MAY 9-12—Internat'l Magnetics (INTERMAG) Conf, Palazzo Dei Congressi, Florence, Italy. INFORMATION: E. Della Torre, Dept of Electrical Engineering, McMaster U, Hamilton, Ontario L8S4L7, Canada

SEMINARS

NOV 21-22 and DEC 12-13—Data Communications: Advanced Concepts and Systems; DEC 7-9—Data Communications: An Introduction to Concepts and Systems; DEC 12-13—Minicomputers and Microcomputers: Selection and Usage Guidelines, San Francisco, Calif; New York, NY; and Washington, DC. INFORMATION: Peggy Quinn, Datapro Research Corp, 1805 Underwood Blvd, Delran, NJ 08075. Tel: (609) 764-0100, (800) 257-9406

JAN 30-FEB 1—Automated Testing For Electronics Manufacturing, Los Angeles Marriott, Los Angeles, Calif. INFORMATION: Sheila Goggin, ATE Seminar/Exhibit Coordinator, 167 Corey Rd, Brookline, MA 02146. Tel: (617) 232-2668

FEB 2-3—4th Joint College Curricula Workshop in Computer Science & Engineering, Orlando, Fla. INFORMATION: Dr David Rine, Info Science Program, Western Ill U, Macomb, IL 61455

SHORT COURSES

NOV 21-23, NOV 28-DEC 2, and DEC 14-16—Data Comm Systems and Networks; Structured Programming; and Minicomputers, Microcomputers, and Microprocessors for Non-Electrical Engineers, George Washington U, Washington, DC. INFORMATION: Martha Augustin, Continuing Engineering Education, George Washington U, Washington, DC 20052. Tel: (202) 676-6106

NOV 28-DEC 1 and DEC 12-15—Microprocessor Training Courses, San Jose, Calif. INFORMATION: John Hatch, Fairchild Camera and Instrument Corp, Instrumentation and Systems Group, 1725 Technology Dr, San Jose, CA 95110. Tel: (415) 962-3617

NOV 28-DEC 2, DEC 6-8, DEC 12-16, JAN 3-5—Hands-On Microprocessor Short Courses with Free Take-Home Microcomputer, and Workshop, Boston, Mass; Detroit, Mich; Chicago, Ill; and Mayaguez, Puerto Rico. INFORMATION: Jerilyn Williams, Wintek Corp, 902 N 9th St, Lafayette, IN 47904. Tel: (317) 742-6802

DEC 5-9—Design and Prediction of Sonar Systems, The Royal Inn of Point Loma, 4875 N Harbor Dr, San Diego, Calif. INFORMATION: Continuing Engineering Education Program, George Washington U, Washington, DC 20052. Tel: (202) 676-6106, or (800) 424-9773

INTRODUCING THE BENDIX PORTABLE MODULE TESTER

Now automatic, on-the-spot module testing is on the way.

Here's a new way to test anything from a printed circuit board to a complex logic system. And you can do it on the job.

Our new portable unit weighs just 30 pounds and has no moving parts. Yet it does everything that stationary digital cabinet-type units can. It eliminates downtime while modules are tested away from the job site. Does away with trial-and-error testing and unwarranted returns, too.

You can take it on board planes or ships, to hospitals, to labs, to computers or communications equipment, and to sophisticated quality-control operations in mass production plants.

Highly trained operators are not needed. Programming procedures are so easy to pick up. And an interactive display system makes operation easier still. Test systems are stored on solid-state cards, providing reusable data memory.

The Basic Bendix unit is capable of testing cards to 64 pins and has the capacity to expand to 256. Additional options are available including:

- Fault Isolation Testing
- Digital Voltmeter/Frequency Counter
- Teletype Interface and Advanced Software Aids.

For more information, contact: Bendix Corporation, Test Systems Division, Teterboro, N.J. 07608. Or call (201) 288-2000, extension 1789.

Bendix

CIRCLE 6 ON INQUIRY CARD



"Talk about

OPEN



Meet the new leader

Talk about prices... It's still 1973

An example: Our Model B5-3 was $24.95 in 1973. Four years later, during a period when "across-the-board" price increases were routine, **Power-One's Model B5-3 is still $24.95!** The same is true with practically all of our standard models.

Amazingly, Power-One open frames were price competitive in '73. Think what they are today.

Talk about variety... Heinz 57, Power-One 83

We've not only outdistanced our competitors, we've even dethroned Heinz as the king of variety.

Power-One's 83 different models easily represent the broadest selection of open frame power supplies in the industry. And these are "off-the-shelf" standards — ready for delivery. Ready when you need them.

Talk about shipments... Over 250,000 to date

Power-One shipped its first open frame power supply in May, 1973. We've now crossed the quarter-million mark. Over 100,000 units were delivered last year alone. That makes Power-One the largest producer of open frame power supplies in the world.

What does this mean to you? Only that a great number of individuals and companies have found continuing and complete satisfaction in our products.

We think you will, too.

FRAMES



Talk about facilities... 60,000 square feet of open frames

Our recent move to the largest complex dedicated solely to the manufacture of open frames has been geared to a single objective — that of making the best product of its kind even better.

Through proprietary production techniques, combined with the finest, most modern equipment available today, our new, enlarged facilities will enable us to continue to hold down costs . . . while ever improving quality, delivery, and service.

So next time you're in the area, stop by. See for yourself who we are, what we are, and most important, why we're the world's largest manufacturer of open frame power supplies.

Talk about reliability... We burn them in so they don't burn out

Every single unit that bears the Power-One label undergoes a full functional test, followed by a minimum 2-hour burn-in plus a final full functional test. We repeat . . . **every single unit!**

We consider this tough burn-in testing one of the key factors in our company's growth. We know of no other company that conducts more than a single operational test on their standard production-line units. Consequently, we know of no other open frames that match up to Power-One's for long life and overall reliability.

Talk about catalogs... Get our new '78 edition now

It's all new, and all inclusive. Complete specifications on every standard model, along with dimensional mounting drawings, product photos and descriptions, prices and ordering information.

Even customs and modified standards are covered.

So please, don't delay. Get your free copy now. Circle the reader's service number or, for faster delivery, phone us direct or send in the completed coupon.

RUSH me a copy of your new '78 edition catalog.

Name _____

Title _____

Company _____

Address _____

City _____ State _____

Zip _____ Phone _____

"Think about

Power-One INC.

D.C. POWER SUPPLIES

Power One Drive, Camarillo, California 93010 • Phone: (805) 484-2806 • TWX: 910-336-1297

CIRCLE 7 ON INQUIRY CARD



The LSI-11 microcomputer is really getting the plastics business rolling.

There's a new computerized extrusion process control system for plastic sheet and film that improves material uniformity by up to 75%. It also decreases usage of expensive resins by up to 10%, while automatically maintaining close produce tolerances. Yet it's one of the most effective extruder control systems you can buy.

It's called the Measurex 2000/25.

And it's run by an LSI-11—the highest performance, most software-supported microcomputer you can buy.

For Measurex Project Manager Dave Stepner, anything less than the LSI-11 simply wouldn't have been enough.

"We were looking to develop the most cost effective, full state-of-the-art system on the market," says Dave. "With the LSI-11, we got the computer power and 16-bit accuracy we needed, plus packaging flexibility."

What Dave Stepner liked most about the LSI-11 compared to other microcomputers, was its full 16-bit accuracy and hardware floating point option. "We have to do a great deal of high speed, accurate calculations to support our sensors and control algorithms. The LSI-11's 16-bit word length and floating point arithmetic let us accomplish this and not sacrifice response or performance."

The people at Measurex were also looking for real flexibility and expandability in their system. "Thanks to the LSI-11's capability, we were able to design a distributed architecture which links up to eight dedicated Measurex 2000/25 control stations, each with its own LSI-11, to a central intelligent data terminal for management reporting. And because of the LSI-11's low cost and single-board packaging, we can provide customers with a spare computer on site."

Dr. Dave Stepner,
2000/25 Project Manager, Measurex Corp., Cupertino, CA.

Dave Stepner concludes: "The LSI-11 really has everything going for it. The instruction set allows for very efficient coding—the technology has been tested and proven—and, of course, Digital has a mass production and delivery capability well matched to our needs."

Why not do like Measurex's Dave Stepner and get in touch.

We'll show you how the LSI-11 can get your business rolling too.

(For 900 pages of solid technical information, plus our new brochure of microcomputer case histories, "Why Anything Less than the LSI-11 Wasn't Enough for Me," just call toll free 800-225-9220 (in Mass. 617-481-7400 ext. 5144), or write Digital Equipment Corporation, One Iron Way, Marlborough, Massachusetts 01752.)

digital
COMPONENTS
GROUP

CIRCLE 8 ON INQUIRY CARD

LETTERS TO THE EDITOR

To the Editor:

On page 120 of the July 1977 issue of *Computer Design* (Microprocessor/ Computer Data Stack), the article on the Relational Memory Systems microprocessor development system . . . refers to the machine as "the only available alternative to the Zilog ICE on the market." This is definitely not so.

The Tektronix 8002 μProcessor Lab offers full support for the Z-80 including in-circuit emulation, (as well as for) . . . the 8080, the 6800, and the 16-bit TMS 9900. This disc-operating-system-based unit offers full development capability including program input and editing, program assembly, in-circuit emulation, both software and hardware debugging capability, and built-in p/ROM programming capability. A second system, the 8001, is offered for those interested in in-circuit emulation only.

Joseph G. McCarthy
Tektronix, Inc
Beaverton, Ore

To the Editor:

The article ("Solving Mass-Produced ROM Programming Problems With Base Registers," pp 99-105) by John A. Carroll in the August issue of *Computer Design* was very interesting. It suggested that the addition of base registers to a microcomputer's instruction set architecture would permit the use of mass produced ROMs for many commonly used software modules. The article made a number of valid points which I have not seen previously discussed in the literature, most significant being that the motivation for his architecture suggestions was the desire to encourage the use of low cost, mass produced ROM modules.

In our business, which includes the design and manufacture of digital microcomputers for the aerospace market based on bit slice microprocessors, the use of ROM memory can be very beneficial. Not only is it low cost (if mass produced in volume), but it is very reliable, low power, very modular (unlike core), and highly resistant to corruption by radiation.

Consequently, we have given considerable thought to the characteristics of computer architecture which facilitate the use of ROM and which make ROM modules reusable for several applications. This interaction is largely ignored in the literature and therefore in the design of microcomputer architectures, so we welcome the treatment provided by Mr. Carroll.

Since we have come to similar conclusions in designing a standard instruction set for our aerospace computer products, your readers might find the following comments a useful extension and clarification of his article.

(1) His attempt to facilitate the generation of code which need not be modified when it is moved, or relocated, in memory is referred to as the generation of "position independent code" in the more formal computer science literature. It is possible to find technical articles on techniques for generation of position independent code whose motivation is invariably the implementation of dynamic relocation in read/write memory (eg, for a timesharing system) rather than the implementation of position-independent ROM modules. The fact that these two problems are equivalent is important to realize.

(2) A powerful technique for the generation of position independent code was not mentioned in the article. This involves the use of the program counter (PC) as an address modifier or base register. If all jump addresses within the ROM module are computed relative to the PC (ie, using the PC as a base register), they become inherently position-independent without requiring the dedication of a hardware base register. In our SKC family of computers, all short jump instructions are executed relative to the PC in part for this reason.

(3) Another way to employ the PC as a base register is via the implementation of instructions with an Immediate Operand capability. That is, the operand for the instruction immediately follows the instruction in (ROM) memory. As a result, it is usually not necessary to set up a region of (ROM) memory for local constant data. The use of a local constant region would have implied the use of another hardware base register. In our new SKC3121 computer, all memory reference instructions have an immediate operand option for this reason.

(4) The link table mentioned in Mr. Carroll's article is a very useful ingredient in designing a modular program in ROM. However, for maximum utility, the jump instruction set must be tailored to facilitate the use of the link table. For example, an indirect subroutine jump instruction was implemented in our standard aerospace instruction set specifically to facilitate the use of a link table for intermodule communication. Without this facility, inefficiency would be introduced in transfers between modules via the link table.

In short, the use of base registers for operand address modification was only the first step in the synthesis of an instruction set architecture which was well suited to the widespread use of ROM for aerospace applications. We hope the issue receives continued treatment in the literature. Perhaps Mr. Carroll's article will serve as a catalyst toward that end.

Austin J. Maher
The Singer Co
Kearfott Div
Wayne, NJ

Letters to the Editor should be addressed:

Editor, Computer Design
11 Goldsmith St
Littleton, MA 01460

Have it your way.

Bit by bit our Standard Modular Memory lets you make every word count.

The Standard.
768K x 16 in one 5¼ x 19 inch chassis.

Need more?
You can address up to *eight* of our MSC 2601 Standard Modular Memory units for up to 6144K x 16.

Want it your way?
Our field-proven MSC 2601 uses dynamic 16K RAM elements. You can organize each card 16K x 1 to 64K x 9. Multiple cards give you almost any word and bit size you want.

Any way you like it.
Up to 14,155,776 bits in one MSC 2601.



MSC – 2601

When you like it.
Access time up to 350 nsec. Cycle time as fast as 450 nsec.

Together in the rack.
RETMA rackmountable or freestanding. Self-contained with power supplies and forced air cooling. Battery backup available, too, for nonvolatile storage.

And for another way.
If you want 4K RAM our static or dynamic versions will let you have your way with up to 192K words.

Our way.
We use fewer components and low power for high reliability. Multiple source, full specification components tested, assembled and then systems tested under worst case operating conditions.

The MSC 2601, Standard Modular Memory... We set the standard.

Visit us in Booth 121-123 Mini-Micro 77 December 6-8 Anaheim, CA

Monolithic Systems corp.
14 Inverness Drive East
Englewood, CO 80110
303/770-7400
© 1977 Monolithic Systems Corp.

by John E. Buckley
Telecommunications Management Corp
Cornwells Heights, Pa.

Office Automation

The field of office automation is rapidly evolving toward the merger of data processing and telephone communications systems. Identified by such nomenclature as office of the future, computerized office, paperless office, and word processing, the basic concept addresses the ability to collect fragmented source data within an office environment and to build centralized data files for demand retrieval or subsequent data processing. While the data processing capability has been viable for several years, the constraint has been data communications capabilities and, particularly, economies.

Ironically, most larger offices have had both data processing and telecommunications resources for some time. These two areas, however, have functioned in isolated and limited environments. Until recently, the telephone system as a means of passive communications could at best function as the network access vehicle between data origination locations (ie, individual telephone extensions) and a centralized data processing system. Introduction of computerized telephone systems (CBXs) changed the telephone system's role to that of an active data control device.

Examination of this emerging area of office automation makes it possible to speculate on the probable applications and requirements that can be expected to become commonplace over the next few years. The concept of management information systems (MIS) has been constantly defined and redefined to offer a timely definition that suits changing applications. However, an examination of the economics involved in primary data source collection has shown the limitations of these MIS applications. For example, a basic application of employee time reporting could ideally be accomplished by installing a data terminal at each employee's desk. Employee and project identification could then be entered each time activities on the project are begun and ended. The value of collecting such data is self-evident; timely and accurate project cost accounting, prompt client or customer billing, and employee efficiency and effectiveness tracking, among others, are obtained. The cost, however, of such a distributed data entry system has been impractical, resulting in the preservation of manually prepared time reports, which are manually collected, sent to a centralized data preparation location, converted to computer-compatible form, and then processed by computer.

Due to the tediousness of the steps to be performed, time reporting is at best a weekly event, producing data reports that lag the actual activities by two or more weeks. With a standard pushbutton telephone set, the CBX collects source data from the primary source as it occurs, requiring the employee to enter minimum data. The project number (entered by the employee) and extension number, date, and time (automatically controlled) are stored on a peripheral disc subsystem. Upon termination of a project, the CBX accesses the stored data, and prepares and stores a complete elapsed time record for later retrieval.

It should not be misinterpreted that the CBX is going to replace the traditional data processing center. Rather than compete with an existing data processing facility, the CBX will complement the data applications to be processed on existing computer equipment. At the present time the necessary basic components of the CBX exist and are operational for automatic incremental data collection and dissemination. The availability of new tools and techniques, together with the rethinking of basic premises of present office data flow techniques must be utilized in order to conceive a system that will meet future applications.

The CBX is not a telephone system controlled by a programmable computer; it is a computer system, similar to traditional message switching systems, that can switch digitized voice bytes to specified addresses. The conceptual development of office automation applications must be formulated with this in mind. Admittedly, the primary addressing function of a CBX is the number the call originator has entered to be called, which usually is another telephone extension on the CBX or an outside trunk to the public telephone network. While the actual data to be switched is analog voice, the digitization of that voice signal coupled with time division multiplex switching completes the parallel between this and the message switching systems.

CBX systems are capable of decoding multifrequency signals generated by a pushbutton telephone set. These same types of signals can also be generated and received by such interactive terminals as keyboard/CRT or keyboard/printer terminals. Outputs from a CBX that are presently intended for trunk circuits to the public telephone network can also be used to interface to disc subsystems, mini or microcomputer systems, and data processing centers. Based on the data content entered from a pushbutton telephone or interactive data terminal, the CBX can select the proper output of the subsequent data entries. The actual processing of the data content can be performed prior to its delivery, so that the CBX, in effect, is functioning as an input/output processor within a data application.

Primary value of the CBX in an office automation environment is not to duplicate existing functions, but rather to provide added dimensions of incremental data



Cost efficiency you can put your finger on . . . CORTRON® SOLID STATE KEYBOARDS

Get your hands on a CORTRON Solid State Keyboard, and you'll soon find out why you can't judge all keyboards on initial price alone.

It's after installation that cost efficiency becomes most important. In life expectancy, ability to endure extreme environments, high speed operation without "misses," accuracy, downtime caused by beverage spillages, reliability, serviceability and human engineered features. That's where a CORTRON Solid State Keyboard really pays off.



Unique contactless key switch makes the difference. Utilizing ferrite core switching technology, the CORTRON Key Switch is mechanically simple (only 4 basic parts!) and has an ultra reliable 100 million cycle life test rating. CORTRON Keyboard Professionals can translate what this can mean to you in cost efficiency terms of MTBF (mean time before failure). CORTRON has actual customer experience of MTBF in excess of 40,000 hours.

They'll also explain other advantages you'll gain over competitive technologies such as Hall effect, reed switch, and capacitive switching. All in all, you'll find the CORTRON Key Switch offers unusual built-in protection against costly service calls and the hardship of downtime.

"Human engineered" keytops and key placement options give CORTRON low profile alpha numeric keyboards the familiar "typewriter feel" that promotes operator productivity and efficiency.

Nothing left to chance. CORTRON solid state keyboard materials, components, subassemblies, and final assembly are 100% inspected and tested to assure your specifications are met with plenty of room to spare.

These are just a few of the cost efficiency benefits CORTRON offers you and your customers.

Cost efficiency you can put your finger on. For a greater insight into the cost efficiencies attainable with a CORTRON Solid State Keyboard, write or call for details: CORTRON, A Division of Illinois Tool Works Inc., 6601 West Irving Park Road, Chicago, Illinois 60634. Phone (312) 282-4040. TWX 910-221-0275.

CORTRON
A DIVISION OF ILLINOIS TOOL WORKS INC

THE KEYBOARD PROFESSIONALS

CIRCLE 10 ON INQUIRY CARD

Hewlett-Packard brings a bright new look to low-cost graphics.



Auto-Plot



Zoom



Area shading



Rubber-band line



Typical application: scientific plotting



Typical application: process flow diagram

The new Hewlett-Packard Graphics Terminal uses a microprocessor and raster scan technology to combine high performance with low cost.

The HP 2648A introduces a whole range of bright ideas to graphics. There's so much power built into the terminal itself that you can perform everything from auto-plots to zoom without any CPU help at all.

Auto-Plot. You don't need to know programming or invest in costly software. Once you've entered your facts and figures from the alphanumeric keyboard, press a few keys and your tabular data is plotted instantly.

Raster Scan. No more pulling down the blind to make your plots visible. Our display is clear and easy to read even in bright light. And the raster scan technology permits selective erase, cutting down the time it takes to modify your picture also.

Zoom and Pan. This lets you magnify any area of the display up to 16 times. And you can pan in any direction for closeup investigation of complex designs, without having to reinitialize the data.

Area Shading and Pattern Definition. This makes it easy to distinguish areas with similar shapes, such as bar charts, mechanical parts and architectural drawings.

Rubber-band Line. You can draw trial sketches, such as architectural floor plans, with or without CPU connection. Think of the time and money you'll save by cutting down mistakes.

Independent Display Memories. Both alphanumeric and graphic data can be shown independently or at the same time. And you can carry on a dialogue with the CPU without disturbing the picture.

The HP 2648A also has all the advantages of our popular HP 2645A alphanumeric terminal. Specifically: mass-storage on 110K byte cartridges (you can store graphics as well as data); 'soft keys' to speed up repetitive jobs; one-button self-test; plug-in PC boards for easy maintenance; extensive data communication and off-line capabilities.

This bright new look in graphic terminals is designed for such applications as electrical, mechanical and architectural design. For process and control. For scientific plots. And for business planning.

We'd like to give you a graphic demonstration of everything the HP 2648A can do. Send us the coupon and we'll set it up. Or contact the nearest Hewlett-Packard sales office listed in the White Pages. We're sure you'll get the picture.

HEWLETT hp PACKARD

Yes, I'd like to take a closer look at your low-cost HP 2648A Graphics Terminal.

☐ Contact me to arrange a demonstration. ☐ Send me complete information.

Name

Company Phone

Address

City/State/Zip

Mail to: Ed Hayes, Marketing Manager, Hewlett-Packard Data Terminals Division, 19400 Homestead Road, Dept. 1207, Cupertino CA 95014.

42703HPT4

CIRCLE 11 ON INQUIRY CARD



Real-time problems? Systems has timely solutions.

Systems Engineering Laboratories has dedicated its 16 year corporate life to solving challenging real-time problems. The experience gained in solving these problems is what led us to pioneer the development of true 32-bit computer systems.

Look into the operating systems, the languages, the data base system, the real-time device handlers and terminal systems, and you will see that we build for the real-time environment. That's our business.

Choose from a well-bred family of computing systems: The SEL 32/35, the SEL 32/55, or the SEL 32/75. Unlike other so-called "32-bit minis" that are only bridge-the-gap systems developed from essentially 16-bit architecture, all SEL 32 systems are true 32-bit machines. This results in richer instruction sets, more precision in data representation and larger, directly-addressable memory. All are available with throughput rates in excess of 26 million bytes/second.

Systems computers fit the term "minicomputer" in price alone. If your application is performance-sensitive, we'll save you money. If you're budget-sensitive, we'll give you more performance for your dollar.

The SEL 32/35 can be configured from 64K bytes to 512K bytes of 900 nsec memory. Resembling its more powerful brothers, the SEL 32/35 is a complete package, including control processor with floating-point arithmetic, memory, chassis, power supplies and cabinet.

The SEL 32/55 is offered in a variety of both single and multiple CPU configurations, with from 32K bytes to 1 million bytes of 600 nsec memory.

The SEL 32/75, with up to 16 million bytes of main memory, has a concept so new, we had to coin a special term to describe one of its main features: Regional Processing Units. Working independently, these RPU's contain sufficient control and buffer storage areas to process an I/O region and transfer the resultant data directly to main memory. Computer system throughput is further enhanced by High-Speed Floating- Point Hardware and Writeable Control Storage.

Just circle our number on the Reader Service Card, or call us today. We'll send you the powerful story of the SEL 32 family.

SYSTEMS
ENGINEERING LABORATORIES

☐ CALL ME
☐ SEND ME MORE INFORMATION
☐ I HAVE PRESENT NEED FOR SYSTEM
NAME _____
COMPANY _____
PHONE _____
ADDRESS _____
CITY _____
STATE _____ ZIP _____

SYSTEMS Engineering Laboratories
6901 West Sunrise Boulevard, Fort Lauderdale, Florida 33313
(305) 587 2900

CIRCLE 12 ON INQUIRY CARD

(Engineers)

SAN DIEGO OPENINGS

The Electronics Division of General Dynamics, located in one of the most beautiful cities in the country, has a number of truly unusual career opportunities for qualified candidates. We are one of the nation's fastest growing electronics companies involved in three principal product lines: universal automatic test equipment, position location systems including tracking and flight test monitoring activities, and data acquisition and processing systems such as the highly successful oceanographic, navigational and environmental buoys.

MECHANICAL ENGINEERS
(Electronic Packaging)

Successful candidates will be involved in the conceptual design and fabrication of diverse electronic medium density packages in the following work areas:

- **Automatic Test Equipment for the F-16**
- **Airborne Radar Systems**
- **Ground Display Systems**
- **Advanced Systems**

Work in these areas involves diversified experience with a minimum BSME educational background.

Excellent benefit program, including Life and Medical Insurance, Dental and Prescription Drug Plan, Savings/Stock Investment and Retirement Plans.

Qualified applicants should submit their resumes, including recent salary history, in complete confidence, to:

GENERAL DYNAMICS
Electronics Division
Drawer 11EP
9078 Clairemont Mesa Blvd.
San Diego, CA 92123

An Equal Opportunity Employer M/F

collection and dissemination on a real-time basis. This aspect is further enhanced since many of these envisioned applications would utilize standard pushbutton telephone sets for data input.

This telephone set also could be used as an audio output device if the CBX is equipped with a voice answer-back peripheral. In a retrieval application an authorized department manager can ask for the total time accumulated on a specific project. The CBX searches the data file for the project number, accumulates the total, and transmits it to the manager by means of the audio response unit.

Through the use of specialized telephone sets, more automated data collection and coordination applications can be implemented. In a manufacturing production environment, existing card dialer pushbutton telephones (also used to make normal phone calls) can be effective data input terminals; an electronic assembly application could have such telephones at the parts receiving and testing area. When a shipment of electronic components are received, a dialing card for the parts lot number can be prepared and read into the CBX, with the quantity entered by the employee. Following receiving inspection and test, the card is again read and the employee enters the accepted quantity. When components are transferred from parts inventory to assembly, the application cards identify the part lots and an assembly card can be prepared and entered for this assembly lot. The assembly personnel would enter the card when actual assembly was initiated and completed. At manufacturing quality control, the same card would be entered along with the quantity of accepted assembly units. The compilation of these incremental source data inputs results in a comprehensive and dynamic manufacturing reporting and inventory system, and an effective employee performance tracking system.

The office automation possibilities of a CBX considered as a computer system that switches audio calls are extensive. Specialized systems are already marketed for office environmental control; the CBX, however, could receive input from environmental transducers connected in lieu of telephone instruments. In another case, access and personnel sensors in a building could track movements throughout the building during nonworking hours; when programmed thresholds or conditions are detected, security personnel are notified or certain specified areas are secured.

The CBX has been a viable system in the marketplace for only two years, with initial growth focusing exclusively on voice telephone applications. With the continued addition of specialized or traditional data terminals, the CBX can become an office automation system.

The operating telephone companies of the Bell Telephone System currently are one of the largest vendors of computerized telephone systems. Under the Consent Decree in force from the federal government on AT&T, as well as the Computer Communications ruling from the FCC, AT&T is prohibited from providing such office automation applications. As the realization of these CBX capabilities becomes evident to potential users, the demand for such applications may stimulate AT&T to try to reverse or modify their present legal and regulatory restrictions. The outcome of negotiations and compromises that would be necessary to achieve this objective, combined with the introduction of computerized telephone systems for more advanced requirements, can be expected to radically change the present telecommunications and data processing environments.

CIRCLE 13 ON INQUIRY CARD

Get Smart.

ADDS *Regent* · Smart for the price of Dumb.

Time was, if a man bought a Dumb terminal, he was considered pretty smart. Times change.

ADDS Regent family of Smart terminals is making Dumb look dumb.

For under $1000 our Regent 100 has features no smart man can resist. You get cursor controls for operational simplicity and extensive remote commands that make it easy to control the Regent from the computer. Optional function keys customize Regent to your specific application.*

You get a Status Line that provides current information on the terminal's operating status. And you get visual highlights such as blinking, zero intensity, half intensity, underline and reverse video.

You also get self diagnostics.

In other words, you get Smart. Or Smarter: Our Regent 200 has everything our 100 has plus buffered transmission, auxiliary port and editing options.

You can't get a whole lot more.

Get Smart. Get ADDS.

Quality, Reliability and Integrity. It all adds up to ADDS.

*In moderate quantity.

ADDS *Applied Digital Data Systems Inc.*
100 Marcus Blvd., Hauppauge, New York 11787 516-231-5400 Dept. 250

Name _____

Firm _____ *Title* _____

Address _____

City _____ *State* _____

Phone _____

CIRCLE 14 ON INQUIRY CARD

Are you rushing into microprocessor-based development with old friends?



You have a new friend.

You don't have to pay a big name price for a universal product development lab. And, don't let your fondness for a certain chip lead you to a convenient but confining marriage. The inevitable divorce will be costly and time consuming. If you want to develop products happily hereafter, move in with Futuredata.

Futuredata systems are universal.

We can move you into multiple-microprocessor-based product development at half the cost. With the largest selection of powerful hardware, software and economical peripherals around. With high speed disk or low cost tape operating systems. With in-circuit emulators for 8080, 6800, and Z-80. With the universal microcomputer that tackles every job.

Only Futuredata can move you in for $3850.*

No other microcomputer can match the cost/performance standards set by our MICROSYSTEM/20 & 30 disk-based systems and our MICROSYSTEM/10 & 15 tape-based systems. Each of these are complete development systems with up to 56K memory, 960 character CRT, ASCII keyboard, two RS-232 serial ports, 8-bit parallel I/O, real-time clock, bootstrap in PROM, 8-level vectored interrupts and complete disk and tape operating systems with monitor, debugger, editor, assembler and utility.

*Domestic U.S.A. prices

The most complete spectrum of economical systems.

Move in with our Dual 5″ Mini Floppy Disk System, our Dual 8″ Standard Floppy Disk System, our unique QUICKRUN™ 32K Tape Operating System or our new Universal Dual Development System. No matter which you choose, the savings will be significant.

Only Futuredata has QUICKRUN.™

MICROSYSTEM/15 has the only co-resident assembly and interactive debugging system in the industry. With editor, assembler and debugger/monitor all in memory, things happen fast. Assembly of a 1000 statement program takes a mere 15 seconds. At $5275,* it's the most cost-effective development tool around.

Now the first Universal Dual Development System.

Futuredata has combined two separate memory/processor systems in one host computer. Mix or match processors, disk or tape operating systems in each half. Put two development engineers to work at full speed, simultaneously. You get two complete systems in one and save nearly $2000.



In-circuit emulation and higher-level language.

We have in-circuit MICROEMULATORS™ for 8080, 6800, Z-80, Extended BASIC, line printers, EPROM programmers, hardware, software, documentation and a rock-solid record for reliability. So, let's be friends!



30-day "Get Acquainted" offer.

Try one of our development systems for 30 days at no risk. For more information, write or call Futuredata today.

Move into product development with a new friend...

futuredata

FUTUREDATA COMPUTER CORPORATION • 11205 S. LA CIENEGA BLVD. • LOS ANGELES, CA 90045 • (213) 641-7700 • TWX 910-328-7202

SEE US AT MINI/MICRO '77, BOOTH #608.

CIRCLE 15 ON INQUIRY CARD

Automated Switching Expedites Data Transfers On All Types of Networks

For multicomputer data networks, the Multitran M3000 series digital network management switch system permits operators of asynchronous terminals to selectively access diverse computer resources. These resources may be application or speed dependent ports on a single computer, or multiple computers located at a single facility or in widely dispersed locations.

The device's function is to dynamically switch data between two channels at high speed with almost no delay. Maximum configuration of an asynchronous switch accommodates a bandwidth of about 60k char/s.

Installed by Computer Transmission Corp, El Segundo, CA 90245 in several applications, the switch replaced telephone data network systems that were so congested that voice communications became degraded. The unit, containing the company's Directran® data set, a modem located at the terminal and at the switch, frees the telephone system for voice grade transmission.

Circle 400 on Inquiry Card

Wideband Communications Are Predicted to Impact Leisure and Business

Communications satellites and fiber optic technologies will soon be combined to provide universal, inexpensive, wideband communications which will change people's working and leisure lives, according to the "Impact of Wideband Communications" report available from International Resource Development Inc, 125 Elm St, New Canaan, CT 06840. While previously too expensive for all but major communications users, a proliferation of wideband telecommunications will have a major effect on the economics of teleconferencing, electronic mail, and data communications.

These effects are expected to be reflected in some substitution of teleconferencing for airline travel, some changes in the way paper is used for business correspondence and forms, and development of new types of office equipment.

Circle 401 on Inquiry Card

Tremendous Increase In Facsimile Use Is Forecast

Increased communications speed, lower equipment and line costs, versatility, interfaces to other systems, and postal service cost increases are



the factors which are most likely to place facsimile technology into many offices during the next few years, and conceivably into the home. Predicting these developments, Dal Berry, president of Graphic Systems, Inc, Corporate Dr, Commerce Park, Danbury, CT 06810 foresees interfaces between facsimile units and copiers for faster and cheaper distribution. Data compression transmission techniques and communications networks using satellites and fiber optic cables will play a significant role in reducing communications costs.

Future information processing networks must be able to handle communications in the forms of words, numbers, voice, and graphics; facsimile can handle more of these than any other technology. As the number of compatible facsimile units increases, the emphasis will shift from intra to intercompany communication. According to Quantum Science Corp, facsimile shipments are expected to reach $700M by 1980.

U.S. Packet Network Implements Standard X.25 Interface

Synchronous data communications service for computers and other programmable devices equipped with a standard X.25 interface is being implemented in the U.S. by Telenet Communications Corp, 1050 17th St, NW, Washington, DC 20036. The added capability for users of the company's public packet network and other compatible packet networks worldwide permit a computer to handle up to 4095 logical connections simultaneously over a single network access line. Each connection is switchable on demand and individually flow-controlled, so that devices of dissimilar speeds can communicate without loss of data or congestion.

The service will be made available in Boston, Chicago, Dallas, Los Angeles, New York, San Francisco, and Washington, DC. By the first quarter of 1978 a total of 22 cities should be included. International expansion is also being planned.

Agreement Upgrades and Expands Switching System

A five-year agreement signed by Collins Commercial Telecommunications Group of Rockwell International, Dallas, TX 75207 and Securities Industry Automation Corp (SIAC) provides expansion and upgrading of SIAC's existing Rockwell-Collins front end/message switching system. Two separate 2-processor C-Systems front-ending a Univac host processor, manufactured by the Collins Communications Switching Systems Div in Dallas, are to be installed to form the Automated Bonds System and Common Message Switch at SIAC's computer center in New York City. □



Count on GA to put COBOL and FORTRAN into microcomputing.

The software used in the thousands of GA minicomputers throughout the world is standard on the GA 220 Microcomputer. With GA you use the same software across our family of micro, mini and multiprocessor systems.

1. **The richest μC program generation tools:** ANSI-74 COBOL, with SORT, FORTRAN IV, COMFORT, BASIC, and Macro Assembler.
2. **The only μC with a wide choice of operating systems:** CONTROL I/II/ and III, RTOS, RTX, DBOS, and FSOS provide flexible and adaptable support for both OEM and end-user applications.
3. **The only μC with a full ISAM file management system:** for creating and manipulating data bases.

We're counting on GA to:

☐ Rush full details on GA 220, the most fully supported μC today.

☐ Contact us for immediate requirements.

Name_____

Title_____

Phone_____ Ext._____

Clip coupon to company letterhead and send to General Automation, 1055 South East Street, Anaheim, CA 92805. Or call (714) 778-4800.
General Automation Europe:
51 Aachen, Postfach 465, West Germany.
Tel: 02405-641. Telex: 841-832-9500.

7-CD

GENERAL AUTOMATION

CIRCLE 16 ON INQUIRY CARD



Our new mini/micro computer printers... "the easy ones."

Features:

- Three popular ASCII input configurations
- Forty characters per line
- Internal data storage
- Double-width character selection
- Power line filter
- Optional tally-roll and/or fast paper feed

EASY TO INTERFACE

The new DP-1000 Series Printer family fits right into most mini-micro computer and modem applications – thanks to three popular ASCII formats available in four different basic models.

Standard Baud rates from 110 to 2400 Baud, and internal storage of up to 104 characters (more optionally) with "hand-shake" control signals, let you pick from a variety of off-the-shelf configurations to fit your specific application.

EASY TO USE

A time-proven, dot matrix impact printing element can print 64 alpha-numeric and special symbols in 40 characters/line at 50 CPS on single or multiple-copy paper rolls. Options such as Tally Roll take-up and Fast Paper Feed, make the printers easy to fit point-of-sale and related fields.

Combining form and function, the modern package blends with virtually any surroundings, while its flip-top design allows convenient access for paper replacement and servicing.

EASY ON BUDGETS

Best of all, single-unit prices for the DP-1000 Series start at under $700, with substantial Dealer and OEM quantity discounts.

Want to see a demonstration in your office, or more details? That's easy too. Just contact Ken Mathews at Anadex; 9825 DeSoto Avenue; Chatsworth, CA 91311; Telephone (213) 998-8010; TWX 910-494-2761.

Anadex

"See us at Mini/Micro Show, Booth 307."

16-Bit Minicomputer Addresses 256k Bytes, Has Mainframe Features

Model 8/16E processor, a 16-bit computer system capable of addressing 256k bytes of semiconductor memory, provides performance capabilities and economy. Suited for use in scientific computation, process control, and data communications, the systems include an enhanced OS/16 MT2 operating system and extended FORTRAN IV software packages.

The 8/16E processor was designed by Interdata, Inc, a unit of Perkin-Elmer Data Systems, 2 Crescent Pl, Oceanport, NJ 07757, to provide big machine features such as 16 general-purpose registers, an IBM-like instruction set, list processing instructions, dual I/O bus architecture, and 255 automatic I/O channels. Integral memory management hardware permits up to 256k bytes of memory to be addressed. Available in 32k-byte increments, memory has an 275-ns access time and a 750-ns cycle time.

Processor architecture, similar to that of the 360/370 line, includes 16 general-purpose registers which reduce overhead, cut execution time, and simplify program development. Supervisor mode when enabled causes I/O and most status switching instructions to become privileged instructions.

Integral memory mapping hardware permits expansion of physical memory from 64k bytes to 256k bytes. Program mapping is performed by implementing additional bits in the program status word. Load program status, load program status register, set map, and set map register instructions control these additional bits, and also serve to minimize the associated overhead incurred by user programs.

Selected blocks of memory can be allocated as write protected, read/write protected, or instruction execution protected through the memory protect controller. Memory can be partitioned into a maximum of 64 blocks with individual protection for each block. The controller also provides two loadable maps for data security and integrity.

In the 156-instruction set are several classes intended to increase memory utilization efficiency. The set provides both 16- and 32-bit formats and permits operation between two general registers; or between a general register and a memory location, a 16-bit data constant carried in the primary instruction word, or a 4-bit data constant.

Dual bus structure of the I/O system permits high speed devices to operate at a maximum of 2,666,-000 bytes/s over the optional extended memory selector channel. Operation of selector or multiplexer channel can be 8 or 16 bits parallel. Either channel operates on a request-response basis for reliable device controller design.

OS/16 MT2 is a real-time, multitasking operating system which provides an event-driven environment for user application programs. It manages system resources, including access to the processor, with up to 255 levels of priority defined by the user. In addition, it provides intertask communication and control facilities, including task common and reentrant libraries, which allow users to create structured event-driven systems such as those needed by transaction processing systems.

Extended FORTRAN IV enables users to access the power of processors efficiently and with a minimum of systems resources. Operating in as little as 21k-bytes memory, the compiler directly generates object code, minimizing program development time, effort, and cost. Exceeding requirements of ANSI standard (X3.9 —1966) FORTRAN, the software provides extensions such as mixed mode arithmetic, ENCODE/DECODE, and Integer *2. A special Reentrant Runtime Library results in greater speed, and accuracy which is better than five decimal digits for REAL function and better than 14 decimal digits for double-precision function.

Circle 410 on Inquiry Card

Fiber-Optic Kit Allows Engineering Evaluation of Complete Interconnection System

A fiber-optic evaluation kit, designed by systems engineers familiar with applications requiring complete TTL electronics, offers a complete interconnect system, rather than connectors only. The system, designed

Fiber-optic evaluation kit developed by Augat provides a complete interconnection system which allows engineers to evaluate the technology for applications requiring TTL electronics

for OEM use as well as laboratory experimentation, allows engineering evaluation of fiber-optic interconnection. It operates from dc to 5M bits/s over the 0 to 55°C temperature range without drifts or inadvertent comparator switching.

The kit, developed by Augat, Inc, Interconnection Products Div, 33 Perry Ave, PO Box 779, Attleboro, MA 02703, contains emitter assembly, 5-m fiber-optic cable assembly, temperature referenced photodetector assembly, TTL-compatible preamplifier and TTL-compatible emitter driver. A second kit is available without preamplifier and driver for applications not requiring the electronics package. Both include a comprehensive application engineering instruction manual containing circuit diagrams for operation to 5M bits/s digital or 10 MHz analog.

Emitter transforms electrical signals to light signals through an IR-emitting diode. It has an 880-nm spectral peak and exhibits rise and fall times of <50 ns when driven with ICs or transistors. Detector transforms light signal to electrical through photodiode. Spectral response of the detector closely matches that of the emitter for maximum system efficiency. Rise and fall times of the detector are <35 ns when properly biased and loaded by receiver circuitry described in the instruction manual. Interconnection of the emitter and detector assemblies is accomplished with a 5-m fiber-optic cable—a 180-fiber bundle with 0.045" (0.114-cm) bundle diameter, jacketed with black Hytrel® for strength and crush resistance.

Emitter driver provides a complete TTL-compatible fiber-optic



Cipher 900X
125 ips
Evaluation units Dec. '77
Production units Mar. '78

Cipher 900X
75 ips
Evaluation units Oct. '77
(call and schedule yours now!)
Production units Jan. '78

Cipher delivers a quiet blow to the competition.

Quiet as a whisper, the 75 and 125 ips Cipher vacuum tape transports simply obsolete every other vacuum drive on the market today.

By design and construction, the Cipher 900X vacuum tape drives are simply the best, most reliable tape transports on the market today. Bar none.

It starts with complete microprocessor control of all of the transport's functions, including complete self-test/diagnostics and a full measure of protection for the tape and an extraordinary reduction of maintenance problems.

In conjunction with our switched linear servo electronics, the microprocessor maintains total servo control during critical load and unload or power fail sequences. It's the smoothest tape handling you've ever seen; there is no possibility of tape damage even if a power failure should occur during high speed rewind.

Power wise. The Cipher 900X series is the lowest power user of all vacuum tape transports. Averaging 300 to 350 Watts with a worst case 450 Watts Continuous Power Dissipation, the 900X series uses roughly half the 650 to over 1,000 Watts used by other vacuum tape transports.

You won't believe the quiet. Thanks to the Cipher 900X's multistage low speed vacuum pump, we use a much smaller motor. At 3400 rpms, our motor is substantially quieter than the competition's 10,000 rpm motors. A whisper instead of a high-pitched whine. And we've reduced more than noise. We've also knocked out 50% of the maintenance requirements found in traditional vacuum tape drives by eliminating belt drives.

No relays. Because the Cipher 900X incorporates opto-isolators to drive the blower motor and switch the high voltage AC components at the zero crossing line, transient generated line RFI is minimized. Power usage is drastically reduced. So is maintenance.

No incandescents. Light Emitting Diodes are used in place of incandescents in the 900X. With the field-proven reliability of solid state electronics, the unpredictable behavior of incandescents is eliminated.

Improved tape path. Only the long life sapphire cleaner and the chrome head (guaranteed for 5,000 working hours) come in contact with the tape. Air entering the tape path is filtered and the tape path itself is under a low positive pressure to prevent accidental ingestion of particular contaminants. No guesswork loading, since servos and transducers under control of the microprocessor automatically feed the column during load and unload. Servo controlled shutdown power fails protect the tape since, in the event of a brown out or failure, energy stored in the servos is utilized to effect a controlled power down.



Easiest to maintain and repair. Our exclusive Optical Sensing File Protect replaces troublesome switches, solenoids and trouble-prone mechanisms. And because the Cipher 900X has internally generated sequences of diagnostic and alignment tests, the MTTR is cut a good 30% by immediately locating the problem area. All mechanical and electronic assemblies in the 900X are modular. No special tools or fixtures are required; all critical tolerances are machined in.

The only thing missing are the problems: No belts, no hoses, no relays, no solenoids, no incandescents, no cooling fans, no power surges, no contaminants, no noise problems, no maintenance problems, no special tools or fixtures, no false EOT/BOT detection, no tape problems—no load snap, no whip, no shredding, no special precautions, no guesswork, and best of all—no price premium. None.

With design simplicity and the use of advanced solid state electronic components, the Cipher 900X series provides unparalleled performance, reliability and serviceability. At low cost. And quietly, too.

For further information and specifications, contact Cipher Data Products, 5630 Kearny Mesa Road, San Diego, California 92111. Headquarters: (714) 279-6550. TWX: 910-335-1251. Eastern Region: (617) 449-3182. Central Region: (312) 296-7250. Or contact your Cipher representative.

See us at Mini/Micro'77 Booth #501/502

Cipher Data Products

CIRCLE 17 ON INQUIRY CARD



Detector in Augat's fiber-optic kit has rise and fall times of <35 ns when biased and loaded using receiver circuitry such as that illustrated

transmitter when used with the emitter assembly, a 5-V power supply, and an optional filter capacitor. Preamplifier provides a complete TTL-compatible fiber-optic receiver when used with the detector assembly, trim pot, and power supply. Both driver and preamplifier are contained in a 24-pin DIP.

All connectors utilize a waveguide beyond cutoff design and are of gold-plated brass construction to ensure retention of the integrity of shielded enclosures. Teflon sockets and low-profile, right-angle brackets are included for PC board, chassis, panel, or bulkhead mounting and connection of the emitter and detector assemblies.

Other standard accessories (not in kit) include cable splice for inline or bulkhead use, O-ring set for hermetically sealing emitter and detector assemblies, and fiber-optic cables of various standard lengths. Kit 698-OK-001 (without electronics) is priced at $99.50 in any quantity; 698-OK-002 (with preamp and driver) sells for $190 in any quantity.

Circle 411 on Inquiry Card

Printer/Printer Terminal uProcessor Controlled For Optimum Throughput

First members of a family of 180-char/s dot matrix serial printers, introduced by Hewlett-Packard Co, 1507 Page Mill Rd, Palo Alto, CA 94304, are the 2631A printer and 2635A printing terminal. Operating under control of an sos microprocessor, both units offer as standard three different ways to print, fast replacement cartridge ribbon, automatic underlining, and smart bidirectional printing.

Bidirectional printing path is controlled by a "smart printing" algorithm. Leading and trailing spaces are detected and ignored; the head moves directly to the next material to be printed. Looking ahead in the data stream, the printer detects spaces imbedded within a line; when 10 or more spaces are found, the printhead speeds to the next printable character at an accelerated 45-in (114-cm)/s rate. Horizontal tabs, a standard feature on both units, also initiate this fast movement. With throughput thus optimized, apparent print rate often exceeds nominal specifications.

There are three standard print modes: normal, expanded, and compressed. In normal mode, 10 char/in (4/cm), 136 columns can be printed on 14" (36-cm) paper. A 5-char/in (2/cm) expanded mode is useful for bold face and highlighting. In compressed mode, 136 columns can be printed on 8.5" (21.6-cm) paper, or 227 columns on 14" (36-cm) paper. Underlining can be simultaneous with printing, and characters may be overstruck. A display functions feature causes control functions to be printed; this is a useful tool for program development.

Vertical line spacing is variable under program control; choices are 1, 2, 3, 4, 6, 8, or 12 lines/in (12 lines/in is used to print subscripts and superscripts). A switch on the 2631A can select 6 or 8 lines/in; any choice may be made via the keyboard on the 2635A.

The long-life printhead needs no alignment, and is therefore easily replaced by the user. The ribbon, good for more than 10M char, is contained in an easily replaced cartridge. Self-test can be initiated by the operator or by a program, to verify proper operation. Standard equipment is the USASCII 128-char set. Each character is formed by dots in a matrix of seven columns and nine rows. Both units can accommodate one additional 128-char set.

Standard interface for the 2631A is an 8-bit differential line driver configuration compatible with the company's line printers. The 2635A features an EIA RS-232-C interface as std. Optional interfaces include EIA RS-232-C with 202-type modem control, and current loop; for the 2631A, HP-IB and 8-bit TTL parallel are also offered.

The microprocessor in both products is a company-designed 16-bit silicon-on-sapphire (sos) device designed specifically to provide a broad

FOR RENT...

the truly universal PROM Programmers from Data I/O that enable you to program any of the more than 200 PROMs now available.

A single Data I/O programmer—the Model V or Model IX—can be used to program every single commercially available PROM.

Data I/O programmers are universal. You can use them to program any PROM, and more than 200 PROMs are currently available. This means you don't have to get a separate programmer to accommodate different PROMs. With either the Model V or Model IX and the appropriate personality card, you can program any PROM or its second source equivalent. Moreover, one personality module can be used to program all PROMs within a generic family and keep your yield at the maximum.

ROM emulation and editing capabilities are built-in, making software development a breeze and virtually eliminating PROM waste.

All the Data I/O programmers save lab time and slash your development expense. These are portable, rugged, human-engineered and easy to use units. They're ideal for field service. Both the Model V and Model IX offer a direct display readout of PROM or RAM data at any address and offer unlimited data editing capabilities. Operation is totally automatic, and you can enter data manually through the keyboard or load it automatically from a preprogrammed master PROM. There are built-in error checking routines to insure accurate and correct data transfers, and serial or parallel I/O are standard. These unique PROM programmers and their personality cards are available now.

Rental Electronics, Inc.
Another of the AMERICAL companies

More than 11,642 electronic instruments... off-the-shelf, throughout North America.

☐ Tell me more about the Data I/O PROM Programmers now!
Call me at_____

☐ Send me your Equipment Sales Catalog—I might be interested in buying some of your great "previously owned" equipment on a money-back guarantee.

☐ I have a pressing need right now for the following:_____

Please phone me immediately at_____

☐ Send me a copy of your free illustrated Rental Catalog.

Name_____
Title_____
Company_____
Address_____
City_____
State_____ Zip_____
Phone No._____ Ext._____

GSA #GS-04S-21963 Neg
©1977 Rental Electronics, Inc.

Complete this coupon and return it today to the world's oldest and largest electronic equipment rental firm, REI, 19347 Londelius St., Northridge, California 91324

Anaheim, CA (714) 879-0561 • Mountain View, CA (415) 968-8845
Fort Lauderdale, FL (305) 771-3500 • Des Plaines, IL (312) 827-6670
Burlington, MA (617) 273-2770 • Gaithersburg, MD (301) 948-0620
Oakland, NJ (201) 337-3757 • Cleveland, OH (216) 442-8080
Dallas, TX (214) 661-8082 • Houston, TX (713) 780-7218
Seattle, WA (206) 641-6444 • Rexdale, Ontario, Canada (416) 675-7513
Montreal, Quebec, Canada (514) 681-9246 • Northridge, CA (213) 993-RENT (7368)

CIRCLE 18 ON INQUIRY CARD

range of I/O and program control capabilities and to optimize controller type applications.* A 34-mm² chip, containing approximately 9600 transistors, executes 34 basic classes of 16-bit instructions tailored for I/O processing. The instruction set allows direct access to 16 registers, eight of which are located in the processor chip itself.

Control capabilities are implemented via decision-making mechanisms such as computed branch and condition code interrogation. Also available are stacked subroutine linkages, direct addressing to 64k words of memory, indexed and indirect addressing modes, and immediate operands. At a worst case 150-ns minor cycle time, instruction speeds range from 0.6 to 1.8 μs with a mean of 1.05 μs.

The chip features fully static and synchronous operation with a single-phase clock. This eases system clock requirements, and aids testing and system debugging by allowing single minor cycling, or single instruction cycling. It can use a single 12-V power supply and dissipates 0.5 W at its full rated speed.

Separate asynchronous I/O and memory handshakes permit memory and I/O operating at different speeds to be mixed. Separation of data, address, and control buses simplifies decoding and increases bandwidth. Both data and address paths are 16-bit bidirectional 3-state buses, permitting simple, fast interface to the processor, thus minimizing system overhead.

Circle 412 on Inquiry Card

Image Display Device Produces 3-D Illusions From Computer Data

An image display device that may bring improved accuracy to air traffic control, mapping of underground ore deposits, and analysis of data from medical scanners has been developed at the University of Utah, Salt Lake City, UT 84112. The 3-D virtual image display device, developed by the Advanced Imaging Methods Laboratory, uses a special optical system and a television screen to produce a realistic 3-D illusion. Such an image can be created from any type of data that can be fed into a computer, including 3-dimensional graphs, brain scanner images, X-rays, maps, and drawings.



Prototype image display system at University of Utah creates realistic 3-D illusions by projecting onto a television screen a series of 2-dimensional images formed from computer stored data. Special optical system spreads the images behind the screen to achieve 3-D illusion

"The special optical system takes a series of 2-dimensional images stored in the computer, and projects them, one behind another using a television screen," says Dr Steven A. Johnson, research associate professor in bioengineering and associate consultant at the Mayo Clinic. "It does not require special glasses like the old 3-D movies, and several people can look at the image at the same time. A person can also move his head and see around the side of the image.

A laboratory prototype of the device, constructed by Johnson and Dr Brent S. Baxter, assistant professor of radiology, has been used to display 3-D images of X-ray brain scans and simple geometric forms. With this device, the scientists hope to be able to view a 3-D image of the contents of the skull which will emphasize lesions and other highlighted structures. This would not only provide advantages in diagnosis, but would give the surgeon a better feel for the location and size of the problem he is trying to correct.

If the prototype achieves the kind of results that are expected, the scientists plan to design a second one which will connect directly with the scanner's computer memory. Although it is now possible to produce only black and white images, there is no reason that color images cannot be achieved.

Circle 413 on Inquiry Card

8080-Based Controller Supports Terminal Cluster Plus Communications

Offering the computing power of larger systems, the SPD 15/25 cluster controller has a price/performance ratio that is acceptable to smaller installations. Incoterm Corp, 65 Walnut St, Wellesley Hills, MA 02181 accomplished this by basing the terminal processing unit on the industry standard 8080A microprocessor.

The SPD 15/25 is a programmable controller for attaching display terminal clusters and online communication to a central computer. Its terminal processing unit (TPU) operates compatibly with the communications protocol of a variety of mainframe computers; it can support up to two 1920-char displays or four 960-char displays, as well as a full line of printers. Multiplexing TPUs enables them to share a single modem and provide extra display positions if required.

In addition to a fully programmable interrupt system, arithmetic/logical processor, and a real-time clock in the controller, the internal TPU has a refresh subsystem with 4k bytes of directly addressable RAM for screen data. A controller can contain up to 64k bytes of addressable memory made up of RAM, EPROM, or core.

A built-in communication controller operates in full- or half-duplex mode with synchronous or asynchronous protocols at speeds from 75 to 9600 bits/s. Support for all standard

*For a more complete technical description of the microprocessor, see "A CMOS/SOS 16-Bit Parallel μCPU," Lam-Giang Dang, et al, *Proceedings of the 1977 IEEE International Solid-State Circuits Conf*, pp 134, 135, 245.

For Tally insert, circle 130 on Inquiry Card→

TALLY 1200 BAUD PRINTER TERMINAL

Key into Tally. . . the most flexible printer

EVERYTHING YOU COULD ASK FOR IN A PRINTER TERMINAL

The Tally T-1612—loaded with functions and features, yet simple enough for anyone to master. Your operator will like Tally best. Here's why. It's quiet. Easy to operate. And very flexible. You can load control functions from your user program or directly from the keyboard. In fact, you get 42 operator programmable keyboard functions. Even unique ones like double width character printing. With Tally, you can mix and mingle 6 different type fonts by simple keyboard programming. And, of course, Tally superb print quality is a built-in bonus.

Boasting a 1 k buffer to sustain a full 1200 Baud printing rate, the T-1612 communicates comfortably at 300, 600, 1200, 2400, 4800 or 9600 Baud. Available in KSR or RO versions, use the Tally T-1612 for both communications and interactive computer console applications. The unit is fully compatible with all major time sharing services.

Convenience. The T-1612 is very operator friendly. And very quiet to the ear. For format programming or interactive communications, your front panel and keyboard controls are clearly labeled and easily accessible. With push button convenience you can select a vast variety of functions or operating modes. The machine can be as simple or as versatile as your needs dictate.

In keeping with easy operation, even forms handling duties are selectable through the keyboard. Select the appropriate keys and set up horizontal tab, vertical tab, top of form, forms length, top and bottom margin, and right and left margin.

Optimized operation. The T-1612 printer terminal is smart, too. Tally uses microprocessor electronics to deliver optimum printer throughput and cut down wasted motion. For bonus throughput, printing is bi-directional. The print head always looks ahead for the shortest path to the next print position. While searching, the head moves at an accelerated rate. This "optimized bi-directional" printing doubles or triples throughput over the printer's rated 160 characters per second without taxing the print head. So important for keeping pace with higher Baud rates.

Outstanding short line capability



HERE'S WHAT YOU GET WITH TALLY

Tabletop or pedestal mount.
160 cps bi-directional optimized printing.
300, 600, 1200, 4800, 9600 Baud operation.
Full-duplex or half-duplex.
ETX, EOT or Reverse Channel HDX protocols.
XON/XOFF FDX protocol.
Up to 218 columns (16.5 cpi).
128 ASCII character set.
ANSI keyboard with multi-key rollover.
Self-test.
Parity selection.
Paperout switch.
EIA interface.
1 k of buffer.
Automatic new line.
Automatic line feed.
20 character answerback.

OPTIONAL FEATURES

Bottom paper feed.
Alternate character set.
14 key numeric pad.
TTL interface.
20 ma/60 ma current loop interface.
75/1200, 150/1200 split Baud rates.
2 k or 4 k buffer.
APL code.

EASY TO USE, EASY TO LIKE

The Tally printer terminal has all the functions you want for optimum interactive data communications. The highly versatile keyboard uses a standard ANSI pattern for typewriter-like operation. A 14 key numeric pad adjacent to the standard keyboard is optional.

POWERFUL YET SIMPLE

Lots of features. Tally has the multi-key rollover feature if two keys are struck simultaneously. And 20 character answerback capability. (The message is stored in memory, and can be reprogrammed from the keyboard.) The standard printer terminal offers a full 128 ASCII code set. For the reduced set of 70 codes for compatibility with other ASCII equipment, simply set the All Caps locking key.

Other standard T-1612 features include end of line warning when keying data and automatic paperout detection. A convenience feature you'll appreciate is the view key for a clear look at the last characters printed.

Options you'll like include alternate character set and a programmable configuration that returns the printer to a specified condition upon power up.

Forms flexible. The Tally printer terminal is easy to like when it comes to forms handling. The flip-up tractor assembly affords easy access to the sprocket wheels for paper loading. Dual tractors are used to hold the paper securely for precise print registration. And the tractors adjust from either end of the carriage to accommodate various width forms from 4 inches to 15 inches. Up to six-part forms can be printed. Forms thickness control is standard. Optionally, the bottom load feature allows paper to enter the printer from either the bottom or back of the machine. Additionally, for clean, fast, and easy ribbon changing, the printer terminal offers a convenient snap-in cartridge. A large, easy to read column indicator is standard. At a glance, you quickly see the exact column you are on.

terminal that you can lay your hands on..

A HANDY CONTROL PANEL

For operator convenience, numerous control functions are located on the front face of the printer for easy accessibility. Also, the critical communications controls have been moved off the keyboard onto the front panel to avoid an erroneous key strike causing lost data. Functions controlled by this panel include power, Baud rate selection, local or off-line operation, half- or full-duplex, automatic line feed, automatic new line and paperout detection.

With the automatic new line (ANL) feature, a line feed is automatically performed when the print head reaches the right margin. This prevents data loss when the data input format does not match the printer format. The automatic line feed (ALF) function, when depressed, creates a line feed whenever the carriage return on the main keyboard is struck or a carriage return is received on the communications line.

PUSH BUTTON CONVENIENCE

Unlike many terminals, the half-duplex switch is not just a "local copy" switch. It indicates to the microprocessor whether or not it should respond to line turnaround indicators.

The two Baud rate switches allow any of three Baud rates to be selected. 300, 1200, or (if both switches are in the out position) 600 to 9600 as selected on a rotary switch on the rear of the printer.

The power light indicates the application of AC power. The XMIT light indicates that clear to send (CB) is high and informs the operator that his input can be transmitted.

The paperout light indicates that the terminal is out of paper or that a test mode is in process.

MORE FUNCTIONS, MORE FEATURES



CONTROL PANEL



Tally T-1612 Printer Terminal

EIA/CCITT INTERFACE

The Tally T-1612 features a standard EIA RS-232 C/CCITT recommendation V.24 serial interface. A nine-foot cable terminated with a standard 25-pin EIA connector is supplied. Pin connections are listed below.

Pin No.	EIA Circuit Designations	Circuit Descriptions
2	BA	Transmitted Data
3	BB	Received Data
4	CA	Request to Send
5	CB	Clear to Send
6	CC	Data Set Ready
8	CF	Rec. Line Signal Det (RLSD)
19	SCA	Sec. Request to Send
20	CD	Data Terminal Ready
22	CE	Ring Indicator
12	SCF	Speed Indicator (212 Series) Secondary RLSD (202 Series)
1	AA	Protective Ground
7	AB	Signal Ground

PARITY

Even parity or odd parity, with or without parity error printout can be selected by the user.

Serial Interface Timing Diagram



SPECIFICATIONS

SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.

OPERATION

Print speed
160 characters per second bi-directional optimized
Vertical slew
8.5 inches per second
Single line advance
50 ms
Full carriage return
350 ms

PRINTING FORMAT

Number of columns
132 (programmable for 80 column format)
Character set
96 character USASCII
Character style
Dot matrix, 7 × 7 half-space
Character size
0.080″ wide × 0.106″ high
Line spacing
6 and 8 lines per inch
Characters per inch
10, 12 and 16.5 cpi
Double width character
Standard

ELECTRICAL

Power
200 watts
Line voltages
105-140 VAC, 60 Hz±2%
90-110 VAC, 50 Hz±2%
187-264 VAC, 50 Hz±2%

PHYSICAL

Width
25.5″
Height
8.5″
Depth
27″
Weight
68.5 lb.

FORMS CONTROL

Feed mechanism
Sprocket feed adjustable from 4″ to 15″
Paper out
Audio alarm sounds 3″ from bottom of form

FORMS SPECIFICATIONS

Type
Continuous fanfold, edge perforated
Width
Variable from 4″ to 15″
Copies
Original plus five
Weight
15 lb. single part, 12 lb. with 7 lb. carbon multipart
Thickness
0.003″ to 0.020″

ENVIRONMENTAL

Operating temperature
50 to 100°F (10 to 38°C)
Operating humidity
10 to 90% RH noncondensing

NOISE LEVEL

55 dBa

COMMUNICATIONS

Code
USASCII
Bit structure
300 to 9600 Baud. 1 start 7 data, 1 parity, 1 stop
Parity structure
Input and output parity. Odd, even and no parity. A received character with incorrect parity will cause a specific character to be printed.

HOW TO ORDER

The Tally T-1612 brings unmatched price/performance to your interactive printing needs. Tally printers are renowned for reliability, simplicity and low cost of ownership. Tally's own nationwide field service organization with resident offices throughout the United States provides back-up support for every installation. Worldwide service is available through Tally subsidiaries and distributors.

Call the Tally sales office nearest you for any assistance you require.

TALLY

TALLY CORPORATION
CORPORATE HEADQUARTERS
8301 South 180th Street
Kent, Washington 98031
Telephone: 206-251-5500
Telex: 320-200
Cable Address: Tally, Seattle, WA

TALLY LIMITED, Reading, England, (0734) 580 141
TALLY GmbH, Frankfurt, Germany, 0611-417191
TALLY GESmbH, Vienna, Austria, (0 22 2) 67 26 47
TALLY ITALIA SRL, Milano, Italy, (02) 404-5546
TALLY ITALIA, Roma, Italy, (06) 8103391
TALLY S.a.r.l., Chatou, France, 913.58.27

OEM SALES OFFICES
Boston (617) 272-8070
New York (516) 694-8444
Chicago (312) 325-9788
Los Angeles (213) 378-0805
Miami (305) 665-5751
San Jose (408) 247-0897
Seattle, (206) 251-6730
San Antonio (512) 733-8153
Washington, D.C. (703) 471-1145
Business Systems (415) 254-8350

T005 10/77

LITHO IN USA

PUT A CHANGE OF PACE

IN YOUR PRINTOUT

THE TALLY PRINTER TERMINAL

HAS SIX DIFFERENT

CHARACTER CONFIGURATIONS TO SAVE PAPER

OR DRESS UP YOUR FORMS

BY ENHANCING READABILITY

10, 12, AND 16.5 CHARACTER PER INCH SPACING

IS OPERATOR PROGRAMABLE THROUGH THE KEYBOARD. AND EACH CPI

FORMAT CAN BE SELECTED TO PRINT DOUBLE WIDTH!!

WITH CONDENSED PRINTING, YOU CAN GET 132 COLUMNS ON NARROW PAPER AND 218 COLUMNS ON STANDARD PAPER.

ACTUAL PRINTOUT HAS BEEN REPRODUCED TO SHOW YOU THE POSSIBILITIES--

AND TO POINT OUT TALLY'S OUTSTANDING PRINT QUALITY

A 7X7 HALF SPACE MATRIX FONT DELIVERS CLEAN, CRISP CHARACTERS WITH

HIGH LEGIBILITY FOR

EASY READABILITY.

THE PRINTER FEATURES DUAL TRACTOR ENGAGEMENT ABOVE AND BELOW

THE PRINT LINE TO HOLD THE PAPER PRECISELY IN PLACE AND DELIVER

FAST PAPER ADVANCEMENT. REGISTRATION NEVER WAVERS.

TALLY
TALLY
TALLY
TALLY
TALLY
TALLY

WITH SO MUCH FLEXIBILITY AT YOUR FINGERTIPS, ITS EASY TO SEE

THAT YOUR BEST BUY IS THE TALLY T-1612 PRINTER TERMINAL.

.42 keyboard programmable functions!

KEYBOARD PROGRAMMING

Via the keyboard, the operator can select 42 distinct control functions. Also, since the printer can be formatted by incoming data, the operator is not required to make any set-ups on the printer. However, the operator can change the format at any time from the keyboard.

Following is a complete listing of the available functions.

42 Programmable Functions

Formatting.
- Set horizontal tab wherever print head is positioned.
- Set horizontal tabs by address.
- Clear all horizontal tabs.
- Clear a single horizontal tab.
- Set vertical tab wherever form is positioned.
- Set vertical tabs by address.
- Clear all vertical tabs.
- Clear a single vertical tab.
- Set left margin.
- Set right margin.
- Set form length.
- Set top margin by address.
- Set bottom margin by address.
- Set top margin on line where form is positioned.
- Set bottom margin on line where form is positioned.
- Clear bottom of form skip.
- Set LED indicator to show vertical line number.
- Set LED indicator to show horizontal column number.
- Select 6 lines per inch.
- Select 8 lines per inch.
- Select 10 characters per inch.
- Select 12 characters per inch.
- Select 16.5 characters per inch.
- Select standard sized characters.
- Select double width characters.

I/O functions.
- Select local mode.
- Select modem mode.
- Select EOT, ETX or CR line turnaround protocol.
- Select DELETE as a pad character.
- Select DELETE as print buffer erase.
- Enter XON/XOFF.
- Exit XON/XOFF.
- Reprogram HERE IS message.
- Erase the data buffer.
- Select attended operation.
- Select unattended operation.

Special functions.
- Select keyboard control.
- Select keyboard and host control.
- Select Special Self-Test mode.
- Select Self-Test mode.
- Clear existing format and reset printer to factory set condition.
- Set customer programmed configuration.

APPLICATIONS ADAPTABLE

AS FLEXIBLE OR AS SIMPLE AS YOU NEED

READY TO PLUG IN

For communications compatibility with your system, you can choose from three serial interface configurations—EIA, TTL or 20/60 ma current loop. The printer terminal comes ready to interface to other RS-232 equipped serial devices for local operation or with modem data sets for data communications. The EIA interface is compatible with CCITT recommendation V.24. It is compatible with 103, 113, 202 and 212A Bell modems and the Vadic 3400 modem. The current loop option is a simple internal change-out cable assembly. No special tools are required.

Parity selection is switch controlled by the operator. Optional 75/1200 and 150/1200 split Baud rates are available.

Half-duplex protocols can be selected by the user to operate EOT, ETX or Reverse Channel.



communications line codes is provided, including ASCII, EBCDIC, and Baudot. The controller also provides 15 levels of priority interrupts and interfaces to control various peripheral devices.

Circle 414 on Inquiry Card

Disc-Based Systems Added to Commercial Minicomputer Line

Three additional models in the DS 990 family of disc-based minicomputer systems offer extensive file management capabilities that support multiple interactive users in a multilanguage environment. Based on the model 990/10 processor and the enhanced DX10 operating system, Texas Instruments Inc, Digital Systems Div, PO Box 1444, Houston, TX 77001 has emphasized systems-level design and support in the models 4, 6, and 8.

Model 4 serves as a small multistation full-function software development system or a medium-scale application system. It includes a 128k-byte processor, 1920-char model 911 video display terminal, 5M-byte fixed disc, and 5M-byte removable cartridge disc drive. Model 6, which offers more disc capability for larger data base applications, includes 128k-byte processor, 911 terminal, and two 25M-byte removable pack disc drives. Model 8 accommodates even larger data bases with two 50M-byte disc drives.

The systems offer software support and utilities for business applications, including COBOL, Sort/Merge, BASIC, and Business BASIC. FORTRAN IV with ISA extension is also available. The DX10 operating system contains file management features including multikey indexed file support. Software development facilities include a macroassembler, interactive source editor, and overlay supported link editor.

Standard options for the system include additional memory up to 2048k bytes, and additional 911 terminals and disc drives as well as diskette units. Model 810 impact printer, 2230 and 2260 printers, 979A 9-track magnetic tape drive, and communications options are also available.

Circle 415 on Inquiry Card

try ours!

If you've been buying keyboards with field replaceable reeds from Spokane, you'll be happy to know that they are also available in Minneapolis! Just ask for the Maxi-Switch 2900 Series.

These keyboards feature rear-mounted reeds, field modifiable switch functions, and optional encoding formats. Modular reed switch construction simplifies assembly of both standard and custom switch and keyboard arrays, and the hermetically sealed contacts are design proven at over 100 million operations, under load.

Maxi-Switch 2900 Series keyboards are already hard at work in process control equipment, data communication systems, computer and data entry terminals, point of sale/electronic cash registers, digital scales, and other demanding applications.

Get your hands on a Maxi-Switch 2900 Series keyboard. Try it out in your environment and under your conditions, and evaluate the specifications in terms of your needs. We know you'll be pleased with the results, and pleasantly surprised at our quantity prices.

You'll find that we work hard at good customer relations, just as we do at keyboard design. If you're looking for a company that tries its best to do business on your schedule, we're both in luck. Call or write the factory, or contact your local Maxi-Switch representative (you'll find him in EEM). We'll put a 2900 Series keyboard in front of you as fast as we can. Try us!

THE Maxi-SWITCH CO.

9697 EAST RIVER ROAD • MINNEAPOLIS, MINNESOTA 55433

(612) 755-7660

TWX 910-576-2690

CIRCLE 4 ON INQUIRY CARD

We looked at all the things you hate about cassettes.

And threw them out.





The remarkably simple MFE cassette drives make cassettes a viable, reliable storage medium.

Those innocent-looking little pieces of plastic and metal are responsible for just about all the problems you've come to expect from cassettes.

That's why we don't use them.

No finicky solenoids and clutches. No whirling pinch rollers, capstans, belts and pulleys.

MFE cassette drives have only two moving parts. Which means there's practically nothing to go wrong. The result is an impressive 15,000 hour MTBF.

Data Integrity. Our revolutionary tape transport system also greatly improves data integrity. Patented servo-controlled reel-to-reel tape handling results in a constant tape speed within ±1% and a low bit-to-bit jitter of ±3%.

We even include a RAW head as a standard feature. Because read-after-write checking is the best way to guarantee data integrity.

Here are a few more reasons MFE cassette drives will change your thinking about cassettes:

Widest speed range. Continuously variable tape speed from 2-120 ips.

Highest data transfer rate. Up to 32K bps ANSI/ECMA compatible.

More options. Both serial and parallel I/O.

Low power requirements. Only ±5V at 5W total power consumption.

We even have a model that's qualified for hostile environments. It operates at temperatures from −40°C to +70°C.

The MFE 250B cassette drive. If you hate cassettes because they're cranky and unreliable, you need another reason.

For details, contact MFE, Keewaydin Drive, Salem, New Hampshire 03079, Tel. 603-893-1921/TWX 710-366-1887/ TELEX 94-7477.

Europe: MFE Products SA, Vevey, Switzerland, Tel. 021 52.80.40/TELEX 26238.

MFE

CIRCLE 20 ON INQUIRY CARD

Modular Automatic Test Equipment System May Produce Savings

A modular automatic test equipment system (MATE) for use in maintenance of aircraft is expected to provide significant savings in equipment, maintenance, and operating costs. Requests for proposals for studies, analysis, and hardware for the system have been issued by the United States Air Force, Aeronautical Systems Div at Wright-Patterson AFB, Ohio.

The system, intended for use in future maintenance work with all types of aircraft, is the first development of automated test equipment to be independent of a specific aircraft. Currently, separate test equipment is developed and purchased for each aircraft at each level of maintenance—field, organizational, and depot.

Under the MATE program, interchangeable or modular parts (hardware and software) to a single system would be procurred. This one system would then be used to perform maintenance checks on all types of aircraft at any level of maintenance. The pieces used in assembling the system would depend on the aircraft and avionics system to be tested. Plans are to test radar, radio, inertial navigation, and electronic countermeasures equipment using the system.

System Reduces Cost of Building Models for Finite Element Analysis

A standalone finite element modeling system, FEM 181 promises to significantly reduce the cost of building models for finite element analysis by cutting the time required by up to 70% and eliminating timeshare costs. The integrated, interactive graphic system allows models to be created fast and accurately. Since models are created offline, host-computer timeshare costs are nonexistent. A universal bulk data formatter provides compatibility with existing analysis systems as well as proprietary analysis programs.

Tektronix, Inc, Information Display Group, PO Box 500, Beaverton, OR 97077 formulated the basic system with a 19" (48-cm) combination storage/refresh CRT display, terminal keyboard, 10M-byte disc unit, hardcopy unit, and finite element modeling software. An 11 x 11" (27.9 x 27.9-cm) tablet is optional.



Tektronix' FEM181 finite element modeling system includes 19" (48-cm) combination storage-refresh CRT display, terminal keyboard, 30 x 40" (76 x 101.6 cm) graphic tablet, disc memory, hardcopy unit, and finite element modeling software. Models created using this standalone system can be verified, formatted for analysis, and then transferred in bulk to the host analysis computer

Operating independently of the host computer, the system allows the structural analyst to create a model, verify its accuracy, and format the model data into a form compatible with the host analysis system's input requirements. Formatted data can then be transferred in bulk to the host computer.

Initial coordinate data can be entered from keyboard, graphic tablet, or down loaded from the host computer. A 30 x 40" (76 x 101-cm) graphic tablet is available, allowing nodes to be digitized directly from engineering drawings. The data loader module permits the data base for an existing model to be transferred from the host to disc memory, and then examined and edited with modeling system software.

The model is shown in three dimensions on the display screen as it is created. When defining node coordinates and elements, the analyst has virtually instantaneous interaction with the display. Copy commands in the system allow a model to be built quickly when only a few initial nodes have been defined.

Verification and inspection of the model is facilitated using system features which allow 3-dimensional rotations, erase and redisplay in a new orientation, and zoom in on specific sections. Z-plane clipping omits the front or rear portion of a model to eliminate confusion.

When an accurate model has been achieved, the bulk data formatter module is used to compile and format the node, element, and property data for processing by the host finite element analysis system in whatever card image format is required. Model data and other system data are then transferred in bulk to the host system for analysis.

Circle 416 on Inquiry Card

Mark Sense Cards Primary Input Medium for Instructional Computer

A compact batch-processing system that uses mark sense cards as its primary input medium to extend computer access to large numbers of students, MSB-11 (Mark Sense Batch-11) supports both BASIC and FORTRAN IV programming languages. The system is available from Digital Equipment Corp, Education Products Group, Maynard, MA 01754 at a cost approximately the same as a 5-user timesharing system.

The PDP-11/04 based system with 32k bytes of semiconductor memory and a dual floppy unit for program and data storage is housed in a 4-ft (1.2-m) high cabinet. Input/output devices include an 180-char/s line printer, LA36 DECwriter II console terminal, and the CMS-11K mark sense card reader.

The desktop 250-card/min reader enables the system to accept 40-col punched or marked cards coded in BASIC or FORTRAN IV. Programs are processed in a single batch stream and are stored on the 512k-byte disc unit, or are printed out on the LA180 matrix printer.

Price of the MSB-11 with a subset of the RT-11 operating system and the BASIC language is $21,460. With a minimum expansion, the system can be configured for scheduled use as either a timesharing or batch system.

Circle 417 on Inquiry Card



To make a complete line of pushbutton controls, you need more than pushbuttons.

Pushbuttons from MICRO SWITCH's AML (Advanced Manual Line) have always been attractive to designers. Because they look so good. And because they're so easy to mount and wire.

But now, the AML series is even more appealing. Because now there's a variety of rocker and paddle switches to choose from, including dual lamp and dual color. Which means now you can perform just about any function with a harmonious display. You don't have to compromise.

AML controls also look appealing to the people who have to do the wiring. All are designed with the same depth for single level termination, regardless of switch or terminal type.

There's easy snap-in mounting from the front, PC board mounting or subpanel mounting using individual, strip or matrix hardware.

Which means mounting is simpler. Wiring is simpler. Engineering time is reduced. And total installed cost is lower.

Plus, they offer solid state, electronic control or power switching in the same size housing. All AML devices are designed to meet international, UL and CSA standards.

Displays include split screen, hidden color, and a unique three-segment lens cap indicator. The choice of lamps includes T-1¾ wedge base, neon and LED.

AML has it all —pushbuttons, indicators, and now, paddles and rockers. But to see how good-looking AML really is, contact us for a personal demonstration.

MICRO SWITCH will provide you with field engineers for application assistance and a network of authorized distributors for local availability. Write us for details or call 815/235-6600.

MICRO SWITCH products are available worldwide through Honeywell International.

MICRO SWITCH
FREEPORT, ILLINOIS 61032
A DIVISION OF HONEYWELL



Circle 21 for data.

In 7 months, I placed 5000 foxes and owls in good homes.

– Jim Folts, Vice President, Terminals Division



Seven months ago, Perkin-Elmer introduced two new CRT terminals. The Model 1100, a very simple terminal that's dumb-like-a-fox for $907.* And the Model 1200, a smart editing terminal known as The Owl for $1383.*

Right away, the big wheels in the terminals business gave us plenty of encouragement. "Who needs another inexpensive CRT?" they said.

"Every OEM and system builder who knows true value," we said.

And, sure enough, smart OEMs and system builders ordered 5000 Perkin-Elmer terminals and really started sales rolling.

Now it's Pussycats.

But, that's only the beginning.

This month we're unleashing a new thermal printer called The Pussycat – a 100 cps CRT page printer that should make hard copy a lot more affordable and send our competition running for cover. Especially when they hear we're tooling up for thousands of Pussycats the first year. Turn the page for a closer look. Then call your nearest Perkin-Elmer Data Systems office.

And while you're at it, get more information on the rest of our menagerie. The Model 1100 Terminal that's dumb-like-a-fox and The Owl, our Model 1200 Editing Terminal.

Perkin-Elmer products. You'll become attached to them in no time.

*Quantity 75.

PERKIN-ELMER DATA SYSTEMS | TERMINALS DIVISION

Randolph Park West, Route 10 & Emery Avenue
Randolph, N.J. 07801 (201) 366-5550 TWX: 710-987-7913

Domestic, call:		Overseas, call:	
(617) 890-0557	Boston, MA	887-1000	New South Wales, Australia
(312) 437-3547	Chicago, IL	416-677-8990	Mississauga, Ontario, Canada
(214) 234-8880	Dallas, TX	539-2260	Paris, France
(714) 544-9093	Los Angeles, CA	753-34511	Slough, Berkshire, UK
(201) 229-4040	Oceanport, NJ	089-753081	Germany
(408) 249-5540	San Francisco, CA	2200949	Singapore
		031/450/160	Frolunda, Sweden

CIRCLE 22 ON INQUIRY CARD

Dumb like a Fox
The Owl
Dumb like a Fox
The Owl

Display Terminal Saves Time and Minimizes Text Processing Errors

A microprogrammed video display terminal, the Delta 4300E incorporates 4k-char memory and offers flexibility in manipulating data on the screen and in memory. Delta Data Systems Corp, Woodhaven Industrial Pk, Cornwells Heights, PA 19020 designed the terminal specifically to add convenience and minimize errors in text processing applications.

Text manipulation features include automatic word wrap, ragged right sentence and paragraph justification, and automatic justification of new insertions. Automatic search modes are search for word or word string, search and replace word or word string, search and replace upon request, and search and delete word or word string.

Operator errors are minimized by ability to move/copy/delete any defined text from memory, automatic carriage return, and a memory preservation feature which prevents loss of data by signaling when a character is added to a full memory.

Display provides a full 128 char u/lc character set, scroll up or down, full tab/clear control, end of data tab, and protected text control. A paging feature permits display of all characters in memory, and permits the user to recover information that has been rolled off the screen.

Communication speeds up to 9600 baud are possible. An optional serial printer port allows hardcopy records of material on the screen to be obtained.

Circle 418 on Inquiry Card

Compact Business System Incorporates Disc Unit And Video Display

Incorporating flexible disc media and expanded memory into a compact, dual-component system, the model 210 business computer serves as a standalone computer for entry level use or as a host or satellite processor in a distributed computing network. The system was designed by Qantel Corp, 3525 Breakwater Ave, Hayward, CA 94545 to perform all computing functions of larger units and for 100% compatibility with software for the company's larger systems.

In basic configuration the unit includes CPU, 16k bytes of user-dedicated main memory, interactive video display, and a flexible disc drive with storage capacity for 1.2M alphanumeric or 2.4M numeric characters of data. Expansion space is provided to accommodate communications, increased memory and storage, and additional plug-in I/O devices. All this hardware is packaged in the video component. The separate keyboard incorporates alpha and numeric pads and connects to the main computer with a 4′ (1.2-m) cable.

System expansion is accomplished by addition of plug-in circuit boards. Fully expanded, the system supports 32k characters main memory, storage for up to 4.8M numeric characters on flexible disc, any of three hardcopy printers, and synchronous or asynchronous communications.

Each I/O controller incorporates a microprocessor and two memories.



Packed with CPU, 16k memory, interactive video display, and 1.2M-character capacity floppy disc, Qantel's model 210 serves as standalone or satellite processor

This, in addition to increasing computer power, enhances efficiency by enabling the main computer to perform multiple jobs simultaneously. An operator can enter data at the terminal in foreground mode while printing reports in background mode.

Circle 419 on Inquiry Card

Storage Capacity and Communications Added to File Management System

Enhancements to the System 5000 quadruple disc storage capacity and add remote batch communications capability to permit its use in distributed computing networks. Disc units introduced by Inforex, Inc, 21 North Ave, Burlington, MA 01803 for use with the system are the 62M-byte model 5303 and the 235M-byte 5304. Up to four drives of either density can attach to a terminal control unit, providing maximum capacities of 940M bytes. Under software release 506, System 5000 display terminals can communicate with IBM 2780/3780 equipment or other equipment capable of emulating either IBM remote batch protocol.

In addition to remote batch communications capability, the software features dynamic disc allocation, and permits users to build index sequential, as well as simple sequential, files. With system enhancements, a user can access any of the 11M records within 80-char record files in less than 3 s. Release 506 allows files stored on disc in the System 5000 to be transmitted at speeds of up to 9600 bits/s, with a single keystroke command, to a mainframe or any device supporting 2780/3780 protocol.

Hardware enhancements for use with the software include a microprocessor-based binary synchronous communications adapter, which offloads communications tasks from the control unit; and a memory expansion unit, which permits remote batch communication to occur concurrently with online file management.

The adapter handles all communications-related tasks, maintaining throughput during file management by relieving the control unit of the communications burden. Throughput is increased by permitting concurrent communications and online file management. The memory expander feature, which adds 64k words of main memory to the terminal control unit, improves terminal response times in large configurations, especially where a number of procedural steps are performed on each record.

Circle 420 on Inquiry Card

Smile, when you say pussycat!

Pussycat. Perkin-Elmer's $795*, 100 cps CRT Page Printer.

Pussycat. That's what we call our new 100 cps thermal printer, The Model 650 CRT Page Printer.

Pussycat. People who make 30 cps printers will think it's an incredibly funny name. Until they realize our meek little Model 650 is half the price of their machines, three times faster, and a whole lot quieter and easier to maintain.

In quantity 75, the Model 650 is only $795 each. Which means you can buy a CRT and a Pussycat printer for what you're now paying for a printing terminal alone.

The Model 650 is fast. It prints an entire screen full of characters in 20 seconds. And, because it's the only printer in its class with a full-screen buffer, the Model 650 can free the CRT in 2 seconds or less. So the operator can go back to work while the printer is printing.

The Model 650 connects to any CRT terminal with an RS232 port – a Perkin-Elmer terminal or, perish the thought, someone else's. No need to replace existing hardware or software.

And no need to worry about noise or maintenance. The Model 650 has only one moving part – the platen.

Check out The Pussycat from Perkin-Elmer. It's a great little printer at a very reasonable price.

And, if you're one of our competitors... Smile, when you say pussycat!

*Quantity 75.

CIRCLE 23 ON INQUIRY CARD

PERKIN ELMER DATA SYSTEMS | TERMINALS DIVISION

Randolph Park West, Route 10 & Emery Avenue
Randolph, N.J. 07801 (201) 366-5550 TWX: 710-987-7913

Domestic, call:

(617) 890-0557	Boston, MA
(312) 437-3547	Chicago, IL
(214) 234-8880	Dallas, TX
(714) 544-9093	Los Angeles, CA
(201) 229-4040	Oceanport, NJ
(408) 249-5540	San Francisco, CA

Overseas, call:

887-1000	New South Wales, Australia
416-677-8990	Mississauga, Ontario, Canada
539-2260	Paris, France
753-34511	Slough, Berkshire, UK
089-753081	Germany
2200949	Singapore
031/450/160	Frolunda, Sweden

Before the board meets to discuss rising service costs,

call Tektronix

Our new 851 Digital Tester can give you the leverage to control those costs.

Managing a service organization is no bed of roses. It's big business. And it's continually getting more costly. Customer engineers, spare parts inventories, training, designing for serviceability, documentation, and instrumentation all contribute to these spiraling costs. Because service is so important to the success of a company, you need to identify those elements which have the greatest leverage for your service organization.

Consider instrumentation.

Typically it is less than 5% of your overall service budget. Yet the right test instrument can have a tremendous impact on the other 95%... training, salaries, inventory requirements, travel and backup.

That's why we built the new 851 Digital Tester. It's a synergistic, new service instrument that combines the functions of many instruments in one portable package.

We know that the task of servicing digital equipment is threatening to outrun existing service resources. Your first-line customer engineers are being required to make more intricate measurements on increasingly complex systems.

With the new 851, your first-line customer engineer will be able to solve more problems in less time on the first call. That's because he can rely on the measurement and interpretation capabilities of the 851 to perform complicated tests in the field. Not only does this save you the expense of calling in the back-up engineer, but it also gives your first-line engineer the satisfaction of solving more problems on the first call.

A new concept in service instruments.

Your inventory of service instruments probably includes oscilloscopes, DMM's, counters, timers, logic probes, thermometers, and some special purpose test equipment.



A bench full of test equipment is a great resource for your customer engineer to rely on...as long as he doesn't have to travel much.

But imagine a self-contained service instrument that weighs only 13 pounds and makes most of those same measurements.

That's our new 851 Digital Tester.

The power of the 851 lies in the fact that even though this one instrument makes the measurements of a variety of test gear, it is also easy to use.

With just one turn of the knob you can dial 22 different functions to make a wide range of system measurements and tests.

851 Digital Tester Functions

MEASUREMENTS		SIGNAL ANALYSIS	SELF TEST
VOLTAGE	**TEMPERATURE**	**LOGIC STATE INDICATORS**	**TEST SIGNAL**
PEAK (25 ns to 25 ms)	**TIME (20 ns to 10 s)**	HI, LO, INVALID, ACTIVE	EXERCISE FUNCTIONS
AC	PERIOD	**% DUTY FACTOR**	ADJUST PROBE
DC	FREQUENCY	**COUNTING**	**READOUT TEST**
POWER LINE	PULSE WIDTH	FREQUENCY RATIO	
INPUT LOGIC THRESHOLDS	INTERVAL	EVENTS BETWEEN START AND STOP PULSES	
RESISTANCE (0.1Ω to 50 MΩ)	COINCIDENCE	TRANSITIONS BETWEEN START AND STOP PULSES	
	TRANSITION	TOTALIZE	

It's easy. Just dial a function, probe the circuit being examined, and read the results directly from the auto-ranging LED display.

And what about product support? With Tektronix, it's worldwide.

Wherever in the world your service organization goes, Tektronix is with you all the way. Service personnel at 46 Tektronix Service Centers in the U.S. as well as service personnel in 50 other countries back our products.

Put the 851 to work in your digital service environment.

The measurement capabilities of the 851 make it particularly useful for sevicing computer peripherals, small business systems, and industrial control equipment.

We had you in mind when we designed the 851 Digital Tester.

Detailed specifications, application notes and a color brochure are available for your information. Please contact your Tektronix Field Engineer. Or write Tektronix, Inc., P.O. Box 500, Beaverton, OR 97077. In Europe write Tektronix Limited, P.O. Box 36, St. Peter Port, Guernsey, Channel Islands.

New concepts in digital service

Tektronix

COMMITTED TO EXCELLENCE

For technical data, circle 24 on Inquiry Card.
For a demonstration, circle 25 on Inquiry Card.

High Density, 28-Track Digital Tape Recorder Offers High Throughput

A 28-track, high density, digital magnetic tape recorder, the HI-D™ system offers a wide dynamic range at high throughput rates with high tape packing densities and data capacities, meeting demands for increased resolution and the need to store increasingly large quantities of information. By recording data in digital form, the need to translate from analog to digital for subsequent data processing is eliminated, increasing the usefulness for real-time uses.

General specifications of the HI-D system, introduced by Bell & Howell Co, Datatape Div, 300 Sierra Madre Villa Ave, Pasadena, CA 91109, include parallel entry and exit of data at data rates to 92M bits/s; TTL-compatible, single-ended or differential input and output of data and coincident clock; and the ability to handle long strings of 0s or 1s. Parallel E-NRZ™ (enhanced non-return to zero) electronics are capable of handling digital data at up to 3.3M bits/s per channel. A minimum of four channels and a maximum of seven or 14 channels on 0.5" (1.27-cm) tape and 14 or 28 channels on 1" (2.54-cm) tape can be accommodated.

The enhanced NRZ recording scheme is a variation of the basic non-return to zero code that is particularly useful for high density recording. E-NRZ takes advantage of the basic code's high packing density capability and overcomes the low frequency limitation by insuring a data level transition using data enhancement techniques. Incoming data are first compressed in time base, then the enhancement bit is inserted. When data are reproduced, the enhancement bit is removed and the original data stream is reconstructed.

Using the E-NRZ technique with a tape speed of 120 in/s (305 cm/s), a nominal input/output data rate of 3300k bits/s per track is achieved with a bit error rate of 1 in 10^6 for 28-track operation. Recording with tape speed of 1.875 in (4.76 cm)/s and 51.5k bits/s I/O data rate per track results in a bit error rate of 1 in 10^5 for 28-track operation.

The system encoder provides an input rise/fall time of 100-ns maximum. The E-NRZ data are augmented by a 40-bit deskewing sync word used to align the output skewing buffers, which consist of four TMS 3120 shift registers with storage capacity for 1280 bits (1120 data bits and 160 enhancement bits). Data rate is automatic with tape speed selection for data rate ranges specified for 1.875 to 120 in (4.76 to 304.8 cm)/s.

Reproduce/bit sync/decoder provides amplitude and phase equalization, synchronizes and regenerates the clock from data, and decodes data to remove parity bit, deskew sync information, and bit inversion to restore data. For setup, troubleshooting, and verification of system performance during operation, record level, reproduce level, bit error rate, and data rate monitor outputs are wired from the decoder to a multipin connector on the back of the amplifier mounting assembly. □

Circle 421 on Inquiry Card

STOP

WAITING ON OUTPUT FROM YOUR MINI

You Are Wasting More In Dollars For Human Resources Than This LINE PRINTER Costs

2400 LPM - 80 COL.
MODEL 8210 - $3450*

1400 LPM - 132 COL.
MODEL 8230 - $3785*



FOR ORDERING INFORMATION CALL OR WRITE:

houston instrument | DIVISION OF BAUSCH & LOMB

ONE HOUSTON SQUARE (at 8500 Cameron Road) AUSTIN, TEXAS 78753
(512) 837-2820 TWX 910-874-2022 cable HOINCO
TELECOPIER
EUROPEAN OFFICE Rochesterlaan 6 8240 Gistel Belgium Phone 059/277445 Telex Bausch 19399

"the recorder company"

* Domestic USA Prices, Qty 1, End User

For a demonstration, circle 26 on Inquiry Card.
For literature, circle 27 on Inquiry Card.

From a single CPU board

to a half million word super computer

That's the selection you get from ROLM's AN/UYK-19 family. It's the most complete line of Mil-Spec computers in the industry. And every piece is backed by extensive, updated, upward compatible software.

Delivery? 30 days or less because they're all standard products in continuous production. Plus they follow a modular concept for interchangeability, compatibility and upgrading.

Rolm completes the package with full nomenclature and an integrated line of both military and commercial peripherals.

In just seven years we've been able to put together a family plan that lowers your programing costs, reduces hardware costs, cuts out your risk and gives you quicker reaction time.

That's Why We're #1 in Mil-Spec Computer Systems

ROLM MIL-SPEC Computers

4900 Old Ironsides Drive, Santa Clara, CA 95050. (408) 988-2900. TWX 910-338-7350.

In Europe: 645 Hanau, Muehlstrasse 19, Germany, 06181 15011, TWX 418-4170.

CIRCLE 28 ON INQUIRY CARD

TOUGH COMPETITION:

The complete 125 ips package—beats anything in its class now moving tape.

Strong words. For strong capabilities, wrapped up in a strong new look. A totally new design in vacuum column drives houses the first *complete* high-speed package in the field.

The T1000 Series from Pertec.

No more compromising. No more shopping around. We've got it all. Together. Just for starters: 125 ips. Plus GCR. Plus auto-thread and auto-load.

You'll find everything you need to feed your powerful mini systems, in a T1000 configuration. These are not only our most advanced, most flexible tape transports produced today—they're built by Pertec to fit tomorrow's data processing applications to a T.

Ask for 6250 bpi GCR. In addition to dual NRZI/PE modes available, T1000 drives offer OEMs the only Group-Coded Recording at 125 ips—*with* a vacuum capstan to protect high-speed operations with a friction-free instant grip, for safer fast starts and stops.

Ask for operational convenience. T1000 makes life easier for your customers: *with* cartridge auto-load, automatic threading, and automatic load point seek. *With* a built-in daisy-chain capability. *With* front access to all electronics to simplify maintenance.

Ask for internal data formatting. Intelligence can be built into T1000 NRZI/PE configurations (as well as our tension-arm 7" reel FT7000 and 10½" reel FT8000, and our 37.5-to-75 ips FT9000 vacuum column series). Pertec is now installing our Microformatter inside these units, on order, to simplify interfacing, and reduce system costs.

Now complete the picture: ask for Pertec. Making it still tougher on the competition, our broad line of tape transports covers the full spectrum of OEM requirements. With the same total commitment backing T1000: Pertec, the world's largest independent manufacturer of peripheral equipment, backs *all* its products with the international sales, support and service operations of Pertec Computer Corporation.

There's a Pertec service office near you... and your customer. With emergency assistance on-call, on a 24-hour 7-day basis, through our toll-free 800 line.

☐ Please send complete details on the Pertec T1000 Tape Transport Series.
☐ Send pricing information as indicated on the RFQ below (no obligation or cost).

Request for Quote

T1000 Model #	Data Format	Data Density (bpi)	Tape Velocity (ips)	Quantity Required	Date Wanted	Send Specs Only
T1640-98	PE/NRZI	1600/800	75-125			
T1940-96	GCR/PE	6250/1600	75-125			
FT1640-98 w/internal formatter	PE/NRZI	1600/800	75/125			

Name_____

Title_____ Phone_____ Ext_____

Please attach coupon/RFQ to company letterhead and return to Pertec, 9600 Irondale Avenue, Chatsworth, CA 91311.

For immediate requirements, call your nearest Pertec regional sales office:
Los Angeles (213) 996-1333. Ann Arbor, Michigan (313) 668-7980. Hudson, New Hampshire (603) 883-2100. England (Reading) 582115.

PCC PERTEC
a division of Pertec Computer Corporation

© 1977 Pertec Computer Corporation

CIRCLE 29 ON INQUIRY CARD

Brooklyn Firefighting Units Respond to Computer-Aided Dispatching System

Four hundred and fifty thousand alarms a year—an average of nearly one alarm each minute. When those figures relate to incidents reported to the fire department in a major city, the problem of apparatus distribution becomes gargantuan and seemingly almost totally unwieldy—particularly if nearly half of the alarms are false, tying up equipment that is needed elsewhere.

New York City's fire department—more commonly designated FDNY—consists of over 350 pieces of apparatus and more than 10,000 firefighters. Until recently, deployment and control of all equipment and personnel in all five of New York City's boroughs was handled manually by human dispatchers.

Under this "manual" system, a fire alarm for a particular borough—usually reported by street alarm box or telephone—is transmitted to a central communications office in that borough, where a dispatcher decides how many and which units to send in response. The dispatcher must assume all alarms to be "real"; even an alarm that the dispatcher believes to be false requires a response of at least two pieces of equipment: one engine or pumper and one ladder. In addition, these "real" alarms do not all concern serious or structural fires. The problem being reported may be a rubbish can fire, a person stranded on an elevator, smoke in a vent, or food burning on a stove.

The dispatcher must know the availability of backup apparatus in case a working fire requires additional firefighting units. No section of the city can be left unprotected. If an area is stripped of fire protection, equipment must be reassigned from another area as cover.

The variety of demands for fire department service and the rapidly increasing rates of alarm activity—30,000 in 1925; 60,000 in 1945; 130,000 in 1965; 300,000, in 1973; 400,000 in 1975; and 450,000 in 1976—forced FDNY to reassess its policies. It had become apparent that present procedures for response and deployment would soon become inadequate, that more sophisticated methods were required for predicting alarm incidents and for assigning units to each alarm.

Brooklyn MICS: The First Step

In February of this year, the borough of Brooklyn—in itself the fourth largest city in the United States—placed online a Management Information and Control System (MICS) that provides computer assistance to that borough's fire department communications facility. Only the Brooklyn MICS is computer assisted; all other boroughs perform their respective dispatching functions manually.

MICS is capable of handling three alarms each minute with 1-s CRT response time—almost four times the 1976 incidence rate. A complete cycle including receipt of alarm, selection of equipment, and relay of alarm and assignments to the watch desk is performed in 40 s or less.

The Brooklyn MICS, contracted for with Bradford National Corp, 1700 Broadway, New York City in March 1975, was built and installed in 18 months and placed online five months later. It is a dual computer system with dual microprocessor backup in the most critical area.

Two Digital Equipment Corp PDP-11/45 computers are chief components of the assignment and dispatch system. One computer is constantly online to a dual access disc subsystem and, via a line switch, to a display/fallback system as well as various input/output systems (Fig 1).

The computers constantly maintain a channel-to-channel link for interprocessor communications. If the online computer fails, the standby unit immediately assumes its duties with full access to all system components.

Similarly, a pair of Intel 8080 microprocessor-based controllers—included in the critical status recording subsystem as backup for the larger computers if both of those units fail—have online and standby duties. In the very unlikely event that all four processors fail, the status recording subsystem reverts to manual operation.

The online PDP-11/45 processes alarms received from the old mechanical street boxes, from newer electronic street boxes that permit voice communication as well as transmission of digital signals, and via direct telephone contact. Based on company availability and programmed rules, the computer determines the quickest and most suitable response to each alarm and displays each proposed unit dispatch assignment on a CRT terminal for the dispatcher's approval or modification according to personal knowledge of the situation. Once the dispatcher agrees with the computer's choice, he validates the assignment by pressing a button which allows the computer to send a message

The new Fluke 3041A programming station with the 3040A Logictester™ for μP boards you haven't even designed yet!

Check one: Fluke's ☐#1 ☐#3 in digital board testers.

Correct on both counts.

More Fluke logic test systems are in production and service applications than anyone's. And more are shipped each month. Two ways of saying we're #1.

And, our customers spent less getting us there than they could have with anyone else. That makes us #3 on average cost.

But low front-end cost is only the start. You'll get lower programming, training and start-up costs than you thought possible. The highest test rates in the business, too, because boards run at rated speeds, including dynamic μP boards at multi-MHz rates.

More importantly, you'll test with confidence. If your board passes our tester, it'll work in your system. It's that simple. And reliable; more Fluke systems sold prove it.

The heart of our 3040A is a new merged sequence technique which lets you mix your test codes with automatically-generated sequences. And the best simulator around: your own known-good board. And dynamic LSI/fault isolation, automatic, manual or both!

Fluke hasn't forgotten about the bad boards either. After the tester nails the bad ones, we automate the troubleshooting. Our Autotrack™ computer-guided troubleshooting leads the operator to the fault. With the new 3041A programming station, you describe the board onto a floppy disk and the 3040A does the rest.

The **3040A**, with up to 240-pin capability, is $60,000 to $95,000*, depending on option configuration.

The **3020A** logic test system, at about $32,000*, is perfect for production test of all popular logic families.

For light production test or field service, our model **3010A** has 128-pin capability for under $15,000*.

Call (415) 965-0350, collect. Ask for the complete story on our high-ranking Logictester™ family, or the location of the closest Fluke office. Or, write: Fluke Trendar, a subsidiary of John Fluke Mfg. Co., Inc., 630 Clyde Ave., Mountain View, CA 94043.

In Europe, write: Fluke (Nederland) B.V., P.O. Box 5053, Tilburg, The Netherlands. Phone: (013) 673-973. Telex: 52237.

*U.S. price only.

Command Performance: Demand Fluke Logic Test.

For literature, circle 30 on Inquiry Card. For a demonstration, circle 31 on Inquiry Card.

FLUKE®

1710-8001

ComputerAutomation's NAKED MINI® 4/10 is the most exciting spread we've ever dished up: a high-speed, versatile, 16-bit processor, up to 4K words of RAM/PROM memory, and four distributed I/O channels. All on a single board. And this powerful, multi-register minicomputer sells for micro prices.

Value, however, is a lot of things. Such as performance, versatility, and a faster, lower cost way of getting a product to market. For the 4/10, your real savings just begin to start with the sale price. Its large instruction set (including multiply/divide as standard) pays off with exceptional programming versatility, faster development, less memory used. Options include floating-point instructions and double-register shifts.

Its four distributed I/O channels are another money saver, cutting interfacing costs by up to half. Our unique Intelligent Cables (19 available) give you interface capability with a broad variety of standard and nonstandard peripheral devices. Distributed I/O has other advantages. Its auto I/O instructions are easier to program, take less memory, and execute faster than traditional programmed I/O. And it has the advantages of DMA at about half the cost.

SMORGA



©1977 ComputerAutomation, Inc.

The 4/10 has 64K-word addressing and a MAXI-BUS that allows interfacing with the wide variety of interchangeable memories and I/O controllers in the NAKED MINI 4 family.

What about software? It's one of the 4/10's real strengths. Not only a wide range of software, but also software optimized individually for both development and execution needs.

Available software ranges from the simplest—a memory-based system that runs in as few as 4K words—through the most sophisticated, a full-blown, disk operating system that supports FORTRAN IV, BASIC, PASCAL, and MACRO 4 assembler.

In terms of hardware and software, the 4/10 is fully compatible with its higher performance brothers, the 4/30 and 4/90.

Okay, we've served up our new 4/10 mini with lots of standard and optional hors d'oeuvres. Still hungry for information? Contact Department 1161, NAKED MINI Division, 18651 Von Karman, Irvine, CA 92713, (714) 833-8830, for our new brochure. It's quite a bit of food for thought.

SBOARD.

ComputerAutomation®
Naked Mini® Division

CIRCLE 32 ON INQUIRY CARD

NAKED MINI products are sold only under volume purchase agreements.

to the firehouse. When the hardcopy record appears on the firehouse teleprinter, a fireman hits an acknowledgement button on a response panel. If this acknowledgement is not received within 20 s, the dispatcher transmits a voice message as backup.

Even after an alarm has been answered, the computer monitors the status of all assignments, including requests for additional units for major fires. It also determines if adjustments and reassignments are necessary to protect an area of the borough from which firefighting units have been depleted—and recommends the relocations to be made. Finally, the dual computer system provides management information reports of all activities processed by the system.

Operational Modes (Fig 2)

Alarm Receipt: This mode supports three methods of receiving alarms: mechanical street boxes, electronic street boxes, and telephone. Coded alarms originating



Fig 1 Basic configuration of Brooklyn MICS. Control computer is backed up by identical standby unit, both of which have access to dual disc subsystem. Online and standby microprocessor controllers serve as dual backup to two larger processors. If all four fail, system is operated manually



Fig 2 MICS modes of operation. All five modes are assisted by computer recommendations but operator or supervisor makes final decision. Box alarm readout system and city-wide deployment CPUs are not actually part of MICS but function with it

Quite frankly, we're going to be #1 in memory testing till the cows come home.



Four years of matching the memory industry breakthrough for breakthrough have made Teradyne the leader in memory testing.

We started back in 1973 with the J384, a dedicated memory test system. It tested RAMs and ROMs efficiently and economically. But things were changing fast.

1974 saw the advent of dynamic devices like the 4k 2107. And we added the M385 microprogrammable pattern generator to keep pace.

In 1975 our answer to increasingly complex memory technology was a new system, the J387.

In 1976, when 16k and page-mode parts went into production, we responded with the H712 test deck.

Today, Teradyne has an installed base of well over 100 J380-series memory test systems working for more than 20 companies. At probe, at final test, and at incoming inspection. That's a larger dollar base than our two nearest competitors combined.

Four years of experience have made us the most capable source of memory test equipment in the world.

If you test semiconductor memories, call us today. You'll call us eventually. Because no matter where memory technology goes from here, Teradyne will be there.

TERADYNE

Semiconductor Test Division
Boston, Mass.–Chatsworth, Calif.


Engineers looking for new and innovative switching come to AMP.
Because we keep an eye on the future.
AMP
435668-6
7532
435166-2
AMP 7625
435727-1
AMP 7612
435478-4
AMP 7625
435733-5
AMP 7612
435673-6
7532
435166-3
TS-41

We started with the world's first miniature Dual In-line Package switch and now have types ranging from new mini-matrix slide switches and coded rotary switches to LED and side-actuated DIP types, to name a few.

And as we have from the beginning, we stand behind every one of them, new or old, with an offer of solid, technical support. Not because they need it. But because we believe you as an engineer, are entitled to it when you innovate. It's the kind of full support that says we're ready to work with you not only in product application and production but even earlier, in research and development, if you desire. And we think you'll find it a good way to keep an eye on the future of switching.

Among the most popular of our "future" switching innovations is the unique Mini-Matrix Slide Switch. It's especially useful for logic level matrix, switching applications. And our new programmable DIP Shunts offer another easy way to program manually. By simply opening or closing conductive straps.

But perhaps the most revolutionary switch of all is our unique, patented coded rotary switch. It switches the circuit instead of the contacts. Just as new, is our DIP Network Switch. It's designed for use with thick film capacitor and resistor chips for impedance switching and time delay functions.

As you can see, there are many more switching innovations, like our Standard Rotary switches and Pull-to-set types. For more information, just call AMP Customer Service at (717) 564-0100. Or write AMP Incorporated, Harrisburg, PA 17105. **CIRCLE 33 ON INQUIRY CARD**

AMP has a better way.

AMP
INCORPORATED







AMP is a trademark of AMP Incorporated

from mechanical street boxes are multiplexed through a box alarm readout subsystem (BARS) where they are converted to digital information and processed automatically by a separate computer. Alarm data (30 bits/alarm) are transmitted to the MICS computer via a standard RS-232-C communications interface at 600 baud.

A different type of electronic street box, used in a new emergency reporting subsystem (ERS), permits a voice alarm to be presented directly to the alarm receipt operator while a digitally-encoded alarm is sent to the BARS central processing unit (CPU) via a modem interface. Each digital alarm consists of 40 bits of information including parity and is transmitted at a nominal rate of 600 baud.

ERS voice alarms and those received via telephone are switched to alarm receipt operators who obtain the pertinent information and enter it into MICS through a CRT terminal. Telephone alarm information is processed by a phonetic address translation program that provides phonetically equivalent alternatives to eliminate the need for correct spellings.

Each alarm is checked by the computer against alarms in process to determine if it is unique or if it has already been received from another source. When an alarm is found to be unique, MICS enters the decision dispatch mode. Under special conditions, an emergency control procedure can be set up to funnel all related alarms for a designated area to a special command post that operates in an independent mode.

Decision Dispatch: For every alarm received, MICS must determine how many and which firefighting units should be sent. Since MICS assists rather than controls, this determination is displayed for review and approval of an operator or supervisor before any further action is taken. Units can be added to or deleted from the recommended response or any of several other actions can be substituted.

In most cases, the decision dispatcher will handle the decision. However, a supervisor can assume control in case of unusual alarms or when coordinated actions are needed to handle special equipment. The supervisor also interacts with the computer to relocate units if an area becomes unprotected or resources have been reduced below an acceptable level.

Status Recording: This mode provides both a visual aid and automated backup. A "chipboard" maintains a record of all current incidents in Brooklyn, keeps track of the status of 100 firefighting companies normally assigned to and housed in Brooklyn, and stores domino-like chips representing the Brooklyn companies plus 45 fire companies housed outside of Brooklyn but commonly used at Brooklyn incidents. In addition, a geographic display (an illuminated map) is used to keep track of the status of the engine and ladder companies in order to assure that minimum coverage is maintained at each area.

We're showing off for Commonwealth Edison.

Chicago's Commonwealth Edison uses Ramtek color graphic displays for rapid display and status reporting of pipelines, valves, pumps, and other generating station data. A clear, color-coded display is updated every 5.0 seconds, giving near-instantaneous visual scan-log-alarm functions, bar graphs, one-line piping diagrams, flow status, etc.

Before the Ramtek systems were installed, status reporting was by hardwired mimic boards, black and white alphanumeric CRTs and typers.

The Ramtek system not only costs less, it also allows more information to be presented to the operator in a form that is quickly and easily understood. This results in better operator efficiency, and faster alarm reaction time. In Commonwealth Edison's 16,000 Megawatt system, thirty Ramtek color graphics displays will be utilized.

Status entry panels are located at alarm notification workstations. Each panel is actually a specially-designed keyboard for updating unit and incident data.

During automatic or prime mode of operation, the online microprocessor controller maintains control of chipboard, map, and status entry panels as a peripheral to the computer. If both PDP-11/45s fail, the microprocessor controllers assume full control of the status recording subsystem.

If both computers and both controllers fail, the displays are updated in manual operation directly by the status entry panels. In that situation the system supervisor determines the availability of a company by the state of the associated light. The supervisor then removes the plastic chips for operational units and sets up a visual display manually.

Notification: At this point in the cycle, the units chosen to respond to an alarm might be in the firehouse or might be at the site of an earlier alarm. If the unit is at the firehouse, the alarm order is transmitted by the teleprinter; if the unit is at another location, the order is sent by radio. In both cases, a hardcopy record is printed on the firehouse teleprinter.

To complete this phase, an acknowledgement must be sent by the selected unit. Each firehouse in Brooklyn contains a microprocessor-controlled response panel which also functions as controller for the alarm teleprinter. Acknowledgement messages are transmitted by pressing panel buttons.

Notification also involves contact with other FDNY commands; eg, second alarms are sent city wide. In addition, certain situations might prompt the operator to notify police, ambulance, or even sanitation departments.

Status Monitoring: The status of both units and alarm incidents are monitored by MICS to provide accurate real-time knowledge of the availability and location of all firefighting units. Units report by radio when they complete their work and are leaving a scene, and again when they arrive back at the firehouse, or at another scene when ordered to relocate.

MICS acknowledges all unit reports and updates availability status records. An automatic monitoring function alerts the radio dispatcher if a unit fails to report within a preset length of time.

Management Information: A variety of functions performed in this mode support the actual dispatching process. These include data recording, which frees dispatchers from preparing routine paperwork and captures data to be reported to management; activity reporting, which provides statistical summaries of unit and department activities; and inquiry/retrieval, which allows access to information on incidents less than 72 hours old.

In addition, this mode provides performance monitoring of critical parameters, and load generation to measure response rates and gather data on city wide deployment. It also programs time scheduled events, supports dispatcher training, and controls operation of printing terminals for administrative message switching.

(*Continued on p* 58)



Commonwealth Edison monitors on-off, full-empty, flow status, and other parameters on a Ramtek FS-2400. Color is assigned for steam, water, no-flow, and oil flow to differentiate visually between materials and status. On the RM-9000, resolutions from 240 lines x 320 elements to 512 lines x 640 elements are available.

Commonwealth Edison is but one of a growing number of customers who are finding that Ramtek's raster scan modular graphics and imagery systems are giving them the expandability, flexibility, and increased productivity they need. Besides the basic alphanumeric and imaging capability, Ramtek offers a wide variety of other functions including graphics—vectors, conics, plots, bar charts—pseudocolor, and grey-scale translation.

Ask about our new Ramtek RM-9000 family that is totally controlled by a standard 8080 microprocessor that really makes it easy to develop and download your own control software.

To find out more about how Ramtek can show off for you, call or write: Ramtek Corporation, 585 North Mary Avenue, Sunnyvale, California 94086 (408) 735-8400.

Ramtek
Our Experience Shows

CIRCLE 34 ON INQUIRY CARD



Fig 3 Brooklyn MICS detailed hardware configuration. Online and standby systems are fully redundant. They access dual disc drive subsystem and special input/output devices via switching network

Hardware

The two PDP-11/45 minicomputers (Fig 3) are configured with 96k words of core memory as well as three 88M-byte discs, two tape drives on each system, line printers, card reader, CRT terminals, special duty terminals for central office operations, and a microprocessor-controlled alarm teleprinter in each fire station. Status recording subsystem 8080-based controllers contain 8k bytes of read-only memory and 2k bytes of random-access memory that enable control of devices which show unit and incident status and location changes.

Communication is maintained via FDNY's own communications lines. Therefore, even a major fire at a telephone company switching center is unlikely to seriously affect the fire alarm system. A communications multiplexer subsystem capable of handling 64 asynchronous telecommunications lines is maintained for MICS.

An input/output (I/O) switch enables access to the dual disc subsystem by either the online or standby computer so that either or both disc subsystems can be connected to either computer. This switch also controls part of an I/O bus, allowing other devices to be accessed by the computers.

Primary access to MICS is via 16 CRT terminals located at alarm receipt, decision dispatch, and management points. In addition, 100 teleprinters are distributed among the borough firehouses and three more are situated at locations in the central office and at headquarters. These provide a hardcopy record of all alarms and equipment dispatch orders. Both firehouse alarm teleprinter/response panels and CRTs are specially designed units supplied by Megadata Computer and Communications Corp.

(Continued on p 62)

Now Norden gives the PDP-11/34M a little brother: the LSI-11M.

New militarized micro-computer uses same software as commercial LSI-11.



The LSI-11M is a full-scale, 16-bit micro-computer and the smallest computer in the PDP-11M line. Part of a new family of fully-militarized computers, it uses exactly the same software as the commercial LSI-11.

Combining Norden's experience in military electronics with DIGITAL architecture and DIGITAL software, the LSI-11M offers exceptional price/performance. This is a direct result of a rich repertoire of over 400 instructions and a low hardware cost.

Familiar features plus militarized peripherals.

Available without chassis, the LSI-11M comes as a 6 x 8.2 x 1" CPU module. This module is available with 4K words of resident semiconductor memory. Further memory options in the form of 4K PROM and 16K and 32K core modules are offered. Peripheral and I/O connections are accomplished thru fully militarized serial and parallel I/O modules. The LSI-11M also has a real-time operating system (RT-11).

For more information, call or write Director of Marketing, Computer Products Center, Norden Division, United Technologies Corporation, Norwalk, Connecticut 06856; Telephone (800) 243-5840 toll-free, or call (203) 838-4471.

PDP-11 and LSI-11 are licensed trademarks of Digital Equipment Corporation.

PDP data processing with Norden military muscle.

NORDEN

Division of
UNITED TECHNOLOGIES®

CIRCLE 35 ON INQUIRY CARD

990 OEM minicomputers.



Built, backed and priced to sharpen your competitive edge.

TEXAS INSTRUMENTS.

The 990/10 minicomputer from TI brings superior value to both you and your customers.

Starting with field-proven hardware, the 990/10 delivers the reliability you expect from TI. And all the off-the-shelf support you need for user applications. You get standard software languages, a broad choice of peripherals and nationwide service.

Built for more processing power.

The 990/10 is the most powerful member of the 990 computer family. Its architecture provides features that give you maximum processing power for your money. Like hardware multiply and divide. A 16-level hardware



Peripheral Interface Modules

interrupt structure. 16 registers arranged in a workspace concept. I/O that's directly programmable through the Communications Register Unit (CRU) and autonomously through a high-speed data bus. And bit, byte and word addressing of memory.

Built for system flexibility.

In small or large configurations, the 990/10 design provides surprising flexibility for a small investment.

The CRU, with up to 4096 I/O lines, reduces interfacing costs by keeping controller complexity to a minimum. The TILINE* asynchronous high-



Model 911 Video Display Terminal

speed data bus can support both high- and low-speed devices and takes advantage of design simplicity for simultaneous data transfer between peripherals, the CPU and memory.

With the 990/10, you get a powerful instruction set with an extended operating feature that allows hardware to take over operations that software would normally execute. An optional mapping feature provides memory protection and memory expansion to 2 million bytes. And, optional error-correcting memory corrects single-bit errors for increased system reliability.

DS 25/50 Disc Drives

Full peripheral support.

As well as a range of standard peripherals, disk storage to 180 million bytes and magnetic tape with 800 and 1600 bpi options are available for low-cost mass storage and back-up.

A choice of software.

With common higher level languages, FORTRAN IV, COBOL and Multiuser BASIC, plus the 990/10 assembly language, you have all the tools you need for an efficient application program.

Both the disk-based and memory resident operating systems give you modularity and flexibility for system generation to meet application de-



Model 979A Tape Drive

mands. We offer program development aids for creating and testing software, and communications software to support synchronous or asynchronous data transmission.

Backed with nationwide service.

Our responsibility to you doesn't end with the sale. We follow through with complete system training, plus a nationwide factory service network.

The TI 990/10 minicomputer. We build it, back it and price it the way you and your customers want it. You can start configuring a system now with our 990 Computer Systems Handbook on the upward-compatible family of the TMS 9900 microprocessor, 990/4 microcomputer and 990/10 minicomputer. For your free copy, send a letterhead request to Texas Instruments Incorporated, P.O. Box 1444, M/S 784, Houston, Texas 77001.

TEXAS INSTRUMENTS
INCORPORATED

*Trademark of Texas Instruments

CIRCLE 36 ON INQUIRY CARD

Copyright© 1977, Texas Instruments Incorporated

Accurate time of day information is provided to the MICS computer by a time base generator. Time is expressed in hours, minutes, seconds, and milliseconds for inclusion in reports.

In the near future, a solid-state uninterruptible power supply (UPS) that will be able to support all MICS equipment for up to 20 minutes will be added to the system. It will be for use during the transient periods that would be required for the central office dual motor-generator sets to come up to speed to supply power if commercial supplies failed.

Software

A control program consisting of system, application, and data management continually coordinates all supervisory functions and monitors, schedules, and controls the execution of MICS programs. It includes the monitoring of all system operations that are program controllable to check hardware operation and performance.

System management is concerned with status, performance, and effectiveness of the overall system. It controls and monitors both the system and interjob processing flow. Events or requests are handled on a



Fig 4 Overall configuration of recently approved centralized MICS for all of New York City. All data processing functions for five borroughs of New York City will be performed at central site. However, each remote site or borough central office will control its own alarm receipt and dispatch functions. Initially Brooklyn MICS will remain in its present state although it will be part of overall system. Later it will be reconfigured to be same as other four central offices



Fig 5 FDNY central site configuration. Dual computers will be redundant but standby unit will be available for other processing duties. Central site concept eliminates need for duplicating some of data processing hardware at each remote site

THE OEM COMMITMENT

We want to do business with every Tom, Dick and Harry.

Whether you need our single board 16-bit 5/16 minis, high powered 32-bit 8/32 Megaminis, or complete systems with Interdata peripherals . . . we're ready to provide all the support you need.

Let's face it. Too many vendors are only interested in the big guys. In this business, he who orders 10 minis today may be reordering 100 tomorrow.

We remember. That's why . . . I'm restating our OEM commitment.

Interdata is out to do things most computer companies won't. Like meet short delivery dates. Back you up with extensive field support. Plus, a 24-hour Hot-Line providing quick information on our products, engineering services, documentation and more.

The size of your company or your application is irrelevant. We want to do business with you.

Want to know how far we'll go? Call me, Steve Sutker, OEM Marketing Manager at (201) 229-4040.

INTERDATA®
A UNIT OF
PERKIN-ELMER DATA SYSTEMS
Oceanport, New Jersey 07757, U.S.A.

CIRCLE 37 ON INQUIRY CARD

priority basis depending on relative importance. Application management controls supervisory application processing needs of the program modules, while data management controls the transfer of information between main storage and external devices.

City-Wide MICS: The Next Step

Approval of a FDNY proposal to expand the Management Information and Control System (MICS) to cover all five boroughs of New York City was received in August of this year, just six months after the Brooklyn computer-aided dispatching system went online. This multi-borough MICS will concentrate data processing at one site that will be in constant contact via 9600-baud communication lines with central offices in all five boroughs (Fig 4).

The new system will necessarily be even more sophisticated than that now in use in Brooklyn. However, the present borough MICS will be compatible with the new centralized system and in time will be converted to include the same equipment.

This centralized approach, according to John Mohan, director of the FDNY Bureau of Information and Computer Services, and Irwin Steinberg, deputy director, will result in a savings of $2 million—about 20%—over the cost of four separate systems. In addition, data processing requirements will be more easily administrated, operated, and supported by only a single group of specialists. There will also be less total equipment and less disruption of services.

The central data processing function will be controlled by dual Digital Equipment Corp PDP-11/70 computers, one online and the other on standby (Fig 5). The latter computer, however, will be available for other communication or batch work until required to go online.

Each processor will be supported by high speed magnetic tape drives, high speed line printer, card reader, system console, synchronous multiplexer for communication with borough central offices and firehouses, and asynchronous multiplexer for local CRTs and printers. Four dual access 176M-character disc drives will permit programs, static files, and dynamic files to be separated.

Communication with borough central offices (remote sites) will be maintained via three synchronous, full duplex channels. Any one of these lines will be sufficient to maintain central to remote communication with minimum degradation; however, an additional "hot line" will be provided between central and remote sites as backup.

All software support and maintenance will be performed at a single location. The central site processor will contain all application and communication software required for borough central office interface.



Fig 6 Borough central office or remote site configuration. Redundant concentrators control message traffic via switching and system control console. Microprocessor controllers are backup as in Brooklyn MICS

(*Continued on p 68*)

Amphenol 17-Series rear-release connectors, contacts, and crimpers.

Now with insulation-support crimp-contact back end.

You asked for it. With our 17-Series, you can crimp any conductor size from 22 to 26 AWG and also crimp the insulation up to a maximum of 0.050" OD.

The connectors are 50% less costly to assemble. Snap several of our crimp Poke-Home® contacts in place in the time it normally takes for a single contact inserted with a tool. You can cut labor costs in half.

The contacts mean big savings for volume users. With our 15,000-contact capacity reels, you can save a bundle over loose contacts.

Our high-speed crimpers lower costs even more. Completely eliminate stripping with our stripper-crimper (up to 1500 terminations per hour). Our semi-automatic crimping machines handle up to 2000 terminations per hour. And our new hand crimp tool makes accurate, identical crimps—time after time.

Get them all—connectors, reeled contacts, crimpers. And get them now. For more details, call: Bob Ashley, (312) 986-3673 or write: Amphenol North America Division, Bunker Ramo Corporation, Dept. L117, 900 Commerce Drive, Oak Brook, Illinois 60521.

Hand crimpers and semi-automatic crimping machine.

The right idea at the right time.

BUNKER RAMO® **AMPHENOL®**

Visit us at Midcon/77 Booths 408-410

CIRCLE 38 ON INQUIRY CARD

Total cpu control
High level command keys and binary/hexadecimal displays provide complete system control, easy operation.

Worldwide portability
μScope 820 is fully self-contained, with accessory storage space. Operates on all standard U.S. and worldwide power sources.

Preprogrammed diagnostics
Overlay memory socket enables designers to plug in and execute customized diagnostics for each end product.

Breakpoint control and trace memory
Built-in high level diagnostics speed and simplify isolation of even the most difficult system problems.

Human engineered
Extensive prompting simplifies operation for test and service personnel, minimizes training time.

Interchangeable front panels, personality cards and personality probes
μScope 820 adapts to a variety of microprocessors. Probe plugs directly into system microprocessor socket.

Intel delivers μScope™ 820. Finally, a diagnostic instrument just right for the Age of the Microprocessor.

Troubleshooting microprocessor systems is easier than ever with Intel's new μScope™ 820 Microprocessor System Console. It's a powerful, programmable, fully portable real-time diagnostic instrument. And it's designed specifically to speed and simplify system checkout of your microprocessor-based products.

μScope 820 is really the first test instrument of its kind. It's built around its own microprocessor, to provide a "smart" solution that's highly sophisticated, yet easy to use. Because it's user programmable with interchangeable plug-in ROMs or PROMs, it's like taking a design engineer along on every service call. And because it's fully portable, the μScope 820 console goes wherever the action is—to the design lab, the production line or into the field.

Unlike logic analyzers, the μScope 820 console provides a genuine solution for test and service personnel. It provides the same inside look at system operation that you get with a logic analyzer. But the μScope 820 goes far beyond the mere collection of data. Its internal microprocessor system can actually analyze the data it collects. It does that with diagnostic programs you design specifically for your end product.

Rather than passively watching system operation, the μScope 820 console lets you execute application programs or diagnostics you develop, in real time or single steps. And it provides full breakpoint capability and a large trace memory.

High level command keys, operator prompting, and binary/hexadecimal display of all system registers, I/O ports and memory give you greater control and make it easier to use than any other test instrument.

Until now the only way to get this kind of diagnostic capability was to use your Intellec® Microcomputer Development System. Now we've taken the Intellec features that have proven most useful for field service and production-level system checkout and have packaged them in this self-contained 20-lb attache case. That's portability.



And we've enhanced that portability with a μScope 820 price of just $2000,* complete with personality probe and all accessories. So you can afford to put a μScope 820 console wherever you need one, and free your development lab instruments to concentrate on development. No longer must you invest in in-house-designed custom test instruments for each of your end products. And the μScope 820 console will be available with a selection of front panel overlays, "personality" cards and system probes to support a variety of microprocessors.

To get your copy of our μScope 820 brochure and to arrange for a demonstration right in your lab, contact your local Intel distributor or sales representative. Or write: Intel Corporation, 3065 Bowers Avenue, Santa Clara, California 95051. Telephone (408) 987-8080. In Europe contact: Intel International, Rue de Moulin a Pàpier, 51-Boite 1, B-1160, Brussels, Belgium. Telex 24814. In Japan contact: Intel Japan, K.K., Flower Hill-Shinmachi East Bldg. 1-23-9, Shinmachi, Setagaya-Ku, Tokyo 154. Telex 781-2846.

intel® delivers.

*Domestic U.S. price only, quantities 1-10.

Circle 39 for technical information.
Circle 40 for technical information and a demonstration.

HOW TO QUIETLY IMPROVE YOUR TELETYPE* MODEL 40 PRINTER.

(Even if you haven't bought it yet.)

The Model 40 is an excellent printer. But it's even better when you enclose it in a Gates Sound Controller.
It becomes so quiet that you can place it anywhere without distraction.

DESIGNED FOR YOUR MACHINES
If you're getting a new printer, you can order a complete Gates Sound Controller instead of a regular teletype case. You'll actually save money. Or you can order Sound Controllers for the printers you already have. Every Sound Controller has a built-in cooling system and space for paper storage.

DESIGNED FOR YOUR PEOPLE
All controls are easily accessible from outside the cabinet. So there's no problem with operation or servicing.

DESIGNED FOR YOUR DECOR
Gates Sound Controllers look as good as they sound. The styling is attractive, and colors can be selected to harmonize with your own decor.

COAST TO COAST SAVINGS
Only Gates has plants on both coasts so your order can be delivered promptly. With more than 35 years of experience, Gates is America's most trusted name in Sound Control.
We make superb Sound Controllers for more than 250 business machines, including all terminals and word processors.

Call us toll free 800-358-8265. In California, call collect 707-544-2711.

*Registered Trademark of Teletype Corp.

GATES

WE'RE QUIETLY IMPROVING THE BUSINESS WORLD
Gates Acoustinet, Inc., Box PP, Santa Rosa, California 95403

DIGITAL CONTROL AND AUTOMATION SYSTEMS

Local CRTs and printers at the central site will also serve in general system monitoring and other functions.

Alarm receipt and dispatch functions will remain within each borough. Two concentrators—using Digital Equipment Corp PDP-11/34 computers—at each remote site will control message traffic to and from the central site (Fig 6). One computer will always be online, the other on standby. A switching and system control console will determine which concentrator is active and direct traffic to it. However, control and operation of the concentrator and switching equipment, as well as all system maintenance, will be initiated from the central site.

The remote concentrators will automatically provide information to the central site CPU on component failures. Therefore maintenance will be initiated without action from remote site personnel.

Standardization will be maintained on all remote site installations. Equipment interfaces and equipment will be identical for each site.

The centralized system will also be designed and implemented by Bradford National Corp, under the direction of project manager Ronald Scherma. Four phases proposed are system design, central site implementation, simultaneous remote site implementation, and interconnection of central and remote sites and the firehouse teleprinter network. A time schedule of 36 months is predicted for completion of all four phases.

Circle 160 on Inquiry Card

DC&AS BRIEFS

Operators in Multistation System Are Instructed by DCC

In a direct computer control (DCC) system offered by Ragen Precision Industries, Inc, N Arlington, NJ, multiple stations automatically supply components to be inserted by an operator who is directed by a precision digitally controlled projector that beams an arrow onto the board, indicating the location, orientation, and polarity of the component. Computer-stored programs, which replace use of punched tapes, are stored, cataloged, and edited and are assignable to equipment stations. Up to seven elements can be included in a system: a processor which is a programmable logical control unit; a disc drive which stores station operating commands and data; and—at each station—operator controls, a digitally controlled articulated projector, an automatic component delivery system, a numerical operation number readout, and auxiliary signal light logic. □

CIRCLE 41 ON INQUIRY CARD

Ramtek's new MICROGRAPHIC™ terminal gives you color, intelligence, graphics, and alphanumerics at a price you can afford.



Color and smarts don't cost a lot anymore.



Here's great resolution and a bright, flicker-free display on a matrix of 512 elements by 256 lines in a terminal that's easy to program to your requirements.

No longer do you have to put up with poor resolution in economy-priced terminals. Ramtek gives you a combination of true graphics—such as vectors, conics, plots and bar charts—and high-speed alphanumerics with a high-resolution industrial-quality monitor. You can choose two sets of 8 colors for both graphics and alphanumerics. Dual and split screen capability too, with all the price/performance benefits of raster scan technology. And the independent alphanumeric refresh offers you single-character addressability within a visible matrix of 25 rows of 80 characters that are bright, crisp, sharp, and well defined. The refresh memory also allows selective erase, modification, and update.

The MICROGRAPHIC terminal is controlled by a powerful Z-80 microprocessor with up to 28K bytes of PROM and 16K bytes of RAM. Ramtek's control software gives you TTY compatibility and high-level graphic functions commanded by ASCII text strings. Choose from an extensive list of options such as additional serial I/O ports, alphanumeric overlays, programmable fonts, and packaged software.

Best of all, you'll find Ramtek gives you an affordable price, depending upon your individual requirements. Find out more by contacting us. We're Ramtek, 585 N. Mary Avenue, Sunnyvale CA 94086. In a hurry? Pick up the phone and call us. We'll tell you why you can afford color and smarts.

ramtek

Our Experience Shows

REGIONAL OFFICES: Sunnyvale, California (408) 732-3572—Dallas, Texas (214) 422-2200—Huntsville, Alabama (205) 837-7000—Cleveland, Ohio (216) 464-4053—Stamford, Connecticut (203) 348-8804—Washington, D.C. (703) 960-3550—Europe (0611) 595980

CIRCLE 42 ON INQUIRY CARD

Mini/Micro77

THE MINICOMPUTER/MICROCOMPUTER CONFERENCE AND EXPOSITION

DECEMBER 6–7–8 • CONVENTION CENTER • ANAHEIM, CALIFORNIA

CONFERENCE SESSIONS

TUESDAY

MORNING

Small Business Systems
Organizer: Don Schnitter, Basic Four Corp.

Trends in CRT Terminals
Organizer: To be announced

AFTERNOON

Small Disk Memory Trends
Organizer: Henry T. Meyer, CalComp

Buyer Be Aware: How Reliable and Flexible will Future Systems Be?
Organizer: Edward J. Bride, The Conference Co.

Low Cost Microcomputers in Business Applications
Organizer: Adam Osborne, Osborne & Assoc.

WEDNESDAY

Trends in Printer Development
Organizer: Neil Kleinman, International Data Corp.

Intelligent Applications of Minis in the Small Business Environment
Organizer: John Kirkley, Datamation Magazine

Criteria Used in Selecting & Evaluating a Minicomputer
Organizer: Joe Baker, Robert W. Baird Co.

How to Keep an On-Line System from Crashing
Organizer: Neil Kelley, Infosystems Magazine

Application of Microcomputers to Military Avionics
Organizer: Joe Genna, Delco Electronics

Trends in Mini/Micro Software
Organizer: Joe DeVita, Computer Automation

THURSDAY

OEM Peripherals in End-User Systems: The Current View
Organizer: George King, Benwill Pub. Co.

Distributed Data Processing
Organizer: Roger Billings, Billings Computer

Getting Into the Microcomputer Business
Organizer: Robert S. Jones, Interface Age Mag.

Computer Law
Organizer: Richard L. Bernocchi, Irell & Manella

Transaction Processing with Networks
Organizer: Elton Sherman, General Automation

NOTES:
1. **Morning Session — 9:30 - 12:00 noon**
   Afternoon Session — 1:30 - 4:00 p.m.
2. **All Sessions will be held in the Anaheim Convention Center**
3. **Monday, December 5 is IEEE Career Day. Contact: Vincent J. Giardina (201) 981-0060**

LIST OF EXHIBITORS (as of October 1)

E & L Instruments
MuPRO
Micro Computer Systems
Optical Electornics
AMPEX
Data I/O
Applied Computer Systems
Okidata
Artec Electronics Corp.
Qantex
Cahners Publishers
Telefile Computer Products
American Microsystems
Newman Computer Exchange
Computer Magazine (IEEE)
Monolithic Systems Corp.
Electronic Representatives Assoc.
Anderson Jacobson
Digital Systems
Logical Services
Computerworld
Micro Communications
Publishers for Conventions
Alpha Data
Shugart Assoc.
Sola Electric
Matrix Publishers
Wyle Distribution Group/ Liberty Elmar (Intel, Motorola, Fairchild, Signetics, Standard Power, Allen Bradley, Corning, Sprague, ITT Cannon)
Biomation Corp
Sord Computer Systems
Dataflux Corp.
Hughes Aircraft Co.
Pro-Log Corp
Zilog
Digital Equipment Corp.
Mini Micro Systems
Teletype Corp
Applied Digital Data (ADDS)
Printronix
MDB Systems
Systems Furniture
Data Systems Design
Basic/Four Corp.
Ball Brothers Research Corp.
Lear Siegler Inc./EID
Minicomputer Accessories
Ex-Cell-O Corp/Remex Div.
Sybex, Inc.
Memorex
Avnet Electronics
Terminal Rentals
Interdyne
Intermec
Intel Corp
Addmaster Corp
Megatek Corp
The Digital Group
Infosystems Magazine
Calex
Parsons Mfg. Corp.
Ai Electronics Corp.
Triple I
Hamilton Electro Sales (Motorola, National, Intel, Burr-Brown, Shugart Assoc., Ryan-McFarland)
General Robotics Corp.
Computer Automation
Tally Corp.
EECO
First Data Corp.
Calcomp
Microdata Corp.
Electronic Memories & Magnetics (EM&M)
Wangco
Applied Data Communications
Tandberg Data
PCC Pertec
Datamation
Computer Roomers
Computer Decisions
Interface Magazine
Elmatex International
Raymond Engineering
Trimm Enclosure Prod.
Pfystar Microcomputer Products
Diva
Educational Data Systems
CMP Publications
Computer Design
Tektronix
Centronics
Cherry Electrical
Benwill Publishing Corp.
Sybex
Iasis
Cipher Data Products
Commodore Bus. Machines
International Microsystems
Texas Instruments
Pacific Telephone Co.
Newport Data Systems
Problem Solver Systems

(More companies are being added on a daily basis)

Conference Program Chairman: Dr. L.A. Lotito (Computer Automation)

Exhibits Committee Chairman: William Handel (Nigbert Corporation)

Please type or print

To: MINI/MICRO COMPUTER CONFERENCE AND EXPOSITION
5528 E. La Palma Avenue, Suite I, Anaheim, CA 92807, Phone: (714) 528-2400

My Primary Interest Is:

☐ **Attending.** Please send me a Preview Program listing information on sessions/papers, exhibitors, and hotel reservations.

☐ **Exhibiting.** Please send a copy of the Exhibit Prospectus.

Name_____

Title_____

Company_____

Address_____ M/S_____

City_____ State_____ Zip_____

TIME SHARE REMOTE BATCH ONLINE OFFLINE

Best Graphic Problem Solvers in the Field

When **SPEED** is a problem let the CØMPLØT® DP-11 Digital Plotter show you greater throughput with 4,000 steps per second (240,000 per minute). Plus quiet operation thanks to our unique "micro drive™".

RESOLUTION is our solution. You get accurate, reproducible charts and plots with our 1,000 steps per inch plotter. Switch selectable resolutions of .005", .0025", .002", and .001" or in metric you have .1mm, .05mm, .04mm and .02mm.

OPERATION is no problem, it's **EASY PLOTTING** because control is via our PTC-5A, a significant advance in plotter controllers. Both remote time-sharing and online operation are simplified. Microprocessor based, it provides automatic detection and correction of data transmission errors, local generation of alphanumerics, circular buffer memory to accommodate greatly compressed plot codes, operates at 110, 300 or 1200 baud and adapts to IBM 5100, HP 9825, Wang 2200 calculators as well as the DEC PDP-11, Data General NOVA/Eclipse, HP 3000 Series, and other computers. Both plotter and controller are **RELIABLE.** Ideal for engineering, scientific, financial and business people to use for such applications as N/C tape verification, load & strain plots, contour maps, isometric piping drawings, subdivision plats, financial graphs and many, many more. Write for brochure today.

houston instrument | **THE RECORDER COMPANY** | DIVISION OF BAUSCH & LOMB

ONE HOUSTON SQUARE (at 8500 Cameron Road) AUSTIN, TEXAS 78753
(512) 837-2820 TWX 910-874-2022 cable HOINCO
TELECOPIER
EUROPEAN OFFICE Rochesterlaan 6 8240 Gistel Belgium
Phone 059/277445 Telex Bausch 81399

®A REGISTERED TRADEMARK OF HOUSTON INSTRUMENT

*USA DOMESTIC PRICE ONLY

For a demonstration, circle 43 on Inquiry Card.
For literature, circle 44 on Inquiry Card

New! DATUM Tape System for IBM Series 1!

Series 1 users can now add mag tape memory capability to their Series 1 (Models 3 or 5) installation! The new DATUM seven- or nine-track system permits recording densities of 200 bpi NRZ through 1600 bpi, phase-encoded. Speeds: from 12.5 ips through 125 ips. As many as four transports can be used.

Individually driven tape drive I/O ports. Read-after-write parity checking. Quartz-crystal-generated timing. Interfaces to industry-compatible drives.

The system incorporates the new DATUM "Universal User's Adapter," a device that allows connection of external devices to the Input-Output bus of Models 3 or 5 of the IBM Series 1 computers. The Adapter operates in the "cycle -steal" mode while exchanging 16-bit words with the computer. With this Adapter, Series 1 users can tailor their system to their own exact requirements, even to the extent of interconnecting several computers.

Diagnostic and operational software is included with each system. Color-coordinated cabinets can be ordered. Service and installation are offered throughout the U.S. Deliveries are 90 to 120 days ARO.

CIRCLE 45 ON INQUIRY CARD

Peripheral Products Division
1363 S. State College Blvd.
Anaheim, California 92806
TWX: 910/592-1289 • 714/533-6333
Telex 68-5579

datum inc



Available digital processing technologies and key design tradeoffs are discussed for the rapidly emerging field of computer voice response systems. These techniques are implemented to develop an operational application

Design Guidelines for a Computer Voice Response System

Paul Thordarson*

Input-Output Computer Services, Incorporated
Cambridge, Massachusetts

The field of computer voice response systems has been developing rapidly in response to the need to structure future computers to communicate in a manner that is natural for the user. For instance, upon suitable user interrogation, computer-driven peripherals could respond directly in spoken words—the ultimate in machine-to-man communication. The input device needed to access such a computerized system, the ordinary dial or touch-type telephone, is already installed in millions of homes and businesses for immediate use by "trained" users. Even today, one can enter a 7-digit number and listen to voice recordings of the latest weather report, stock report, or time of day. These systems communicate by voice in one direction—from machine to user—upon coded keypad entry.

To enable designers to choose the best method for structuring machine-to-person voice communications, techniques and implementation considerations pertinent to such a system are discussed. First, various technologies available to make a computer "speak" are described. Second, some design tradeoffs to be considered in developing a voice response system are analyzed. Finally, an operational implementation of a computer voice response system for a real-world application—an automated weather bureau for the general aviation public—is presented.

Voice Response Technology

Computer voice response (CVR) systems consist of a data base containing a collection of individual words or phrases (a vocabulary) and some means of assembling these words or phrases into meaningful responses (Fig 1**). The exact format of the vocabulary varies substantially among the existing technologies. In general, the more compact the representation for speech, the more complex the recording and reproduction processes become.

Current technology available for CVR systems can be classified under two very broad categories: waveform coding and analysis/synthesis. Waveform coding represents a signal by recording its amplitude while it varies in time. Analysis/synthesis records a set of parameters, such as frequency content, derived from the waveform. Both systems vary greatly in complexity and performance, so that design tradeoffs can be highly involved.

Waveform Coding Systems

Waveform coding systems produce voice output using recordings of human speech. A vocabulary of individual words and phrases is recorded and entered into the computer. Typically, each word is entered as an individual file or record in a large data base. Entire sentences are "spoken" by retrieving required individual words and phrases from the vocabulary and

*Mr Thordarson is currently employed by Digital Equipment Corp, Maynard, Mass.

**From Rabiner and Schafer, Copyright 1976 by IEEE.



Fig 1 All-digital voice response system. This system requires analog-to-digital coder for obtaining digital representation of speech signal. Similarly, appropriate digital-to-analog decoder converts digital representation to analog signal. Vocabulary, in digital format, is first processed and then stored in digital memory. Access to vocabulary entries is performed by message composition system for correct sequence and presentation to output decoder (Courtesy of IEEE)

reproducing them in the proper sequence. Although both analog and digital techniques can be used for recording the speech, this article concentrates on digital recording techniques because they are more easily adapted to conventional computer hardware.

Digital waveform coding requires that the amplitude of the speech signal be sampled. Sampling is done using an analog-to-digital converter (ADC) which measures the signal amplitude at regular time intervals and produces a series of binary numbers representing that signal amplitude at each interval. For a sampled waveform, the highest frequency in the waveform which can be reproduced qualitatively is called the Nyquist frequency, which is equal to one-half of the frequency or rate of sampling. Experiments show that acceptable quality speech can be reproduced with a signal bandwidth of 3 kHz, thereby requiring a sampling rate of 6 kHz or greater.

Digital recording and reproduction of speech requires the circuit devices as shown in Fig 2. The input speech signal is first filtered to remove all frequencies in the signal above the Nyquist frequency (in this example 3 kHz), then sampled using a sampler and encoder—an ADC. A digital representation of the signal amplitude is produced every 166.7 μs (for a 6-kHz sampling rate); this representation is stored on the vocabulary storage medium, such as a disc, for later reproduction.

The reverse of the recording process, the reproduction process consists of first reading the digital representation of the waveform from the vocabulary storage medium. The retrieval component is a simple hardware device or retrieval software running on a general-purpose computer. Retrieved digital samples are converted to an analog waveform by a decoder, such as a digital-to-analog converter (DAC). This decoder



Fig 2 Digital recorder/reproducer. Speech signal is first filtered to remove high frequency components unnecessary for quality speech reproduction; cutoff frequency of filter is 3 kHz. Filtered signal is then sampled at rate at least twice cutoff frequency (6 kHz), and samples are stored on digital storage medium such as magnetic disc. Speech is reproduced by retrieving speech samples and decoding them by applying function which is inverse of the encoder function. Resulting signal is filtered to remove distortion introduced by sampling process, giving reproduction of original signal

applies the inverse of the encoder function to the samples to reproduce the original waveform. Finally, the reproduced waveform is again filtered by a 3-kHz lowpass filter to remove all harmonic components introduced by the sampling process.

All techniques for waveform coding resemble the system shown in Fig 2. Most systems use a sampling rate between 6 and 8 kHz. However, the number of bits recorded in the encoded speech samples varies greatly between systems. The waveform coding techniques to be reviewed here vary in bit rates from 10k to over 60k bits/s, and result in a factor of 6 change in the amount of data stored for any given spoken word. Therefore, the choice of encoding technique directly affects the size and throughput required of the storage medium. For example, the size and throughput required of the vocabulary storage medium are both six times greater at 60k bits/s than at 10k bits/s. However, encoding techniques which offer lower data rates require more complex encoding equipment. Choice of technique depends on whether the vocabulary is small, with encoding/decoding equipment representing most of the cost, or large, with vocabulary storage medium representing the largest part of the cost.

Pulse Code Modulation

Pulse code modulation (PCM) is the simplest and most widely known waveform coding method. Using a conventional ADC, encoded samples are a linear integer representation of the waveform amplitude; if signal amplitude doubles, the corresponding integer sample value doubles. Most ADCs produce a binary representation, although some may provide a decimal number encoded as a binary coded decimal (BCD) number.

Accuracy of the integer representation in a PCM waveform coding system depends on a quantity called the step size—the difference in signal amplitude represented by two successive integer sample values. For example, if in a PCM encoder the integer 14 represents a signal amplitude of 14 mV and the integer 15 represents a signal amplitude of 15 mV, step size for this encoder is 1 mV. Fig 3 illustrates a waveform and the encoded samples produced by a PCM encoder with a 1-mV step size and a sampling rate of 1 kHz. Sample values are shown as decimal integers; actual representation is binary.

Step size determines the smallest variation in the input signal which will produce a variation in the encoded samples. The smaller the step size, the more accurate the signal reproduction will be. Smaller step sizes, however, require a larger number of steps (ie, larger "greatest possible integer value" for an encoded sample) to ensure that the entire range of input signal values can be encoded. The largest possible value for the integer determines the number of digits (bits) in the binary value of that integer. For example, if an encoder with a 1-mV step size is used to encode signals which could vary from −1 to +1 V, encoded samples would have 2000 possible values. Since the binary number for decimal 2000 is 11 bits long, sample size in this example would be 11 bits. Sample size multiplied by sampling rate gives required data rate for the PCM system (ie, the number of bits which are processed in a unit of time in order to maintain voice output).

Although PCM systems are the simplest CVR systems to implement, their data rates are the highest. A sample size of at least 11 bits (data rate of 66k bits/s when sampling rate is 6 kHz) is required to achieve high quality speech reproduction. With this sample size, the distortion introduced by the sampling process is barely perceptible to the listener. Higher distortion levels are tolerable; however, a sample size of less than eight bits (data rate of 48k bits/s) will intro-



SAMPLE TIME (ms)	ENCODER OUTPUT
1	−83
2	−121
3	−53
4	28
5	75
6	165
7	112
8	50
9	−110
10	−62

Fig 3 Waveform encoded using pulse code modulation. Waveform is sampled by PCM encoder every millisecond (1-kHz sampling rate) using step size of 1 mV. Sample time and corresponding integer value of encoder output are listed in table. Integer corresponds exactly to signal amplitude in millivolts



Fig 4 Log PCM transfer characteristic. Response sensitivity of human ear is logarithmic; therefore, its "incremental" sensitivity is lower at larger amplitudes. Log PCM takes advantage of this characteristic by providing small step size at low signal amplitudes, and large step size at high amplitudes, thus increasing encoder resolution at amplitudes where ear's sensitivity is greater

duce more distortion than is acceptable by the majority of listeners.

A decrease in data rate can be achieved by using a variation on PCM called log PCM. In log PCM, step size is not constant over the entire range of signal amplitudes to be encoded. Rather, it increases as the signal amplitude increases. The transfer function (signal amplitude vs encoded sample value) for a log PCM encoder is shown in Fig 4. Note that encoded sample values are proportional to the log of signal amplitude. This encoding method is effective in reducing the data rate because the human ear's response to signal amplitude is also logarithmic. Sample size in log PCM should be seven bits or greater to achieve high quality speech reproduction.

Differential Coding

Data required to encode speech waveforms can be reduced by taking advantage of some inherent audio properties. One known property is that the greatest amount of signal energy in a speech waveform lies below the Nyquist frequency. This causes successive speech samples to exhibit a high degree of correlation. (The amount by which a signal changes between successive samples is likely to be less than the largest possible value the signal can have.) Because of this correlation, a smaller sample size is required to encode



Fig 5 Differential encoder and decoder. Encoder (a) produces difference signal d(n) by subtracting predictor output x'(n) from incoming audio signal. d(n) is encoded to produce digital sample value c(n) which is stored on vocabulary storage medium. Encoder also produces d'(n), which is d(n) rounded to nearest step size. d'(n) is summed with predictor output to produce x(n). Predictor uses x(n) to produce next value of x'(n). Optional logic component uses all previous c(n) values to adjust step size of encoder. Decoder (b) takes encoded samples and decodes them to produce difference signal d'(n). Logic component adjusts step size of decoder based on all previous values of c(n). Difference signal is summed with predictor output x'(n) to produce x(n), which is used for both audio output and for predictor input which is used to produce next value of x'(n)

a waveform if the difference between successive samples is recorded than if the exact value of the signal is recorded for each sample.

Fig 5 shows a generalized differential encoder and decoder. Encoding begins by computing the difference between the input signal voltage and the predictor voltage x′ (n). This difference is the signal d(n). The encoder converts d(n) to the digital sample c(n), which is recorded on the vocabulary storage medium; conversion occurs at the sampling rate. The encoder also produces the signal d′(n), which is d(n) rounded to the nearest step-size value. For example, if the step size is currently 1 mV, a value of 14.5 mV for d(n) would give a value of 14 mV for d′ (n). This is added to the predictor output voltage to produce the signal x(n), which is used by the predictor to calculate the next value of x′ (n). While the predictor can be a complex function, in most cases it is just a holding circuit whose transfer function is x′ (n + 1) = ax(n). The term "a" is a constant whose value is close to, but less than, 1. It represents any leakage or loss which may be present in the holding circuit. The logic component is present in some encoding methods and is used to adjust the step size of the encoder based on previous values of the digital samples c(n).

On decode the reverse of the above process occurs. Digital samples are retrieved from the vocabulary storage medium and are decoded to produce the difference signal d′ (n). This signal will be the same as the corresponding signal d′ (n) in the encoder. The logic component dynamically adjusts the step size based on previous values of c(n). Signal d′ (n) is added to the predictor output x′ (n) to produce x(n). Audio output signal x(n) is the reproduction of the signal encoded, and is also the input to the predictor which is used to compute the next value of x′ (n).

The simplest technique using differential coding is delta modulation (DM). In delta modulation, a signal is encoded using a 1-bit sample size. If input voltage is greater than the predictor value, a logic 1 is produced for the encoded signal value, and the predictor voltage is incremented; if less, a logic 0 is produced and the predictor is decremented. Sampling rates for DM are generally much higher than PCM encoding to improve sample-to-sample correlation and, therefore, the quality of the signal achieved with the 1-bit sample size.

The signal-to-noise (S/N) ratio of DM can be improved by adjusting the step size of the quantizer (ie, encoder). This improvement is achieved because the difference samples recorded in a differential encoding scheme also show some degree of correlation. That is, if difference sample "n" is large, it is very likely that difference sample "n + 1" will also be large. Therefore, it is possible to vary the amount the predictor voltage is incremented or decremented at each sampling interval in order to more accurately track the signal voltage. This encoding method is called adaptive delta modulation (ADM).

Data rates for the encoded speech signal can vary considerably in ADM and DM systems. The rate depends on the desired S/N ratio and, in the case of ADM, the sophistication of the algorithm used to vary the step size. One system implemented using an ADM algorithm was able to produce acceptable quality speech with a data rate of only 10k bits/s. The algorithm for controlling the step size, however, was complex and costly to incorporate.



Fig 6 Comparison of signal-to-noise (S/N) ratio to data rate for several encoding methods. Note that ADPCM gives S/N improvement of almost 10 dB over log PCM for corresponding data rates. Two random data points represent S/N ratio as perceived in listening tests rather than with signal measuring hardware. Point labeled "*" represents ADPCM with a 4-bit sample size (24k bits/s) and "+" represents 10k bits/s ADM. Note that S/N ratio of ADM as perceived in listening tests is almost 20 dB better than its value obtained with signal measuring hardware (Courtesy of IEEE)

A multibit quantizer permits sampling closer to the Nyquist rate. Using the encoder design for DM with a multibit encoder yields differential pulse code modulation (DPCM). If step size is allowed to vary as in ADM, the encoding method is called adaptive differential pulse code modulation (ADPCM). ADPCM has been found to produce quality speech using adaption algorithms which are simple and inexpensive to implement. Typical sample sizes are three or four bits, giving a data rate of 18k to 24k bits/s, respectively.

Various encoding techniques are compared in Fig 6*. The chart shows S/N ratio versus data rate in kilobits/second for three encoding methods: log pulse code modulation, adaptive delta modulation, and adaptive differential pulse code modulation.

*From Rabiner and Schafer, Copyright 1976 by IEEE.

In itself the S/N ratio is not the final indicator of speech quality. Each encoding scheme introduces its own particular type of distortion. While contributing to a decrease in the S/N ratio, the distortion may not reduce the understandability of the reproduced speech. For example, noise introduced in reproduction of sounds like "th" would detract from the objective S/N ratio; however, since the sound produced for "th" resembles white noise, many kinds of noise introduced by the encoding algorithm can go unnoticed. Two data points in Fig 6 show relative quality of the speech as perceived by listeners for 4-bit ADPCM (the point labeled "*") and for the 10k-bit/s ADM system cited earlier ("+").

Analysis/Synthesis Systems

Waveform coding methods deal with time sampling of audio waveforms. Modest data rate improvements can be achieved by using some statistical properties of typical waveforms. Much greater reduction in bandwidth can be achieved by encoding speech with parameters based on a model for human speech production—the analysis/synthesis methods. While the possible parameters which can be encoded are many, an example coding scheme based on a particular set of parameters provides a basis for understanding the general concepts.

Every spoken language consists of a set of fundamental sounds called phonemes. These fundamental sounds are strung together to form consonant and vowel sounds which make up the spoken language. For example, the vowel sound "i" as in "bite" is produced by the phonemes "ah" and "ee." Most languages consist of less than 200 phonemes, with the number in common usage ranging from 50 to 60. Slight variations can be given to each phoneme by changing the stress (eg, angry, calm, or happy) and duration (how long the particular phoneme takes to pronounce). Stress does not vary by much at the phoneme level; limiting the stress to four different values is adequate to cover most speech. Duration for most phonemes is covered by a range of 25 to 100 ms. Using 15-ms steps from 15 to 240 ms (16 steps) is sufficient to satisfy duration range requirements.

A data rate can now be determined for this encoding method. Each encoded value contains three parameters: the encoded phoneme, its stress, and its duration. Since the number of phonemes is less than 200, the phoneme is encoded as an 8-bit integer. Stress, which can be one of four possible values, is encoded as a 2-bit number. Duration can have one of 16 possible values, thus requiring a 4-bit integer. This method gives a total of 14 bits for each encoded value or sample. Since phonemes are typically greater than 25 ms in duration, the number of samples per second will be 40 or less, giving a maximum data rate of 560 bits/s for an analysis/synthesis system that uses phonemes as the encoding parameter. Although bit rates can vary according to the parameters selected for the waveform encoding, it is clear that they are at least an order of magnitude less than their waveform coding counterparts.

Analysis/synthesis systems also offer a great deal of flexibility. A given word in any language can vary considerably in sound, depending on the context, that is, whether it occurs at the beginning or end of a sentence, and whether the sentence is a question or a statement. In waveform coding methods, either one recording of a word must be used in all contexts, affecting the naturalness of the speech, or many different recordings of a word must be used, requiring more storage. In analysis/synthesis methods it is possible to adjust the parameters, such as stress, to fit the context the word is spoken in.

While analysis/synthesis methods offer promise for both low bit rates and high flexibility, they suffer from some serious limitations. First, most equipment is more expensive than for waveform coding techniques. Second, while the speech quality is acceptable, its "unnatural" or "inhuman" sound may negatively affect understandability since listeners may pay more attention to the sound of the speech than to what is being said. Finally, methods for taking advantage of the inherent flexibility are still in the laboratory phase. Therefore, waveform coding techniques will continue to dominate the commercial market for at least the near future.

System Selection

The decision to buy or design a system for a particular application is made by examining the application in terms of the following requirements: vocabulary size, expected number of users, mode of interaction, and how the computer voice response system fits with existing applications (system structure).

Vocabulary Size

Vocabulary size is the most important variable in a CVR system. Its size determines the amount of storage required, and affects the decision of which waveform coding technique to use. A small vocabulary will indicate that a simple waveform coding technique, such as PCM, should be used since encoding and decoding hardware will represent most of the system cost. If a large vocabulary is chosen, a more complex system, such as ADM or ADPCM, can be used since the interface cost may be recovered through savings in storage requirements.

Vocabulary requirements for a given application can vary greatly; however, a minimum set of words and phrases exists which will handle the job. Any additional vocabulary usually is added merely to make a system more convenient to use. The upper limit on size

will be determined by evaluating the system user and how much inconvenience he will tolerate.

Minimum vocabulary size is relatively easy to determine. For example, consider an inventory control system which accepts orders for particular items by part number and updates the available inventory for that item. A minimum vocabulary might contain 10 digits (0 to 9) to record part numbers, quantities, and prices; and several phrases to guide the user through the dialogue, such as "enter part number," "enter quantity," or "the price for the selected item is." Ten such phrases should be adequate. The resulting vocabulary would contain the 10 digits (0 to 9) and the 10 phrases. Digits require roughly 0.67 s each to speak, while the phrases may average about 2 s each. Thus, 10 x 0.67 or 6.7 s of speech are required for the 10 digits, and 2 x 10 or 20 s of speech for the 10 phrases, making the entire vocabulary requirement equal to 26.7 s of speech. Even when using PCM at 60k bits/s, total vocabulary storage requirement is only 200k bytes—a fraction of the storage on even the smallest disc systems currently available.

Maximum limit on vocabulary size is somewhat harder to determine, since the vocabulary for the example system could be increased for convenience without adding any new capabilities. For example, several phrases could be added to the vocabulary to ease the handling of incorrectly entered data. Actual part names, such as "size 14 rubber grommet," could be added to the vocabulary to give additional confirmation that the data are correctly entered. Including the entire alphabet allows spelling of abbreviations. For an inventory of 500 items, the additional vocabulary consists of about 10 extra phrases or 2 x 10 s, the 26 letters of the alphabet or 26 x 0.67 s, and 500 part names at about 2 s each for 500 x 2 s. The total vocabulary size in seconds of speech, including the 26.7 s from the minimum vocabulary, would be 1064 s. At 60k bits/s, the vocabulary would require approximately 7.98M bytes. Changing to ADPCM at 24k bits/s would lower this requirement to 3.19M bytes, a savings of 4.79M bytes. Additional cost of ADPCM decoding hardware would be made up if the saving in storage avoids the purchase of an additional disc drive.

Number of Users

A CVR system might be expected to support a number of users simultaneously. The number of users affects the throughput required from the vocabulary storage medium and total cost of decoding hardware. By determining the throughput required for voice response, the decision to use the unused capacity of existing system storage or a dedicated storage device can be made. Hardware costs for the decoders are easier to determine, since the cost is proportional to the number of decoders.

The number of simultaneous users to support is more difficult to determine than the vocabulary size. While most of the considerations are specific to each application, some general ones are outlined below. System usage can be divided into periods of time which are called "user sessions." Each session begins when a user gains access to the system and ends when the desired operations have been completed. In an inventory control system, for example, a session consists of a salesman accessing the system by typing a code or password and then entering and verifying several transactions.

Based on the particular application, the length of a typical user session is estimated. This estimation, coupled with the maximum number of user sessions that can be expected within a given period of time, determines the average number of sessions that might be active. Probability shows that the number of sessions concurrently active can exceed this average, since a session can begin at any random time a user gains access to the system. The exact number of users a system is designed to support must be based on expected average use and a factor to handle times when the load exceeds the average. In general, the concept is to attempt to guarantee that x% of all users will find the system available on their first attempt to access it. The exact value assigned to "x" depends on how costly waiting can be. In any system where the general public is the principal user, x must be close to 100 since excessive waiting time can mean lost customers.

Mode of Interaction

CVR systems can offer many modes of interaction. Level of interaction can vary from almost none, such as a single voice output for reporting status or emergency situations, to very heavy, as in the inventory control system.

Interaction can be classified as being in transaction mode or in batch mode. In transaction type interactions, the entire session consists of short user requests followed by short answers from the system, or the reverse. The amount of voice output occurring between user inputs will be on the order of a few seconds. The inventory control system represents a transaction mode interaction.

Batch type interaction involves a brief dialogue between the machine and user to determine what response is required. At the end of the dialogue, the system performs an information-search action, and then usually provides a long verbal report to which the user listens. The only interaction during this period may be special functions to permit pauses in output to give the user time to digest the information, or to skip information which may not be of interest. An example of batch mode interaction is a medical history system. Initial dialogue would determine the patient, data desired, and beginning and end dates for the data. After this brief dialogue, data reports would be given with no further interaction on the user's part.

Also related to mode of interaction are the physical devices used for the interaction. At one extreme, all users would have terminals specially designed to precisely fit the dialogue. At the other extreme, users would access the system using ordinary dial or touch-type telephones. In the latter case, dialogue would have to be specially tailored to the limitations of using an ordinary telephone as an interactive data entry terminal.

Use of telephones also poses data entry problems since the interaction must be structured to the telephone, rather than the reverse. Among the factors to be considered are problems imposed by a restricted character set, user frustration caused by excessively complex dialogues, and excessive amounts of user input before positive or negative feedback is obtained from the system. Unfortunately, since these user areas are very subjective and human-oriented, definite system recommendations beyond practical experience can not be made. While these factors have little effect on the overall design of a system, they do have a strong effect on user acceptance of the system.

System Structure

The above considerations define a CVR system as it appears to the user. The designer must also consider how the CVR system must interface to existing applications, both hardware and software. To do this, all demands placed on a system must be examined to determine the impact of adding voice response.

First to be examined is the number of decoder interfaces or voice channels required. This number is determined by number of users and mode of interaction. If batch interaction is planned, it is very likely that all users may require voice output at the same time. Therefore, number of channels will equal number of users. However, if the mode is transaction, and the length of a typical response from the system is comparable with the delay which can be tolerated by the user, a channel may be multiplexed over several users. A channel is assigned to a particular user for the duration of a response from the system; when the response is completed, the channel is free to be assigned to another user. Number of channels required is determined by considering the length of a typical response versus the time between responses, and the maximum tolerable delay. Exactly how these factors combine depends on the particular application; specific guidelines beyond practical knowledge are not conclusively adaptable. It should also be noted that multiplexing a hardware channel over more than one user requires sophisticated software techniques. Therefore, the expected cost of developing and supporting the software in this case is a major consideration in determining the feasibility of such an approach.

Next item to be examined is the vocabulary storage medium. Amount of storage required is determined directly by vocabulary size and encoding technique. Performance required from the storage is the product of the number of channels times the data rate for the encoding technique employed. This product value gives total throughput required from the storage medium. Throughput for a given medium is a function of its access time and the method used for buffering the device. Again, exact throughput is determined by the particular configuration, and specific guidelines cannot be readily derived.

After these factors have been established, the choice must be made between two basic approaches. First, the designer can add all required peripherals and software to an existing system by utilizing "excess" throughput available in the system. The second approach is to design a voice response "frontend" processor to handle all user input and voice output. The host computer is required only to retrieve information needed by the frontend processor.

Response time is a major item which must also be considered. A user can tolerate a minor amount of delay between making a request for information and the time when it is obtained. However, once the response begins, it must continue without interruption, because otherwise pauses can occur in mid-sentence or even in mid-word. This means that all input/output (I/O) operations required by the CVR system, such as disc accesses, must be given higher priority than other access requests; this could adversely affect response time of the application.

In general, using a frontend processor has the advantage of better response time and greater future expandability. Its major disadvantage is cost. The proper choice lies in carefully applying the above considerations to the particular application.

Automated Weather Information System

An automated weather information system has been developed by Input Output Computer Services, which typifies the implementation of a CVR system. This system is designed to serve as part of a Dept of Transportation development effort called the Flight Service Station Automation (FSSA) Program. Normally, general aviation users, such as private pilots, obtain weather information required to plan a flight by calling a Flight Service Station (FSS) attendant who must first access available weather information (eg, maps and reports) and then vocally provide the caller with the needed information. The FSSA program was initiated to curb projected future manpower requirements and associated costs for FSSs by using a CVR system to provide an interactive weather information system. Users would obtain the latest weather reports using a touch-type telephone as a data entry device. After keying in flight locations and other information required to obtain a report, the automated system would return with the desired weather report.

Vocabulary Size

The FSSA system needed a vocabulary size sufficient to adequately describe aviation weather. It had to include names of reporting stations and airports, cloud types, wind conditions, numeric entries, and words and phrases required to convey this information in common English language. In addition, the user-computer dialogue was to be guided by a series of instructions from the computer, all of which were to be stored as single phrases rather than individual words. These requirements resulted in a vocabulary size of 3500 to 4000 items. Most were individual words averaging a duration of about two-thirds of a second each.

Number of Users

The FSSA system was designed to support up to ten simultaneous users. This number was chosen arbitrarily, since the system was intended to prove the feasibility of a multiuser voice response system. Usage statistics, which would be collected online during system test would be used to more accurately determine the number of users for future systems.

Mode of Interaction

Users interact with the FSSA system using touch-type telephones as data terminals with their keypads serving as data entry devices. Alphanumeric data are entered using a special entry protocol which requires two keystrokes to define a single character. Input editing functions, such as "cancel last input," are also available.

A user session with the system consists of the dialogue to determine what information should be retrieved and the retrieval during which the weather information is presented to the user. Dialogue begins with a request for location codes—3-character abbreviations for weather reporting stations and airports. These codes entered by the user are typically points of departure and destination for a flight, as well as selected locations along the route of flight. Location codes are entered one at a time with a confirmation after each code, followed by a selection of the type of weather information required. In all, nine types of reports, such as surface observations, winds aloft, and weather warnings, are available. For some weather reports, only this information is required, and the dialogue would end. Other reports, however, require additional information; for example, winds aloft requires an altitude and a time, which would be requested at this time.

Weather reports are presented during the retrieval phase. At this time, the only interaction between user and CVR system is a set of special function commands. These commands are used to customize the presentation of data to the user's needs. Available functions include skipping reports, rereading reports, pausing, and ending the retrieval phase.

This mode of interaction is of the batch type described previously. Dialogue occurs at the beginning to select information to be presented, followed by the actual presentation when the user does little except listen. In this particular system, a brief dialogue could easily cause 15 min or more of a report to be presented for one user.

System Structure

First step in determining system structure was to choose the method of voice output and then to determine the demands for system resources that this selection would make. A study of technology available for CVR led to the selection of waveform coding over analysis/synthesis. Analysis/synthesis techniques, while holding future promise, cannot presently compete with the waveform coding technique for simplicity and speech quality.

Choice of the particular waveform coding technique was based to some extent on vocabulary size requirements. As mentioned, the vocabulary consisted of about 4000 words and phrases, each 0.67 s in duration. At a 6-kHz sampling rate, this results in about 4000 samples/word, or a total of 16M samples for the entire vocabulary. Selection of a coding technique with a small sample size was desirable, since a reduction of just 1 bit/sample would save 2M bytes of vocabulary storage. In addition, reduction of sample size decreased the throughput requirements for the vocabulary storage medium, which also lowered cost.

The waveform coding technique chosen was adaptive differential pulse code modulation (ADPCM) with a 4-bit sample size. ADPCM offered a data rate that was relatively low (24k bits/s), and a decoder interface which was simple to construct. Simplicity refers to the fact that the interface to the computer's I/O bus accounted for a sizable portion of the total cost of the decoder interface. Since the I/O bus interface was required regardless of the particular decoding method used, changing to a method simpler than ADPCM would not substantially reduce the cost of the interface.

Data rate for ADPCM could now be used to determine required performance for the vocabulary store. First, since the FSSA used a batch mode of interaction, it was not feasible to multiplex ADPCM interfaces over many voice channels. Therefore 10 interfaces would be used, giving a composite data rate of 240k bits/s for all 10 channels. This data rate, however, had to be combined with other factors such as available core buffer size and the likelihood of reading only partial disc blocks (a spoken word rarely occupies an integral number of blocks). The calculations were highly complex and are beyond the scope of this discussion.

Remaining functions (touch-type telephone signal decoding and message handling) required special interfaces and software, but had little impact on overall performance requirements. System structure was then dictated by the voice response requirements. Therefore,



Fig 7 10-user computer voice response system. Host computer receives latest weather information from network link to national Weather Message Switching Center. Host maintains this information in data base used by many applications programs, including graphics displays, terminal printers, and voice response system. Frontend processor "fields" user requests for weather information and retrieves this information from host via communications line. Output data are then "spoken" using vocabulary of weather terms resident in frontend processor

a dedicated frontend processor was chosen to ensure the response time critical for voice output without substantially impacting response time for other applications. This resulted in a system with a voice response frontend computer handling all user-machine dialogue functions attached to a host computer. The host maintained the data base of current weather information, and handled the selective retrieval of that information (Fig 7). This configuration relieves the host of much of the work of supporting the voice response system, freeing it for other applications.

Conclusions

Computer voice response offers the system designer a means of making a complex machine system available to many unskilled users. The required data entry terminal (an ordinary telephone) is commonly available. While limited by human speech's serial presentation and lack of hard copy, the automated weather information system implementation shows that highly technical applications can be developed and put online quickly for users with no computer training.

While this discussion has presented some general guidelines for designing a CVR system, specific use of the guidelines is highly application dependent. Many issues are, therefore, addressed in only general terms. The automated weather information system serves to illustrate how the guidelines might be implemented in a real-world situation.

Computer voice response holds a promising future for many applications where the principal user is the nontechnical public. Waveform coding systems will continue to dominate applications which require immediate acceptance by the user. Analysis/synthesis systems require further advancement before they achieve their full potential.

Bibliography

T. G. Homsby, Jr, "Voice Response Systems," *Modern Data*, Nov 1972, pp 46-50

L. R. Rabiner, R. W. Schafer, "Digital Techniques for Computer Voice Response: Implementation and Applications," *Proceedings of the IEEE*, Apr 1976, pp 416-433

R. W. Schafer, L. R. Rabiner, "Parametric Representations of Speech," *Speech Recognition*, Academic Press, 1975, pp 99-150

"Special Issue on Man-Machine Communication by Voice," *Proceedings of the IEEE*, Apr 1976



Paul Thordarson is a senior software engineer for Digital Equipment Corp. Previously, he assisted in development of a single-user prototype of a multiuser voice response system, and was the leading team member responsible for the initial engineering design of the multiuser system. He holds a BSEE degree from the Massachusetts Institute of Technology.

Put our new UART and BIT RATE GENERATOR together and what have you got?



The first programmable CMOS Communications System.

With the Harris HD-6402/6402A CMOS/LSI, and HD-4702/6405 CMOS Bit Rate Generator, you can convert parallel data to serial and back again asynchronously, substantially reducing the amount of interconnect in your data acquisition systems.

Now, all it takes is two lines to connect terminals to computers, for example, instead of the spaghetti of wire used in older systems.

And, only with Harris do you enjoy the benefits of all-CMOS technology. Like less power consumption, permitting remote, hand-held battery-operated systems. Faster speed. Fewer and smaller components for added economy in equipment costs. Plus full temperature ranges, including military.

The Harris HD-6402/6402A, designed to replace the older and slower P-channel types, is the industry's first CMOS UART. It features an industry standard pinout. Single power supply—operates on 4 to 11 volts. And it's fast... 125K Baud... the *fastest* UART in operation today.

The Harris all-CMOS Bit Rate Generator provides the necessary clock signals for the UART. The HD-4702 generates 13 commonly used bit rates, while the HD-6405 provides two additional bits and consumes significantly less power, with no pull-up resistors.

If you've been waiting for CMOS for your modems, printers, peripherals, and remote data acquisition systems designs, your wait is over! Now Harris technology has something you can really work with. And you can start *today!*

For full details, call the Harris Hot Line, or write:
Harris Semiconductor, P.O. Box 883, Melbourne, FL 32901.



HD-4702/6405 FEATURES

- CMOS
- TTL Compatible
- Low Power Dissipation: 4.0mW TYP. (6405); 4.5mW TYP. (4702)
- Conforms to EIA RS-404
- One unit controls up to eight transmission channels
- On-chip input pull-up circuit (4702 only)
- 16 pin Cerdip and Epoxy dual-in-line packages
- Second source available

HD-6402/6402A FEATURES

- CMOS
- Operation from D.C. to 4.0MHz
- Low power—TYP. 10 mW @ 2.0MHz
- 4V to 11V operation
- Programmable word length, stop bits and parity
- Automatic data formatting and status generation
- Compatible with industry standard UART's
- Second source available

HARRIS HOT LINE!
1-800-528-6050, Ext. 455
Call toll-free for phone number of your nearby Harris sales office, authorized distributor or expedited literature service.

Harris Technology... Your Competitive Edge

HARRIS
SEMICONDUCTOR
PRODUCTS DIVISION

CIRCLE 46 ON INQUIRY CARD

Your new Smart Box

All you do is plug it in

What "point-and-push-the-button" sophistication did for photography, our new Smart Box does for desktop punched tape readers. All you do with the new Decitek Model 262D9 is plug it into your RS232C port.

Then, using the DIP mode selector switch on the rear panel of the Smart Box you can select data transmission rate, word length, parity and number of stop bits. You also have the full range of Baud rates from 110 to 9600 as options.

And our new Smart Box configures to RS232C, current loop or parallel I/O.

Additional program functions all internally programmable by jumpers. You also get patented dual-sprocket drive, 25,000 hour light source with fiber optics, and stepper motor drive—all proven Decitek reader advantages.

That's a lot of desktop tape reader. There's not another one on the market that gives you this kind of flexibility with our Smart Box's plug-in simplicity.

But your biggest surprise will be the reasonable cost of the Smart Box. It would be smart of you to find out about that right now. Call or write. We'll be happy to give you complete facts and figures.

When reading matters

DECITEK

A Division of Jamesbury Corp.
250 Chandler Street, Worcester, Massachusetts 01602 U.S.A.
(617) 798-8731

CIRCLE 47 ON INQUIRY CARD

Multiserver queuing models, coded for a handheld calculator, permit the evaluation of computer system performance, using powerful decision-making simulations to evaluate equipment, judge prospective reconfigurations, and modify existing operations

Computer Queuing Analysis On a Handheld Calculator

Ronald Zussman

Securities Industry Automation Corporation
New York, New York

Queuing theory can be practically applied to estimating computer performance and locating system bottlenecks. This is demonstrated by a generalized multiserver queuing model coded to run on the Texas Instruments SR-52 handheld calculator. The model is interactive so that effects of prospective design changes can be evaluated immediately, allowing an analyst to make the iterative design decisions required to optimize system effectiveness. Having the model preprogrammed for a portable calculator further increases its availability and convenience.

Where a complicated problem can be separated into a number of basic queuing situations, it is often possible to use this calculator model instead of an exten-

Multiserver Queuing Equations

Input Parameters

Average arrival rate: λ

Average service rate: u

Number of servers: s

Performance Attributes

Facility utilization: $U = \lambda/us$

Probability of finding no items* in the system:

$$P(0) = 1/\left(\left(\sum_{N=0}^{s-1} (\lambda/u)^N/N!\right) + (\lambda/u)^s/(s!(1-U))\right)$$

Probability of finding n items* in the system:

$P(n) = P(0)\ (\lambda/u)^n\ (1/n!)$,$n < s$

$P(n) = P(0)\ (\lambda/u)^n\ (1/(s!\ s^{n-s}))$,$n \geq s$

Probability of finding all servers busy (ie, that $\geq$ s items are in the system):

$$B = \sum_{n=s}^{\infty} P(n) = (\lambda/u)^s\ P(0)/(s!(1-U))$$

Average waiting time in the queue:

$TW = B/(su(1-U))$

Average system response time (ie, total time an item spends in the system):

$T = TW + 1/u$

Standard deviation of system response time:

$\sigma(T) = \sqrt{B(2-B) + s^2\ (1-U)^2}\ /(su(1-U))$

$\sigma(T) = \sqrt{B(2-B) + s^2\ (1-U)^2}\ TW/B$

Probability of waiting time in the queue exceeding t:

$P(TW>t) = B\ e^{-su(1-U)t}$

Average number of items in the queue:

$\overline{Q} = \lambda(TW)$

Average number of items in the system:

$\overline{N} = \lambda(T)$

*Items in the system either reside in the queue or are being processed by one of the servers.

TABLE 1

SR-52 User Instructions for Multiserver Queuing Model

Step	Procedure	Enter	Press	Display
1.0	Load program card (sides A and B)			
2.0	Input parameters:			
2.1	Average arrival rate	λ	STO 0 1	
2.2	Average service rate	u	STO 0 2	
2.3	Number of servers	s	STO 0 3	
3.0	Calculate P(0) before proceeding to Step 4			
3.1	Probability that 0 items are in the system*		P(0)	Probability
3.2	Facility utilization of each individual server		U	Utilization
4.0	Request the following in any order			
4.1	Probability that n items are in system*	n	P(n)	Probability
4.2	Probability of finding all servers busy (Probability that $\geq$s items are in system)		B	Probability
4.3	Average waiting time in queue		TW	Time
4.4	Probability that waiting time in queue >t	t	P(TW>t)	Probability
4.5	Average system response time* (Total time item spends in system)		T	Time
	Standard deviation of system response time		RUN	σ(T)
4.6	Average number of items in queue		$\overline{Q}$	Number
4.7	Average number of items in system*		$\overline{N}$	Number

*Items are in system when they reside in queue or are being processed by one of servers

sive and expensive real simulation. Although the discussion concentrates upon computer central site queuing, this model also has wide application in communication systems and industrial engineering.

Assumptions

Several simplifying and yet conservative assumptions are used to derive the analytic equations listed as "Multiserver Queuing Equations." Random arrival and random service are assumed. All servers are considered identical, with the same capacity and equal loading. Dispatching is first-in first-out (FIFO). No input traffic is lost because all arrivals are queued until they can be serviced.

Mathematically, the input traffic rate is assumed Poissonian in nature, with interarrival times following an exponential distribution. These distributions are characterized as memoryless and their arrivals as random. For this type input, arrival probability is constant and traffic load is independent of time. This means that different input rates must be modeled individually. Another attribute of the Poisson distribution is nonzero interarrival time, which rules out the occurrence of simultaneous inputs. Lastly, arrivals are independent of past events and have no influence on future inputs.

The model assumes exponential service times, which are mutually independent, identically distributed, random variables. Service time specifications parallel those for input traffic, as stated previously. Exponentially distributed interarrival and service times are Erlang 1 distributions, a special case of the gamma function. Time periods are so widely fluctuating and random that the standard deviation equals the mean.

$$(\text{mean} \div \text{standard deviation})^2 = \text{Erlang 1}$$

Their coefficient of variation is also 1.

$$\text{coefficient of variation} = (\text{standard deviation} \div \text{mean}) = 1$$

Modeling with exponential distributions is a standard conservative approach. In contrast, simulations using constant arrivals and service times predict best-case performance with minimal queuing. Constant distributions are Erlang infinity with standard deviations of zero.

TABLE 2

SR-52 Coding Form For Multiserver Queuing Model

Loc	Code	Key	Comments	Loc	Code	Key	Comments	Loc	Code	Key	Comments
000	46	LBL	RCL	075	55	÷		150	95	=	
	19	D′			42	STO			22	INV	
	42	STO			00	0			23	ln x	
	01	1			06	6			65	X	
	09	9			05	5			46	LBL	B
005	36	IND		080	19	D′		155	17	B′	
	43	RCL			55	÷			06	6	
	01	1			03	3			19	D′	
	09	9			19	D′			65	X	
	56	rtn			29	x!			07	7	
010	46	LBL	U	085	85	+		160	19	D′	
	16	A′			07	7			55	÷	
	01	1			19	D′			03	3	
	42	STO			95	=			19	D′	
	00	0			20	1/x			29	x!	
015	05	5		090	42	STO		165	55	÷	
	01	1			00	0			05	5	
	19	D′			07	7			19	D′	
	55	÷			56	rtn			95	=	
	02	2			46	LBL	P(n)		56	rtn	
020	19	D′		095	12	B		170	02	2	σ(T)
	55	÷			90	if zro			75	—	
	42	STO			11	A			17	B′	
	00	0			42	STO			65	X	
	04	4			00	0			17	B′	
025	03	3		100	00	0		175	85	+	
	19	D′			75	—			03	3	
	95	=			03	3			19	D′	
	22	INV			19	D′			40	x^2	
	44	SUM			95	=			65	x	
030	00	0		105	80	if pos		180	05	5	
	05	5			87	1′			19	D′	
	56	rtn			00	0			40	x^2	
	46	LBL	P(0)		19	D′			95	=	
	11	A			29	x!			30	$\sqrt{x}$	
035	16	A′		110	41	GTO		185	55	÷	
	03	3			46	LBL			53	(	
	19	D′			87	1′			17	B′	
	75	—			48	EXC			65	X	
	01	1			00	0			41	GTO	
040	42	STO		115	03	3		190	13	C	
	00	0			45	y^x			46	LBL	$\overline{N}$
	07	7			48	EXC			10	E′	
	95	=			00	0			01	1	
	90	if zro			03	3			19	D′	
045	00	0		120	65	X		195	65	X	
	07	7			03	3			53	(	
	00	0			19	D′			46	LBL	T
	42	STO			29	x!			14	D	
	00	0			46	LBL			02	2	
050	00	0		125	46	LBL		200	19	D′	
	04	4			55	÷			20	1/x	
	19	D′			07	7			85	+	
	45	y^x			19	D′			46	LBL	TW
	43	RCL			55	÷			13	C	
055	00	0		130	04	4		205	02	2	
	00	0			19	D′			19	D′	
	55	÷			45	y^x			20	1/x	
	43	RCL			00	0			55	÷	
	00	0			19	D′			03	3	
060	00	0		135	95	=		210	19	D′	
	29	x!			20	1/x			55	÷	
	95	=			81	HLT			05	5	
	44	SUM			46	LBL	P(TW>t)		19	D′	
	00	0			18	C′			65	X	
065	07	7		140	65	X		215	41	GTO	
	58	dsz			03	3			17	B′	
	00	0			19	D′			46	LBL	$\overline{Q}$
	05	5			65	X			15	E	
	01	1			02	2			01	1	
070	04	4		145	19	D′		220	19	D′	
	19	D′			65	X			65	X	
	45	y^x			05	5			41	GTO	
	03	3			19	D′			13	C	
	19	D′			94	+/−					

Labels: A = P(0), B = P(n), C = TW, D = T, σ(T), E = $\overline{Q}$, A′ = U, B′ = B, C′ = P(TW>t), D′ = RCL, E′ = $\overline{N}$

Registers: 00 = dsz, n; 01 = λ; 02 = u; 03 = s; 04 = λ/u; 05 = 1-U; 06 = (λ/u)^s; 07 = P(0)

The model delivers realistic results, even when actual distributions deviate from exponential. Practical job scheduling algorithms introduce even greater randomness than the FIFO discipline assumed in the model. Empirical measurements indicate that although coefficients of variation may exceed 1 at the central processing unit (CPU), they are usually less than 1 for the input/output (I/O) peripherals. Fortunately, these departures from exponential distributions have opposite effects on computer system performance and tend to negate one another.

Validity of predicted results depends on the accuracy of a model's input data as well as on the adaptability of the model to the system being simulated. Determining input data using a monitor is the most accurate approach. Using a hardware monitor to measure input parameters and the same monitor to validate the model's predictions, such queuing models for IBM and Univac mainframes have proven correct to within 5%. More typically, performance can be predicted to an accuracy of 10% either way of observed values.

The Model

Challenges encountered in programming this model for the SR-52 calculator included the problems of trying to fit the code within 224 instruction steps, minimize calculator execution time, and provide convenient user operation. The resultant program, listed in Tables 1 and 2, is an optimal tradeoff between these three sometimes conflicting objectives.

Subroutines were used extensively to enable the code to fit into 224 program steps. However, as subroutines take more time to execute than inline code, they were avoided in iterative loops. To further speed execution, frequently used labels were placed in low address locations and absolute addressing was used wherever possible.

Ten user-defined functions can be executed by pressing the top row of keys on the SR-52 calculator. To provide maximum user convenience, these user-function keys are named and referenced as follows:

Key	Name	Key	Name
A	P(O)	A′	U
B	P(n)	B′	B
C	TW	C′	P(TW > t)
D	T, σT	D′	—
E	$\overline{Q}$	E′	$\overline{N}$

With minor modifications this program is upward-compatible to TI-58 and -59 calculators, which use the same algebraic hierarchy and have the same number of user label keys as the SR-52. Using their additional program step capacity and companion PC-100A printer, the code can be expanded to print out alphanumeric messages for prompting and headings or to plot results.

Readers without access to TI calculators can use the multiserver model, by reprogramming the "Multiserver Queuing Equations" for whatever calculator is available.

The model requires input parameters λ, u, and s, which reflect characteristics of both workload and service facilities. As a preliminary step, these variables are stored in the calculator's memory registers. Then, as indicated in Table 1, "User Instructions," the simulation is run (Step 3.1) and any of the ten performance attributes listed in "Multiserver Queuing Equations" can be displayed.

Central Processor Simulation

Seven practical examples are given in Tables 3 and 4 to illustrate the technique for modeling CPU configurations. In Table 3, the three input parameters necessary for modeling are determined. In Table 4, the simulation results are listed.

One measure of processor speed is the time it takes to execute instructions. Average instruction execution time (AIET) depends on both the hardware and the software application. Scientific, business, and control system users have different AIETs on the same computer. To measure this value empirically, connect a counter to the instruction fetch strobe signal, then divide CPU active time by this instruction strobe count. The CPU in Table 3 has a given AIET of 1.072 μs. The reciprocal of AIET is the maximum number of instructions that can be executed by the processor in a unit time period. For modern full-scale computers, this number is so large that it is usually quoted in terms of millions of instructions per second (MIPS), which is the instruction execution rate for a saturated CPU running at 100% utilization. In this example, it is equal to 0.932836.

Before CPU service rate can be computed, the average number of instructions processed for each transaction or job must be established. Transactions are studied in real-time systems, while jobs are used for batch. If the system under investigation is still in the planning or design stage, the only way to proceed is to use a combination of time-consuming instruction counts (if code actually exists) and/or judicious estimating; this means tracing execution paths and actually counting or estimating the number of lines of code. The level of preliminary work done here will establish your confidence level in the simulation results. If the system is already operational, an exact count can be determined via a software accounting package, software monitor, or hardware monitor. Make certain that the final count includes instructions in the application code and a proportion of the operating system, utilities, and I/O handler overhead. In Table 3, the average number of instructions executed for each transaction is specified at 67,500.

CPU service rate is MIPS divided by the instruction-per-transaction overhead, then multiplied by 10^6 to keep units in line. In the previous example

$$\text{CPU service rate} = (0.932836 \div 67{,}500) \times 10^6$$
$$= 13.82 \text{ transactions/s}$$

Thus maximum CPU throughput is 13.82 transactions/s. At higher rates, queues continuously build, eventually outgrowing their buffers. Batch systems have their service rates quoted in jobs per second.

Two other parameters needed are number of servers and input transaction (or job) arrival rate. Number of servers (s) is taken equal to the level of multiprocessing. In uniprocessor configurations s = 1. For multiprocessors, where s is greater than 1, the model uses the actual overall arrival rate. In multiple uniprocessor configurations, only one CPU is modeled and input transactions are assumed to be uniformly distributed to all pro-

TABLE 3

Determining Input Parameters For Modeling CPU Configurations

Configuration	Total No. CPUs	Transaction Arrival Rate (per second)	CPU Service Rate (per second)	Model Input Parameters λ	u	s
2-CPU multiprocessor	2	25.00	13.82	25.00	13.82	2
3-CPU multiprocessor	3	25.00	13.82	25.00	13.82	3
4-CPU multiprocessor	4	25.00	13.82	25.00	13.82	4
2 uniprocessors	2	25.00	13.82	12.50	13.82	1
3 uniprocessors	3	25.00	13.82	8.33	13.82	1
4 uniprocessors	4	25.00	13.82	6.25	13.82	1
1 CPU (100% faster)	1	25.00	27.64	25.00	27.64	1

AIET = 1.072 μs

$$\text{MIPS} = \frac{10^{-6}}{\text{AIET}} = \frac{1}{1.072} = 0.932836$$

Average number of instructions-executed-per-transaction = 67,500
(includes application + operating system + utilities + I/O handler)

CPU service rate = MIPS x 10^6 ÷ (instructions/transaction)

$$= \frac{932{,}836}{67{,}500} = 13.82 \text{ transactions/s}$$

TABLE 4

Queue Statistics (for CPU Configuration in Table 3)

	Simulation Results										
Configuration	U	P(0)	P(1)	P(2)	B	TW	P(TW>.1)	T	σ(T)	$\bar{Q}$	$\bar{N}$
2-CPU multiprocessor	0.9045	0.0502	0.0907	0.0821	0.8591	0.3254	0.6598	0.3978	0.3819	8.1356	9.9446
3-CPU multiprocessor	0.6030	0.1443	0.2610	0.2361	0.3586	0.0218	0.0691	0.0941	0.0861	0.5446	2.3536
4-CPU multiprocessor	0.4522	0.1601	0.2896	0.2619	0.1304	0.0043	0.0063	0.0767	0.0742	0.1077	1.9166
2 uniprocessors	0.9045	0.0955	0.0864	0.0781	0.9045	0.6852	0.7926	0.7576	0.7576	8.5652	9.4697
3 uniprocessors	0.6027	0.3973	0.2394	0.1443	0.6027	0.1098	0.3481	0.1821	0.1821	0.9146	1.5173
4 uniprocessors	0.4522	0.5478	0.2477	0.1120	0.4522	0.0597	0.2121	0.1321	0.1321	0.3734	0.8256
1 CPU (100% faster)	0.9045	0.0955	0.0864	0.0781	0.9045	0.3426	0.6946	0.3788	0.3788	8.5662	9.4697

cessors. Therefore, arrival rate to the one modeled CPU is the overall arrival rate divided by the number of uniprocessors.

Computers often process several distinct classes of input simultaneously. When this occurs, these different classes may be combined and modeled as one representative type of input. The example in Table 5 shows how to merge three transaction types: inquiries, orders, and reports. Total arrival rate is a summation of individual arrivals:

17.0 + 20.0 + 4.5 = 41.5 transactions/s

The equivalent instructions-executed-per-merged transaction is weighted average, based upon relative arrival frequency and instructions-executed-per transaction:

(0.41 x 1500) + (0.48 x 6700) + (0.11 x 74,000)
= 11,971 instructions/transaction

As previously discussed, CPU service rate is computed by multiplying the given 0.500000 MIPS rate by 10^6 and then dividing this product by 11,971 instructions/transaction, yielding a result of 41.8 transactions/s.

Once input parameters are known for the merged transaction, a calculator simulation can be run to determine queue statistics.

When facility utilization exceeds 80%, both queue size and waiting time increase exponentially. The processor of Table 5 has a utilization just below 100% (U = 0.9928). This is too busy for satisfactory performance. Almost all of the 138.3333 transactions in the system ($\bar{N}$) are immobilized in the queue. Simula-

TABLE 5

Merging Transaction Types Into One Equivalent Transaction

MIPS = 0.500000

Three Transaction Types	Arrival Rate (per second)	Relative Arrival Frequency	Instructions Executed per Transaction	CPU Service Rate (per second)	CPU Utilization U
Inquiry	17.0	0.41	1,500	333.3	0.05
Order	20.0	0.48	6,700	74.6	0.27
Report	4.5	0.11	74,000	6.8	0.66
Totals	41.5	1.00			0.98

One Equivalent Transaction

Arrival rate = 41.5 transactions/s

Instructions/transaction = (0.41 x 1500) + (0.48 x 6700) + (0.11 x 74,000) = 11,971

CPU service rate = 500,000 ÷ 11,971 = 41.8 transactions/s

Model Input Parameters			Simulation Results				
λ	u	s	U	TW	T	$\bar{Q}$	$\bar{N}$
41.5	41.8	1	0.9928	3.3094	3.3333	137.3405	138.3333

tion predicts 137.3405 transactions queued ($\bar{Q}$), each waiting for an average of 3.3094 s (TW). Overall response time (T) is 3.3333 s. Therefore, only 3.3333 − 3.3094 = 0.0239 s are actually consumed for processing. Most of the response time (3.3094 ÷ 3.3333 = 99.28%) is spent waiting; only 0.72% is used in obtaining actual service.

While it is cost-effective to make good use of hardware, always consider the tradeoffs of adequate response time and realistic buffer size. No system can be expected

TABLE 6

Modeling Preemptive Priority Queue Disciplines

Three Transaction Types	Priority Level	Arrival Rate (per second) λ	Instructions Executed per Transaction	MIPS (for Subdivided Models)	CPU Service Rate (per second) u	U Subdivided Models
Inquiry	high	17.0	1500	0.500000	333.3	0.05
Order	medium	20.0	6700	(1-0.05) (0.500000) = 0.475000	70.9	0.28
Report	low	4.5	74,000	(1-0.05) (1-0.28) (0.500000) = 0.342000	4.6	0.98

Subdivided Models

Three Transaction Types	Model Input Parameters			Simulation Results					
	λ	u	s	U	TW	T	Throughput 1/T	$\bar{Q}$	$\bar{N}$
Inquiry	17.0	333.3	1	0.0510	0.0002	0.0032	316.3000	0.0027	0.0537
Order	20.0	70.9	1	0.2821	0.0055	0.0196	50.9000	0.1108	0.3929
Report	4.5	4.6	1	0.9783	9.7826	10.0000	0.1000	44.0217	45.0000

to operate safely with a facility utilization above 80% anywhere in the processing chain (CPU or channels). At high utilizations, any small increase in arrival rate or deviation of distribution may result in severely degraded performance. Data can be lost because of overflowing buffers or the system can be brought down entirely.

Until now, different transaction types have been implicitly assumed to be at the same priority level. However, modeling need not be so restricted. Table 6 develops the concept of job stream priorities. The approach is to subdivide one computer into a number of separate pseudomachines, one processing each transaction type, and each with its own MIPS rate. These pseudomachines are modeled independently to determine performance characteristics for the various classes of input.

Since Table 6 considers three transaction types, three pseudocomputers are modeled. Inquiries receive precedence and are given the full benefit of the 0.500000 MIPS. CPU service rates, for the pseudoprocessors, are calculated by multiplying their respective MIPS by 10^6 and then dividing by instructions per transaction. For inquiries, this service rate calculation is

$$0.500000 \times 10^6 \div 1500 = 333.3 \text{ inquiries/s(u)}$$

Once λ, u, and s are determined for the pseudoprocessors, the model can be run to display their queue statistics. Such simulation indicates that the inquiry processing pseudocomputer is only 5% utilized (U). Table 6 also lists waiting time (TW), response time (T), throughput (1/T), and queue length ($\overline{Q}$, $\overline{N}$) statistics.

Order processing ranks second, having preemptive priority over reports. The MIPS available to orders (0.475000) is computed by multiplying the original MIPS rate (0.500000) by the inverse of CPU utilization for the inquiry pseudoprocessor:

$$(0.500000) \times (1 - \text{inquiry CPU utilization})$$
$$= (0.500000) \times (1 - 0.05) = 0.475000 \text{ instructions/s}$$

The third pseudocomputer, for reports, gets whatever MIPS is left over (0.342000). This computation is analogous to the one for orders.

$$(0.475000) \times (1 - \text{order CPU utilization})$$
$$= (0.475000) \times (1 - 0.28) = 0.342000 \text{ instructions/s}$$

Resulting queue statistics, in Table 6, are valid performance indicators for the three transaction types. However, utilization of the actual processor remains to be resolved. The percentage of real CPU utilization, contributed by each input class, is calculated by multiplying arrival rate by instructions per transaction and then dividing by the product of the overall 0.500000 MIPS rate times 10^6.

		CPU Utilization
Inquiry:	$(17.0 \times 1500) \div (0.500000 \times 10^6)$	= 5.1%
Order:	$(20.0 \times 6700) \div (0.500000 \times 10^6)$	= 26.8%
Report:	$(4.5 \times 74{,}000) \div (0.500000 \times 10^6)$	= 66.6%
	Total	98.5%

Combined CPU utilization for inquiry and order processing is only 5.1% + 26.8% = 31.9%. This indicates that inquiries and orders are processed more expeditiously than in the single priority system of Table 5. Report processing, having lowest priority, is degraded the most. Average report queue length ($\overline{Q}$) is 44.0217, and mean response time (T) is 10.0000 s.

Subdividing one computer into a number of pseudoprocessors assumes smooth and homogeneous CPU execution for transactions of all priority levels. However, in practice, CPU activity occurs in bursts interspersed with idle periods. Modeling errors will be small so long as either (1) instruction overhead for high priority transactions is shorter than for those of lower priority and/or (2) high priority transactions only lightly load the system. The degree to which these two assumptions are met determines result accuracy.

In Table 6, errors caused by our homogeneous processing assumption are less than 5%. Conditions ensuring accurate results are:

Instructions Per Transaction	Inquiry < Order < Report
	1500 < 6700 < 74,000
CPU Utilization	Inquiry + Order = 31.9%

Similar stipulations can be expanded to any number of priority classes. Generally, high priority transactions and jobs have shorter instruction execution paths than those of lower priority. In practice, preemptive priority queue modeling is applicable and its results are realistic. Case histories have been documented in which such pseudoprocessor analytic models were as accurate as discrete simulation packages which had run and accumulated statistics for many thousands of transactions.

Disc and Drum Channel Simulation

Five examples of channel configurations are given in Tables 7 and 8. Table 7 develops the three input parameters (λ, u, s) needed for modeling. Queue statistics resulting from these simulations are listed in Table 8.

Throughput capacities for three types of drums are computed in the upper half of Table 7. All quoted times and rates represent averages. Access time includes seeking and rotational delay. Drum seek times are always zero because heads are fixed and stationary. Average rotational delay (latency) is the time consumed by one-half a disc or drum revolution. Data transfer time depends on the physical characteristics of the device, r/min, and bit-packing density, as well as on blocking size. Adding access to data transfer time results in I/O service time. The reciprocal of service time is service rate u, the maximum possible number of device I/O operations per second.

When different classes of transactions reference the same I/O device, the relative frequency of their accesses is used to compute a weighted average block size. This is done by multiplying the block size of each transaction

TABLE 7

Modeling Channel Configurations

Drum Type	Channel Characteristics: Access Time(s)	+ Transfer Time/Byte(s)	x Bytes/Transfer	= Service Time per I/O(s)	Service Rate(/s)
A	0.01700	4.25×10^{-6}	560	0.019380	51.60
B	0.00425	4.25×10^{-6}	2048	0.012954	77.20
C	0.09200	7.00×10^{-6}	384	0.094688	10.56

Example	Drum Type	Channel Configurations: Description	Total No. Channels	I/O Rate/s	Model Input Parameters: λ	u	s
1	A	1 single channel	1	22.20	22.20	51.60	1
2	B	2 single channels	2	150.00	75.00	77.20	1
3	B	1 dual channel	2	150.00	150.00	77.20	2
4	C	4 single channels	4	4.32	1.08	10.56	1
5	C	2 dual channels	4	4.32	2.16	10.56	2

TABLE 8

Queue Statistics
(for Channel Configurations in Table 7)

Example	Model Input Parameters: λ	u	s	Simulation Results: U	P(0)	P(1)	P(2)	B	TW	P(TW>0.1)	T	σ(T)	$\bar{Q}$	$\bar{N}$
1	22.20	51.60	1	0.4302	0.5698	0.2451	0.1055	0.4302	0.0146	0.0227	0.0340	0.0340	0.3249	0.7551
2	75.00	77.20	1	0.9715	0.0285	0.0277	0.0269	0.9715	0.4416	0.7796	0.4545	0.4545	33.1194	34.0909
3	150.00	77.20	2	0.9715	0.0145	0.0281	0.0273	0.9575	0.2176	0.6166	0.2306	0.2274	32.6407	34.5837
4	1.08	10.56	1	0.1023	0.8977	0.0918	0.0094	0.1023	0.0108	0.0396	0.1055	0.1055	0.0117	0.1139
5	2.16	10.56	2	0.1023	0.8144	0.1666	0.0170	0.0190	0.0010	0.0028	0.0957	0.0952	0.0022	0.2067

type by the percent of accesses attributable to that transaction type. Summing all these products gives the weighted average block size. Then, device service rate is calculated as shown in Table 7. Multiplying average block size by the transfer time per byte and adding access time gives the service time per I/O, the reciprocal of which is service rate (u).

Peripherals having the most influence on system performance are mass data storage discs and drums. Channel configurations interface sets of these I/O devices to the CPU. A one-path interconnection is interpreted as a "single" channel; two access paths represent a "dual" channel, where any two peripherals in the set can be accessed simultaneously.

Drum channel queuing is more pronounced than queuing at the device level; so rather than model individual peripherals, aggregate channel activity is considered. A channel is in use for the total busy time of all drums accessed through it. The underlying supposition is that both a drum and its channel are seized and released simultaneously. Queues form when all channel access paths to a device are in use. "Single" channels are represented by one queue and one server. A "dual" channel is modeled as two servers replenished from one queue.

Channel service rate is determined by the peripherals interfaced, and equates directly to drum service rate in Table 7 because all drums on each channel have identical specifications. In practice, there may be cases where the same channel is used by several different types of drums. Channel service rate is then an average of drum service rates, weighted according to frequency of drum accesses. This is calculated by multiplying the service rate of each drum on the channel by the percent of channel accesses attributable to that drum. Channel service rate is the sum of these products.

Selector channels handling command-chained channel programs are busy during the total time that their discs

TABLE 9

Determining Optimum Multiprogramming Level For Computer System

Model Entire Multiserver CPU (where each initiator is a server)						Drum Type B on One Dual Channel					Total System	
Number of Initiators N	λ	u	s	U	Response Time T_1	λ	u	s	U	Response Time T_2	Response Time $T=T_1+T_2$	Message Throughput N÷T
1	3	40.00	1	0.0750	0.0270	1.5	77.20	2	0.0097	0.0130	0.0400	25.03
2	6	20.00	2	0.1500	0.0512	3.0	77.20	2	0.0194	0.0130	0.0642	31.17
3	9	13.33	3	0.2250	0.0761	4.5	77.20	2	0.0291	0.0130	0.0891	33.68
4	12	10.00	4	0.3000	0.1013	6.0	77.20	2	0.0389	0.0130	0.1143	35.00
5	15	8.00	5	0.3750	0.1269	7.5	77.20	2	0.0486	0.0130	0.1399	35.74
6	18	6.67	6	0.4500	0.1530	9.0	77.20	2	0.0583	0.0130	0.1660	36.15
7	21	5.71	7	0.5250	0.1800	10.5	77.20	2	0.0680	0.0130	0.1930	36.27
8	24	5.00	8	0.6000	0.2087	12.0	77.20	2	0.0777	0.0130	0.2217	36.08
9	27	4.44	9	0.6750	0.2410	13.5	77.20	2	0.0874	0.0131	0.2541	35.43
10	30	4.00	10	0.7500	0.2807	15.0	77.20	2	0.0972	0.0131	0.2938	34.04
11	33	3.64	11	0.8250	0.3389	16.5	77.20	2	0.1069	0.0131	0.3520	31.25
12	36	3.33	12	0.9000	0.4600	18.0	77.20	2	0.1166	0.0131	0.4731	27.48
13	39	3.08	13	0.9750	1.2227	19.5	77.20	2	0.1263	0.0132	1.2359	10.52
14	42	2.86	14	1.0500	—	21.0	77.20	2	0.1360	0.0132	—	—

and drums are active; this includes seek (arm movement), latency (rotational delay), and data transfer times. Access time is the sum of seek and latency. Drums, having fixed heads, always have a seek time of zero. Once access time is established, channel calculations are made as in Table 7.

If one disc channel program initiates a standalone seek and a second channel program initiates a data transfer operation (after the seek is complete), the selector channel is freed during the seek operation and its access time is equal only to latency. The tradeoff is the additional overhead caused by the extra interrupt and I/O supervisor processing which needs to be added to the CPU model.

Block-multiplexer channels are more efficient because they automatically disconnect during seeks, even with only one command-chained channel program. Utilization of a disc block-multiplexer channel can be as low as one-half or one-third of the combined utilizations of its individual discs. Disc block-multiplexer channels are modeled by proceeding as indicated in Table 7 without adding disc seek time into access time. Block-multiplexer channels with "rotational position sensing" are also free during latency and their access time is therefore zero.

Rules for representing channel arrival rates (λ) and number of servers (s) are similar to those for CPUs. Single channels are modeled as one server. λ is the total I/O arrival rate divided by the number of single channels. Only one of the single channels in the group is actually simulated, with its results applying to all. A dual channel is modeled as two servers fed from one queue; dividing the total I/O arrival rate by the number of dual channels computes to λ. Table 7 provides additional details.

The model assumes an absence of dual channel device lockouts, attempting to simultaneously use one peripheral device via each of the two access paths. One request is blocked until completion of the other. With a number

of I/O devices on each channel and an even distribution of files, the probability of device lockout is small. Instances of high probability are best represented by the single channel model.

Central Site Modeling

When transation flow can be approximated by sequential queues, CPU and channel models can be consolidated. Total central site response time is estimated by summing response times for processor and each appropriate channel.

Table 9 shows how to determine the optimum number of initiators. This example is a CPU and drum channel system with two queues in series. Total transaction response time (T) is computed by adding together computer (T_1) and drum channel (T_2) response times. Dividing the number of initiators (N) by this total response time (T) approximates a theoretical system throughput capacity.

The processor is multiprogrammed with initiators modeled as individual servers. Total CPU service rate remains fixed at 40.00 transactions/s. Number of initiators corresponds to level of multiprogramming. An increasing number of servers is balanced by a diminished processing power allocated per server. Each initiator is consigned a service rate (u) of $40.00 \div N$.

The goal is maximizing real transaction throughput for the system. This corresponds to the maximum transaction arrival rate (λ) which can be handled. The last column in Table 9 lists a theoretical system throughput capacity ($N \div T$). Optimal real system throughput is the highest transaction arrival rate which satisfies the relationship $\lambda \leq (N \div T)$. In Table 9 the best choice for N is 10 ($\lambda = 30$ and $N \div T = 34.04$); at this point, the CPU arrival rate and theoretical system throughput capacity curves effectively intersect. Higher traffic rates cannot be supported by the system and will result in queue backup and overflow. For example, at $N = 11$, arrival rate (λ) of 33 transactions/s is higher than the theoretical system throughput capacity ($N \div T$) of 31.25 transactions/s.

Total system throughput depends on both processor and drum I/O. As the number of initiators is increased, the CPU saturates much more rapidly than the channel. At $N = 11$, CPU utilization has already reached 82.5% while channel utilization is only 10.69%. The computer determines the level of multiprogramming, and its utilization controls the shape of the theoretical system throughput capacity curve. Drum hardware characteristics establish a lower bound ($T_2 = 13$ ms) on system response time.

Summary

The generalized computer system simulation package presented can evaluate any level of multiprogramming and multiprocessing with any combination of interactive and batch workloads. Elaborate queuing formulas have been reduced to a simple technique for efficiently evaluating complex systems on a programmable calculator.

A wide range of problems facing manufacturers of mainframes and peripherals as well as end-users can be addressed. The impact of hardware configuration changes and software modifications on performance can be anticipated. The effect of totally new hardware, improvements to existing machines, and the interplay of components can be assessed. The consequences that projected increases in a system's online workload will have on response times, batch throughput, and turnaround times can be predicted. Bottlenecks that are likely to arise as workload increases can be located.

Before using the model, the computer designer merely characterizes system resource demands and capabilities with a small set of easily researched parameters, determined by some combination of monitor measurements, estimates, or design specifications. Pressing a few calculator keys simulates the effect of job contention for processor and I/O, predicting the performance of any computer system. With such a queuing model, the programmable calculator becomes a convenient and indispensable tool for predicting and optimizing system performance.

Bibliography

C. W. Churchman, R. L. Ackoff, and E. L. Arnoff, *Introduction to Operations Research*, John Wiley & Sons, Inc, New York, 1957, Chap 14

J. Martin, *Design of Real-Time Computer Systems*, Prentice-Hall, Inc, Englewood Cliffs, NJ, 1967, Chap 26

J. Martin, *Systems Analysis for Data Transmission*, Prentice-Hall, Inc, Englewood Cliffs, NJ, 1972, Chap 31

M. Reiser, "Interactive Modeling of Computer Systems," *IBM Systems Journal*, No. 4, 1976, pp 309-327

Univac Applications Engineering, "Central Site Queuing Model," *System Design and Simulation Technical Memorandum*, Univac DPD, PO Box 8100, Philadelphia, Pa, June 1969

J. Webb, "Queuing Theory and Performance Analysis," *Computer Measurement and Evaluation*, Vol III, SHARE, Inc, Chicago, Ill, Dec 1973-Mar 1975, pp 309-332

R. Zussman, "Computer Simulation On a Pocket Calculator," *Computer Design*, May 1977, pp 105-109

Ronald Zussman, currently senior consultant and project leader of computer measurement and evaluation at SIAC, has experience that includes development of interactive models of shipboard computer systems and a prototype of an automated trading post. He holds BSEE, MSEE, and professional EE degrees from Pratt Institute, New York University, and Columbia University, respectively.

SAVE 80%

on PDP-11/70 main memory with Dataram BULK CORE



1024K x 18
(one megaword)
PRICE COMPARISON

DEC				DATARAM			
Qty	Item	Unit Price	Sub-Total	Qty	Item	Unit Price	Sub-Total
1	MJ11-BC 256K word (512KB) system	$ 55,500	$ 55,500	1	BC-417 chassis and accessories	$ 3,400	$ 3,400
3	MJ11-BG 256K word (512KB) additional	53,240	159,720	8	128K x 18 (256KB) additional	5,140	41,120
			$215,220				$ 44,520

Source: Datapro, February '77

SAVINGS $\frac{215{,}220 - 44{,}520}{215{,}220} = \frac{170{,}700}{215{,}220} =$ **79.3%**

You read right!

Dataram's BULK CORE provides a dramatic main memory alternative for PDP-11/70 users. BULK CORE system BC-417 interfaces to DEC's 11/70 Memory Bus, and is completely compatible with DEC's MJ11 series of core systems.

The BULK CORE BC-417 system is offered in a 15¾" chassis with a minimum configuration of 256K x 18. It can be expanded in increments of 256K x 18 to a maximum of 1024K x 18 (one megaword).

BULK CORE. An economical, exciting . . . and proven alternative.

DATARAM CORPORATION
PRINCETON-HIGHTSTOWN ROAD
CRANBURY, NEW JERSEY 08512
TEL:609-799-0071 TWX:510-685-2542

I'd like to learn more about BULK CORE for my PDP 11/70

☐ Please send information
☐ Please have a salesman contact me

I'd also like to learn more about BULK CORE for my ☐ PDP-11 ☐ Nova

Name _____

Title _____ Phone _____

Company _____

Address _____

City _____ State _____ Zip _____

☐ Please send me information about Dataram's ADD-ON/ADD-IN memory for minicomputers.

PDP and DEC are registered trademarks of Digital Equipment Corporation

Canada: Tracan Electronics Corporation, Ontario/Quebec/British Columbia • **Belgium/Luxembourg/Netherlands:** Synelec Information Systems, (02) 647-67-12 • **France:** YREL, 950-2224 • **Italy:** Telcom, s.r.l. 422-8646 • **Sweden/Finland/Norway:** Teleinstrument AB, 08-380370 • **Spain:** Aupoca, (01) 457-53-12 • **Switzerland:** Intertest AG, 031-224481 • **United Kingdom:** Sintrom Ellinor Ltd., (0734) 85464 • **West Germany/Austria:** O.E.M. Elektronik GmbH, 0711-798047 • **India:** Industrial Electronic Instruments, 79281 • **Israel:** K.D.M. Electronics Ltd., (03) 58232 • **Japan:** Matsushita Electric Trading Co. Ltd., (03) 435-4552 • **Australia/New Zealand:** Anderson Digital Electronics, (03) 543-2077.

CIRCLE 48 ON INQUIRY CARD

The minifloppy®

Proven in 10,000 installations and never more affordable.

A year ago when we introduced our minifloppy, we frankly didn't expect the revolution that was about to happen. Now we've got 10,000 units delivered and our production experience allows us to pass along a nice 15% price reduction. Naturally, we are very flattered by the acceptance the little drive has received (and by all the imitations). There are a lot of good reasons why our minifloppy has been accepted as number 1.

35 Tracks. A format with a future.

The minifloppy provides fast, random access to the industry accepted 35 recording tracks. This is the format that will help you grow *compatibly* and *reliably* into double density and double sided recording later, when you are ready. Transfer rate is 125 kbits per second, seek time is 40 msec track to track.





The compact minidiskette® media carries 110 KB of information. And this convenient disk configuration is easy to file and easy to load. The minidiskette media is available hard or soft sectored.

Reliable Storage

The Shugart minifloppy drive has the proven mechanical reliability and data integrity of standard flexible disk drives. It reads and writes with the same glass bonded ferrite/ceramic head used in Shugart's standard-sized SA800 flexible disk drives. Shugart makes over 100,000 of these heads each year. The SA400 also uses a SA800-2 style interface like big brother. Interface commonality allows upward expansion and ease of conversion.

Mechanical Reliability

Proven flexible disk drive technology gives you a MTBF of 8000 Power-On-Hours in typical duty applications. Die cast construction offers high mechanical integrity.

A DC drive motor with precision servo speed control using an integral tachometer eliminates AC power requirements. The unique stepping motor actuator uses a direct drive spiral cam with ball bearing V-groove positive indent. This assures perfect head registration every time.

A positive media interlock prevents diskette damage. The door interlock insures that the door cannot be closed until the diskette is fully inserted. Your customer can't jam this drive.

from number 1

Data Integrity

Error rate is a critical factor in your system's performance. The Shugart minifloppy drive improves error rate by two orders of magnitude compared to cassettes. Soft errors are only one in 10^8, and seek errors one in 10^6.

Write protect circuitry prevents loss of recorded information. It's standard with every Shugart SA400.

The minidiskette media is recorded at 20% less density than our standard floppy. This generous safety margin is your assurance of data integrity and the lowest possible media costs.

Maintainable Performance

Simple, modular components reduce Mean-Time-To Repair to thirty minutes. The self-aligning head eliminates the need for head alignment tools in the field.

Inexpensive Storage

Applying floppy technology in a compact size reduces OEM and end user cost. And with our recent 15% price reduction minifloppy disk storage has never been more affordable.

Small drive size (5.75″ wide, 3.25″ high and 8.0″ deep) reduces total system cost. Low unit weight of three pounds offers OEM system designers new application opportunities, too.

Low power consumption (only 15 watts continuous duty, 7.5 in standby) reduces power supply cost and heat problems (fan noise, too). Standard twelve volt and five volt DC power is all that is required.

The SA4400 ministreaker™ Controller

The SA4400 ministreaker controller controls up to three minifloppy drives, providing up to 241.8 kilobytes of on-line data storage. Using a modified IBM 3740 format and a 128 byte buffer, the controller operates on 8 bit byte bi-directional parallel I/O.

Features include direct track/sector addressing, asynchronous TTL host interface, seek overlap and simplified command structure.

Support

Shugart has made the floppy smaller and product support bigger. We give you more support—systems design, technical service, documentation and applications help.

Two out of three OEM's specify Shugart. They get more experience, more technology, more support. So talk to number one in low cost disk storage. Talk to Shugart.



Shugart Associates®

415 Oakmead Parkway, Sunnyvale, California 94086
Telephone: (408) 733-0100
West Coast Sales/Service: Telephone (408) 252-6860
East Coast Sales/Service: Telephone: (617) 890-0808
Europe Sales/Service: 3, Place Gustave Eiffel, Silic 311
94588 Rungis, France Telephone: (1) 686-00-85

™ ministreaker is a Shugart trademark

CIRCLE 49 ON INQUIRY CARD

We'll go head-to-head



with any other serial printer

Florida Data Corporation has brought the question of matrix printer reliability to a head! The Model PB-600 print head will print over **500 million characters** at **100%** duty cycle.

With only normal preventive maintenance during that time, the PB-600 will maintain dot registration with ± 1/2 dot width and no missing dots. Compare that performance against any other dot matrix serial printer!

And while you're checking our PB-600, check these other important features:

- **SPEED** – 600 CPS. That translates to 240 LPM at full 132-column line width, or as many as 1465 LPM for 1 character lines.
- **GRAPHICS** – 7 x 7 matrix, with 7 x 8 available for lower case characters. Interchangeable PROMS make almost any graphic set available.
- **COMPATIBILITY** – we interface with positive or negative TTL, Centronics, Data Products or Logabax. A Centronics-compatible serial interface and a 20 ma Current Loop are optionally available.
- **BUFFER** – 896 character capacity and FIFO format are ideal for communications applications.
- **PRICE** – even with all this capability, FDC's PB-600 is competitively priced with less versatile, less reliable dot matrix printers. You get line printer speed at serial printer prices.

We're using our head to solve OEM printer problems. For complete technical details, contact Florida Data Corporation, 3308 New Haven Avenue, West Melbourne, Florida 32901. Telephone: 305/724-6088.

FDC

CIRCLE 50 ON INQUIRY CARD

Various magnetic tape transport speeds, track configurations, and read/write densities are automatically software-controlled by a universal buffered tape formatter that incorporates a high speed oriented microcomputer and offers IEEE-488 interface compatibility

Magnetic Tape Formatter Design Reduces Hardware/Software Requirements

A. Scott McPhillips

Information Development & Applications, Incorporated
Beltsville, Maryland

A universal buffered tape formatter resolves the recurring disadvantages of demand-designing tape interfaces, resulting in lower cost, increased adaptability and reliability, and expanded capability. Incorporating a microprocessor, which provides significant economies by greatly simplifying interface hardware and tape handling software, the formatter is plug-compatible with most existing devices that interface to magnetic tape.

Interfacing this buffered formatter to a data or instrumentation system is simplified since the formatter is compatible with the IEEE-488 standard interface. This general-purpose interface bus (GPIB) is now available on many minicomputers, programmable calculators, instruments, and other data handling devices. Thus, the buffered formatter is automatically plug-compatible with a majority of the existing devices that must be interfaced to magnetic tape. For noncompatible data devices, it is easier and less expensive to add a GPIB interface than to add a conventional tape interface. In addition, the GPIB interface provides device-compatibility to present as well as future data processing systems and instruments.

The industry's highly standardized tension-arm magnetic tape transports are available in several speeds, track configurations, and recording densities. This diversity of timing and format requirements causes present tape formatters to be complex and expensive. A typical formatter designed with transistor-transistor logic (TTL) requires 125 integrated circuits (ICs) to handle standard tape densities through 800 bits/in and another 125 ICs if it is to handle 1600-bit/in tapes as well. In contrast, the microprocessor-based buffered formatter (Fig 1) uses 80 chips to duplicate all functions of an 800-bit/in formatter. Provisions are also made for adding an optional 50-chip board to convert to 1600-bit/in operation.

In addition to this factor-of-two parts reduction, the microcomputer approach provides even more significant economies by greatly simplifying the interface hardware and tape handling software in the data system that controls the formatter. The microcomputer buffer memory allows incremental writing and reading. This removes all timing constraints on the external system and often avoids the need for a direct memory access (DMA) controller. The GPIB interface is already available in many systems, avoiding the need for any custom interface design. The microcomputer can be directed to search a tape to find a desired data block or file, freeing the system processor of this time-consuming task. Most important, microcomputer software can automatically handle all error detection and recovery procedures, completely relieving system software of these details.



Fig 1 Buffered magnetic tape formatter. Microprocessor performs tape timing, data buffering, and formatting. Parts count is only about half that of conventional unbuffered formatters, even though system includes such extra capabilities as tape searching and automatic error correction. Wide card in front contains microcomputer and buffer memory expansion sockets. Tape interface board (rear left) includes "poor man's DMA" controller. Other boards are IEEE-488 interface and power supply



Fig 2 Industry standard 7- and 9-track magnetic tape formats add error detection codes to each data block. Individual data characters are protected with parity bit, and longitudinal redundancy check character (LRCC) code is used to check parity along each track. 9-track format also includes cyclic redundancy check character (CRCC) error correction code that permits automatic correction of most errors

Error Detection

Errors are detected in magnetic tape systems by recording two or three types of check bits with each data block (Fig 2). While a block is being written, it is simultaneously read back by a separate tape head and all error detection codes are checked. If a recording (write) error occurs, the formatter automatically backspaces, erases the small region of tape that contains the error, and then rewrites the block from its buffer memory. If a read error occurs, the formatter software goes into a 2-phase process designed to recover the original data if at all possible. First, the data block containing the error is reread several times while varying the sensitivity of the tape transport read amplifier. If the error is "soft" (temporary), perhaps caused by a speck of dust or slightly deformed tape, it can often be read correctly after a few tries. A "hard" (permanent) error will persist through any number of rereads and calls for the second phase of the error recovery software to be invoked.

This error correction phase makes use of the cyclic redundancy check character (CRCC) recorded with each data block. CRCC is an error detection and correction code designed to correct any number of errors—provided that all errors occur in the same track on the tape. Stray dust or tape particles tend to be much smaller than the distance between tape tracks so that single-track errors are by far the most prevalent. Therefore, most hard errors can be detected and corrected using the CRCC.

The longitudinal redundancy check character (LRCC) consists of parity bits that make the total number of 1s in each track even. This assures that all tracks will erase with the same magnetic polarity in the



Fig 3 Organization of buffered tape formatter. Formatter uses microprocessor to interface industry standard tape drive to IEEE-488 bus. Software handles all tape formatting, timing, and error recovery procedures plus bus handshake protocol. Processor accepts incremental data from bus and stores it in RAM. When complete data block is received, required check characters are added and block is recorded synchronously on tape. Error detection circuitry continuously monitors data received from tape, providing read-while-write data checking while software concentrates on write timing

interblock gaps. The older 7-track format also uses the LRCC to detect multiple-bit errors that might produce acceptable character parity. Although the LRCC provides reliable error detection, it is not sophisticated enough to support automatic error correction; thus 7-track systems will suffer from a higher rate of uncorrectable errors.

Error detection and correction using rewrites, rereads, amplifier threshold adjustments, and the CRCC code are all well-known and widely used techniques on tape controllers designed for use with large mainframes. Rarely, if ever, however, have all of these capabilities been included in a small formatter designed for offline use. Without the microcomputer, these capabilities would be prohibitively expensive in small data systems.

Software Replaces Hardware

The block diagram in Fig 3 shows the organization of the formatter. All timing, counting, and delay generation circuitry typical of present formatters is absent—replaced with a microprocessor and associated memories to form an integral microcomputer. Even the GPIB interface is composed of little more than input/output (I/O) ports and line drivers, plus software that performs bus handshake and control tasks. The interface between the microprocessor and tape transport is not as simple, but still relies on software as much as possible to eliminate hardware.

While the microprocessor is busy recording data, special parity and CRCC checking circuits simultaneously monitor the read data output of the transport for tape errors. After a data block is written, the microcomputer checks this hardware to determine whether any errors occurred during the write cycle. Other than this hardware assistance, all tape timing, coding, reading, and writing are handled by software that adapts to the format and tape speed required for the tape transport in use.

Data bytes received from the GPIB are stored in random-access memory (RAM) until a complete tape block is received. Software then adds the required parity bits and check characters, creating an exact image in RAM of the block as it is to appear on magnetic tape.

When the RAM image is ready, the microcomputer becomes a tape formatter for the few milliseconds needed to record the data block on magnetic tape. Software first starts the tape in motion, and then generates a prerecord time delay that allows the tape to reach rated speed. This delay interval and all other tape timing depends on tape speed, tape format, and operation cycle (read, write, backspace, edit, etc) in process. More than 100 time delays are stored in program tables to handle various operations that can occur at four standard speeds (12.5, 25, 37.5, and 45 in/s) and in three formats (7-track NRZI,* 9-track NRZI, and 9-track phase-encoded).

When the tape reaches rated speed, actual recording occurs. Software outputs the tape block image from RAM one byte at a time at a rate appropriate for tape speed and desired recording density. These parameters are selected by setting speed/density switches that are sampled by the software when the system is turned on or reset. Four tape speeds and four standard densities (200, 556, 800, and 1600 bits/in) are accommodated,

*Nonreturn to zero inverted

introducing a total of 16 possible recording frequencies. Each of these required frequencies is generated by a software timing loop that outputs one byte each time around. While the lower speeds and densities are easily handled, the transfer rate for 45 in/s at 1600 bits/in is 72k bytes/s (about 13.9 μs/byte), which initially appears to be beyond the capabilities of available microprocessors. Therefore, a technique was developed to output 72k bytes/s using a conventional metal-oxide semiconductor (MOS) microprocessor.

Speeding up a Microprocessor

The 8080 microprocessor was selected for the investigation into speedup techniques because its interface signals and architecture offer several options instead of forcing a standardized design. Fig 4 shows a first attempt to output tape data with a fast 8080 software loop. This loop executes in 46 clock cycles, which takes 23 μs with the 8080. Unfortunately, this loop time is almost twice the required 13.9 μs/byte.

The usual design solution to this type of data transfer problem is to incorporate a DMA interface and allow external hardware to pull data from RAM at whatever rate is needed. While this approach is quite feasible for handling the 13.9-μs transfer rate, it would be cumbersome in this application because 16 different transfer rates are required at various speeds and densities. A DMA controller that must operate at any one of 16 unrelated frequencies is just the kind of complex timing circuitry originally slated for elimination with software.

This impasse was overcome by combining hardware and software to implement a "poor man's DMA." Key to this technique is to improve the microcomputer transfer rate by eliminating an inherently wasteful processing sequence. As with most small computers, the 8080 can output data only from its accumulator. If the needed data are in RAM, they must first be read into the accumulator, then output. This is evident in the program of Fig. 4. The MOV A,M instruction loads the accumulator from memory so that the OUT TAPE instruction can then output the data byte.

Adding a single NAND gate eliminated the need for this double transfer (Fig 5). This gate allows the write data register to receive the data byte at the same time that the 8080 reads it. A spare 8080 address line, A15, enables the gate. Whenever the microprocessor reads memory with the A15 address bit set, the data read are transferred directly from memory to the output latch. This technique eliminates the need for an output instruction in the program loop, thus saving 5 μs for every transferred byte. The only penalty is that with the A15 address line dedicated to controlling the special output port, the microprocessor can address only 32k of storage instead of the normal 64k. However, 32k is still far more storage than required.

Streamlining the Software

Eliminating the OUT instruction reduces the loop execution time to 18 μs, still short of the 13.9-μs goal. The final speedup is achieved by reworking the loop program to take advantage of the fact that the accumulator is no longer needed as a transfer station for output data. The program listed in Fig 6 has only four instructions in the output loop and, with the help of the added NAND gate and some advance data preparation, it outputs 1 byte every 13 μs. With this program, the required output rate (13.9 μs) can be achieved exactly by using a slightly lower than normal crystal frequency in the 8080 clock oscillator.

In the revised loop program, the first difference from the original program is that the memory pointer

```
                                                    Timing
        LXI   H,BUFSTART      ; POINT AT FIRST BYTE
        LXI   D,BYTECOUNT     ; LOAD LOOP COUNT
LOOP:
        MOV   A,M             ; FETCH BYTE FROM RAM      7
        OUT   TAPE            ; OUTPUT IT               10
        INX   H               ; POINT AT NEXT BYTE       5
        DCX   D               ; DECREMENT LOOP COUNT     5
        MOV   A,D             ; SEE IF LOOP COUNT = 0    5
        ORA   E               ;                          4
        JNZ   LOOP            ; JUMP BACK IF NOT        10
                                                         46 clock cycles
                                                         (23 μs)
```

Fig 4 Simple 8080 programmed output loop. After fetching and outputting data byte, program must update two registers (H and D) and then test for 0 in double-precision loop counter. Timing measurements show that loop consumes 23 μs/byte—too slow for design requirements

register is initially loaded with BUFSTART + A15. This register is loaded with the address of the first byte to be transferred, as before, except that address bit A15 is also set. Any memory access using this pointer will now output data.

The first instruction within the transfer loop, MOV B,M, reads memory using the pointer, and this outputs a byte to the special port. This instruction has been changed from the original MOV A,M to shunt the byte into otherwise unneeded register B, which frees the accumulator for more profitable work. The data byte is not needed in any register—it is merely read to make it available to the external latch. Because the instruction set requires a destination for any read instruction, the 8080 reads the byte into a surplus register.



Fig 5 Poor man's DMA. Adding one NAND gate to 8080 microcomputer system provides poor man's DMA. NAND gate forces a direct memory-to-output data transfer to occur whenever program reads RAM with address bit A15 set, eliminating need for several instructions and doubling the processor's output transfer rate

With this novel programming technique, the accumulator is not used while outputting data. Instead, it is devoted to streamlining the loop exit-condition checking. The accumulator is eight bits wide with a capability to count up to 256. Unfortunately, the tape formatter may be called upon to record blocks of several thousand bytes, so the accumulator cannot be utilized as a simple loop counter.

Nevertheless, loop termination testing can be done with only one instruction, CMP H, if data to be recorded are placed properly in memory. This instruction compares the number in the accumulator with the number in the H register, and sets flags that control the succeeding conditional jump. The H register contains half of the memory pointer—the most significant eight bits. Thus, the program compares an 8-bit value called HLIMIT + A15 (held in the accumulator) with the most significant eight bits of the memory pointer. The loop can terminate only when the most significant half of the pointer changes. This change occurs at addresses that are multiples of 256. To detect the end of the loop properly, the memory image of the block to be recorded must end exactly at one of these boundaries. Since there is no restriction on where the block can start, blocks of any size can still be accommodated. The only advance preparation needed is to assure that the block is properly positioned in RAM before the write loop is executed.

This extremely short program loop, and the gate circuit that made it possible, increased the programmed output transfer rate from 38.4k to 76.9k bytes/s. In

```
                                                    Timing
        LXI   H,BUFSTART+A15    ; POINT AT FIRST BYTE
        LDA   HLIMIT            ; PUT HLIMIT IN A
LOOP:
        MOV   B,M               ; HARDWARE GRABS BYTE      7
        INX   H                 ; POINT AT NEXT BYTE       5
        CMP   H                 ; SEE IF H = HLIMIT        4
        JNX   LOOP              ; JUMP BACK IF NOT        10
                                                          --
                                                          26 clock cycles
                                                          (13 μs)
```

Fig. 6 Final output program. 4-instruction loop outputs one byte every 13 μs, exceeding timing goal. First instruction in loop triggers direct memory-to-output transfer. INX H updates memory address register. Since accumulator is no longer needed for output, it is used to simplify loop control to just two instructions

the buffered formatter design, this rate is set to the desired 72k bytes/s by slowing down the 8080 clock. The other 15 required transfer rates are provided by other software loops with built-in time delay instructions. Although the buffered formatter is intended only for tape speeds of up to 45 in/s, incorporating double-speed 8080 components and doubling the clock frequency will extend formatter capability to 90 in/s.

Reading is Easier

Reading tape data into RAM is accomplished with an input version of "poor man's DMA." Problems here are that the number of characters to be read is unknown (almost any block size may be encountered) and timing of the external read data clock is subject to tape speed inaccuracies and jitter. Even though a very simple software loop can be used to input data and increment to the next RAM address, hardware must be provided to synchronize the software to the external clock and to escape from the loop when a complete block has been read.

To synchronize with the external tape clock, use is made of the 8080 READY interface line. While this signal is low, the 8080 pauses during the memory access portion of a machine cycle. The circuitry illustrated in Fig 7 detects the moment when the software loop is writing to RAM, again using address line A15 to activate a direct memory transfer. In this case, however, the DMA circuitry also "freezes" the microprocessor until the next byte of data is clocked in from the tape transport. Once the byte has been received, the READY signal is set high again, permitting the software to continue in its loop, incrementing the memory address register, and restarting the cycle. This process will continue indefinitely, with the software stuck in a never-ending input loop, until the MPD (missing pulse detector) circuit detects the end of a data block. This occurrence interrupts the 8080, providing an escape from the loop so that normal processing can resume. Trigger time of the MPD is controlled from a few microcomputer output bits that are initialized at power-on for the transfer rate in use, again using software and programmable read-only memory tables to avoid the use of complex timing hardware.

Conclusions

This microprocessor-based formatter design originally appeared to be impractical because low cost MOS microprocessors were apparently too slow to handle 45-in/s magnetic tape data. Undoubtedly, a smart formatter might have been developed by adding a microprocessor to a conventional formatter, but this would be an expensive solution. Instead, a microprocessor's capabilities were stretched, using a synergistic blend of hardware and software to double its speed. This made it possible to replace most of the circuitry found in present formatters with a microcomputer. Once this was accomplished, several advanced capabilities could be added by merely including more software.

The result is a tape formatter that uses fewer components than its TTL-based predecessors while providing



Fig 7 Input version of poor man's DMA. Tape data are read directly into RAM while small software loop provides sequential addresses. Ready flip-flop synchronizes program to external clock by stopping processor until next tape character arrives. MPD (missing pulse detector) senses end of data block and terminates loop by interrupting microprocessor

new capabilities. The microprocessor inherently provides data buffering, and this is exploited to full advantage by adding a software-controlled interface compatible with the IEEE-488 standard. Additional software makes it possible to handle tape transports at all common speeds and densities without changing any components, to search a tape for a desired file or block, and to automatically reread, rewrite, or correct tape errors. If these kinds of capabilities were implemented with TTL, the resulting design would be prohibitively expensive. With a microcomputer, however, these features are attained by adding only a couple of program storage memories to the hardware cost.

Bibliography

Recorded Magnetic Tape for Information Interchange (ANSI X3.2.1/426), American National Standards Institute

8080 Microcomputer System User's Manual, Intel Corp, Santa Clara, Calif, 1975

OEM User's Manual for Tape Transports, Pertec Corp, Chatsworth, Calif, 1973

A. Scott McPhillips is a microprocessor design consultant at IDEAS. His experience includes the application of microprocessors to numerous tasks, and the design of magnetic tape transports and formatters. He holds a BSEE degree from the University of Maryland.

"I've been digitized!"

and TALOS does it best!

Sound a little strange . . . Not Really! Through the wizardry of a Talos standard, rear-projected or back-lighted Digitizer used in conjunction with a computerized study of x-rays, vital pictures of Debra's beautiful eyes or teeth, her lungs, her perfect bone structure can be digitized and committed to the memory of some lucky computer. Further, her entire wardrobe can be created with the aid of a TALOS digitizer.

Digitizers are the eyes of a computer and Talos CYBERGRAPH™ units have "seen" a lot of applications.

- Advertising
- Agriculture
- Aircraft Control
- Animal Research
- Architecture
- Astronomy
- Astrophysics
- Cartography
- Cartooning
- Cellular Research
- Clothing
- Data Reduction
- Dental
- Design
- Drafting
- Education
- Engineering
- Environmental Studies
- Forrestry
- Interactive Graphics
- Inventory Control
- Land Reclamation
- Mapping
- Medical
- Military
- Movies
- Natural Resources
- Order Entry
- Orthodontia
- Pathology
- Pattern Generation
- P. C. Boards
- Seismology
- Stress Analysis
- Text Editing
- Topography
- Waveform Studies
- Weather Forecasting

So, if you want a digitizer to help you visualize, imagine, create, diagnose, etc., ask for Talos. We have the widest range of sizes and configurations available anywhere.

Talos **really** does do it best!

talos

For the complete story contact: TALOS SYSTEMS INC.

7419 East Helm Drive • Scottsdale, Arizona 85260 • (602) 948-6540

CIRCLE 150 ON INQUIRY CARD

APPLICATION NOTE

Pattern Sensitivity Techniques for Testing CCD Memories

Ivan D. Vancov*

Bulgarian Academy of Sciences
Sofia, Bulgaria

Use of RAM test programs with serial shift CCD memories requires time-consuming and expensive measurements. By analyzing parameter and pattern sensitivities, simplified but sufficiently thorough tests for these memories have been developed that reduce safe testing from hours to minutes, while resulting in significant cost savings

Recent appearance of charge-coupled device memories on the market has brought about an increasing range of information storage applications. As with other semiconductor memory types, sensitive operating parameters and data patterns must be thoroughly checked using timely, cost-effective test procedures. The former refers to such critical parameters as shift period and drain supply voltage and the latter to the applied test patterns of various combinations of logic 1s and 0s. A number of standard memory test programs, such as MARCH (write and read/write forward and backward), WAKPAT (walking pattern or ripple), GALPAT (galloping 1s and 0s), and others,[1,2] were developed mainly for testing random-access memory devices and systems.

These common tests have proved to be highly effective. For their program execution, however, a specialized high speed test system such as the Macrodata MD-104 or MD-154 is required, which usually is not available to memory users. Furthermore, the realization of these memory test programs by a commercial minicomputer is a time-consuming procedure due to the slow operation of the program interface channel, especially for a charge-coupled device (CCD) memory with a minimum size of 16k. For example, a checkout of the Intel 2416 CCD memory[3] by a single WAKPAT test pattern using a Multi-20 minicomputer (manufactured by Intertechnique, France) takes about six hours. Consequently, by exploiting the device's internal organization, simpler and more conclusive parameter and pattern test programs have been successfully derived to save both cost and time.

Memory Device Organization

A synchronously clocked 16,384-bit CCD memory, the Intel 2416 is organized as 64 parallel, independent, recirculating shift registers (SRs) of 256 bits each with a refresh amplifier at each end. Shifts of 1 bit are initiated simultaneously within all 64 SRs by exercising the 4-phase clock signals. During the time between each shift, any one of the 64 SRs can be accessed for an input/output (I/O)

*The work described was performed by the author at the Laboratoire d'Electronique et de Technologie de l'Informatique du Centre d'Étude Nucléaire de Grenoble, France.

TABLE 1

Lowest Drain Supply Voltage Values for Normal CCD Operation

Test Program \ t_{SP} (μs)	0.65	0.70	0.75	0.8	0.9	1.0	1.2	1.4	1.6	9.0	20
1. Write All 0s	11.1	9.6	9.5	9.5	9.3	9.3	9.2	9.0	8.9	8.9	9.0
2. Write All 1s	11.6	9.7	9.0	8.9	8.8	8.7	8.5	8.3	8.3	8.2	8.3
3. 0 Between 1s	11.5	10.7	10.3	9.9	9.6	9.5	9.4	9.3	9.2	8.9	9.0
4. 1 Between 0s	11.1	9.8	9.2	8.9	8.8	8.7	8.6	8.5	8.5	8.2	8.3
5. 00110011...	—	9.8	9.5	9.4	9.3	9.2	9.1	9.0	9.0	9.0	9.1
6. 010101...	—	10.5	10.1	9.7	9.4	9.3	9.2	9.1	9.0	9.2	9.3
7. 0101.../1010.../0101...	—	10.9	10.3	9.9	9.7	9.5	9.4	9.3	9.2	9.3	9.4

operation by applying an appropriate 6-bit address input through the 1-of-64 decoder. Information stored in any (no matter which) bit location is constantly circulating through each SR, ie, each recorded logic 0 or 1 level is incremented through each of the 256 bit locations of its particular SR. Therefore, the device organization combines serial and random address memory functions for the 64 SRs.

Test Program Development

Upon examination of the memory's internal structure, it is reasonable to assume that there is no outstanding advantage in checking all 64 x 256 or 16,384 bit locations of the device using a separate test word, as was done in the previously mentioned test programs. It should be sufficient to write the test information into one bit location of each SR, and then test the remaining SR bit locations by 255 shifts.

In a multibit memory system at least one separate 2416 device must be used for each bit because only one SR from the chip is accessible for an I/O operation at the same time. Interactions between these separate devices, ie, between the different bits of the memory system, are not probable. Thus, all memory system bits can be tested independently, by the same information pattern; ie, the test words could contain the same logic level in all memory bits, such as 0000...0 or 1111...1.

Test Programs

Using previously developed SR test patterns[2] and taking into account the unique properties of CCD memories, the following test programs were devised.

1. *Write All 0s or 1s.* All logic 0s or all logic 1s are written into every bit location of the memory. Each location is read out and verified, in turn, for correctness. This is an absolute minimum test necessary in order to check every SR as well as addressing.

2. *0 Between 1s or 1 Between 0s.* This modification to the Walking Pattern Shift Register Test (SRWALK) is realized by initially writing all 1s throughout the memory. A logic 0 is then written into one bit location of SR-n, where n is any one of 64 SRs. Next, while reading and checking for information destruction, SR-n is shifted 256 times. The 0 bit location, surrounded on all sides by 1s, is incremented through all 256 SR locations (cells) until it returns to its starting location. This tests for worst case charge interactions between neighboring cells of a CCD. Next, a logic 1 is rewritten in place of the 0 bit. In SR-n + 1, a logic 0 is then written into the same bit location as described for SR-n; SR-n + 1 is likewise incremented, read, and checked using the same shifting technique. After rewriting logic 1, the succeeding SR is tested until all 64 SRs have been checked out. Similarly, the 1 between 0s test program can be carried out by first writing all 0s throughout the memory and then using a single logic 1 as the check bit.

3. *001100110011....0011 Test.* This program, based on the alternating word pattern shift register test (ALTWOR), is recommended as a test for device sensitivity to a sequence of all possible information transitions—such as 0 to 0, 0 to 1, 1 to 1, and 1 to 0. A 001100110011....0011 test pattern is written into each SR of the CCD, and all addresses are read, in turn, to verify correctness.

4. *01010101....01 Test.* Alternate 0s and 1s are written into ascending bit locations of each SR, starting with logic 0. Each bit location is then read out and checked for information destruction, to test for sensitivity to the successive 0 to 1 and 1 to 0 transitions.

5. *0101.../1010.../0101.../1010... Test.* To stress the interaction between neighboring cells of different SRs, this checkerboard test pattern is used. Alternate 0s and 1s are written into all bit locations of the first SR, starting with logic 0. The same sequence, starting with logic 1, is written into the second SR. Logic 0 is the first level of the sequence in the third SR, while logic 1 starts SR-4, and so on. The device is read out and checked for information correctness in ascending bit locations.

TABLE 2

Drain Supply Voltage Values of Eight Devices Tested by Five Programs for Two Shift Periods

t_{SP} (μs)	1.0								1.5							
Memory Device / Test Program	a	b	c	d	e	f	g	h	a	b	c	d	e	f	g	h
1. 0 Between 1s	9.3	8.5	8.4	8.2	8.7	9.4	8.8	8.9	9.3	8.3	8.2	8.2	8.4	9.3	8.8	8.7
2. 1 Between 0s	9.3	8.9	8.4	8.2	8.9	9.5	8.8	8.7	8.9	8.5	8.2	8.3	8.5	9.3	8.8	8.7
3. 00110011...	9.3	8.4	8.3	8.2	8.6	9.5	8.8	8.8	9.3	8.4	8.2	8.3	8.5	9.3	8.9	8.7
4. 010101...	9.3	8.9	8.7	8.3	9.0	9.5	9.0	9.0	9.3	8.6	8.2	8.3	8.6	9.4	9.0	8.7
5. 0101.../1010.../0101...	9.3	9.0	8.8	8.4	9.2	9.6	9.1	9.3	9.3	8.6	8.2	8.3	8.6	9.4	9.0	8.7

TABLE 3

Results of Testing Same Eight CCDs Organized as Two 16k, 4-Bit and Two 64k, 1-Bit Memories

t_{SP} (μs)	1.0				1.5			
Memory Organization	16k, 4 Bits		64k, 1 Bit		16k, 4 Bits		64k, 1 Bit	
Memory Devices / Test Program	a-d	e-h	a-d	e-h	a-d	e-h	a-d	e-h
1. 0 Between 1s	9.3	9.4	9.3	9.4	9.3	9.3	9.3	9.3
2. 1 Between 0s	9.3	9.5	9.3	9.5	8.9	9.3	8.9	9.3
3. 00110011...	9.3	9.5	9.3	9.5	9.3	9.3	9.3	9.3
4. 010101...	9.3	9.5	9.3	9.5	9.3	9.4	9.3	9.4
5. 0101.../1010.../0101...	9.3	9.6	9.3	9.6	9.3	9.4	9.3	9.4

Test Results

These test programs have been implemented by a Multi-20 minicomputer, using its program interface channel and a computer program for peripheral testing. The longest test program (No. 5: 0101.../1010.../0101...) at a shift cycle time of 9 μs takes about 2 min for a 16k memory. For all test patterns, the effective limits of the drain supply voltage (V_{DD}) and shift cycle time, chosen as the most sensitive device parameters, were measured. A concurrent investigation of the influence of the V_{BB} supply voltage has disclosed that its value is not critical—the memory operated successfully under test for V_{BB} variations from 1 to 5 V.

Lowest values of drain supply voltage (V_{DDL})** at which a single 2416 device continues to operate normally are listed in Table 1. These values were obtained by running seven test programs at 11 shift periods (t_{SP}). As listed, no large variations in V_{DDL} exist in the shift period range of 1 to 20 μs. For t_{SP} values less than 1 μs, a significant increase in V_{DDL} with a decrease in shift period is observed. These results show that in the manufacturer's guaranteed range of shift period—0.75 to 9.0 μs—the device operates with a reasonable margin of change in V_{DDL}—1.7 V minimum (12.0 − 10.3) at a t_{SP} of 0.75 μs. A comparison with results from random-access memory (RAM) testing demonstrates that better stability exists for a CCD memory: V_{DDL} values for a 4k RAM[1] are 11 V for the MARCH test program and 11.9 V for the GALPAT pattern, while a V_{DDL} value of 10.3 V at 0.75 μs is obtained for the CCD memory in the worst case. The nominal value of V_{DD} for both memories is 12 V.

Table 2 gives the V_{DDL} values for eight 2416 devices at two shift periods. A comparison of the results of any two devices demonstrates no correlation in their patttern sensitivity—V_{DDL} increases in value for the same device in all test programs. It can also be seen that for some devices the pattern 0 between 1s gives higher V_{DDL} values than the pattern 1 between 0s; however, for others this effect is reversed. Most likely, for this reason, the test programs 010101... and 0101.../1010.../0101... give the maximum V_{DDL} values, since the two configurations 0 between 1s and 1 between 0s are repeated successively in these test patterns.

**Investigations show that up to the absolute maximum V_{DD} value (14 V) as prescribed by the manufacturer, there are no upper limiting values of V_{DD} under all test conditions.

Data in Table 3 were obtained by testing the same eight devices, this time divided into two groups of four (a through d and e through h). Each group was organized either as a 16k, 4-bit memory or as a 64k, 1-bit memory. A comparison of data in Table 3 with those in Table 2 shows that memories formed by devices a through d have the same V_{DDL} values as those of device a when tested separately. The same result is observed for memories formed by the second group of devices e through h, whose V_{DDL} values coincide with those of device f. Note that V_{DDL} values of devices a and f are the highest for each group; therefore, these devices determine the limit of the V_{DD} decrease for corresponding memories. Lack of change in the V_{DDL} values, when a CCD (a and f in this case) is tested separately or included in a memory system, confirms the stipulated absence of information interaction between separate bits of the memory system (the 16k, 4-bit case). Also, no interaction between the four devices forming one bit of the 64k memory system could be observed.

For comparison, the second 16k, 4-bit memory (including devices e through h) was tested by a WAKPAT program at a t_{SP} of 1 μs. The background pattern was 1010, and a complement test word was written successively in all locations, with reading and information checks of all other addresses after each new writing. The V_{DDL} value obtained—9.5 V—is equivalent to the results for the same memory when tested by 1 between 0s, 00110011..., and 010101... programs, and is below the V_{DDL} value obtained by the 0101.../1010.../0101... program (Table 3). This fact shows that simplification of CCD test programs has not decreased test efficiency.

Conclusions

The acquired results show that CCD memories, like other memory types, have pattern sensitivity over a valid range of operation, and careful testing is inevitably required. For this purpose, the proposed test programs are highly effective. By exploiting the internal CCD structure, sensitive test programs ensure sufficient testing in minimum time and can be realized economically by a standard minicomputer. For a basic evaluation at the component level, a full testing by all patterns is advisable, while for an SR memory system, the rather unsophisticated pattern of 0101.../1010.../0101... is recommended as a safe test.

Acknowledgements

The author is indebted to Messrs R. Gariod, C. Axelrad, and J. L. Lecomte who made this work possible and is thankful for the valuable advice and counseling offered by Messrs L. Chabanas and B. Thevenin.

References

1. A. Chiang and R. Standridge, "Pattern Sensitivity on 4k RAM Devices," *Computer Design*, Feb 1975, pp 88-90
2. "MD-104 LSI Test System," Technical Spec, Macrodata Corp, Woodland Hills, Calif
3. B. Papenberg, "Design and Applications of Intel's 2416 16k CCD," *Memory Design Handbook*, Intel Corp, Santa Clara, Calif, 1975, p 9.1

CITIZEN SERIES 8000 PRINTERS

heavy-duty 132 Columns 250-720 LPM Chain Printer Excellent Quality and Price

Manufactured by
CITIZEN WATCH CO.
Tokyo, Japan



Exterior view of cabinet

Interior view of printer mechanism

Font train



If you are an OEM in the computer industry, you know the crucial importance of gaining a competitive edge. We know it, too.

CITIZEN is the largest independent line printer manufacturer in Japan. We are new in the U.S. market. A very tough market. And we are growing fast because we offer our clients a very advantageous price/performance mix. The competitive edge.

The Citizen Series 8000 Line Printers are available in two basic models, with the following minimum speeds:

Model 8201	Model 8601
298 LPM — 48 characters	720 LPM
250 LPM — 64 characters	600 LPM
188 LPM — 96 characters	444 LPM

Full details on the competitive edge offered by the Citizen Series 8000 printers are yours for the asking. Call or write to:

Mike M. Fujiwara
Marketing Manager, Line Printers
C. ITOH ELECTRONICS, INC.
5301 Beethoven Street
Los Angeles, California 90066
Telephone: 213/390-7778

Distributed by:
C. ITOH ELECTRONICS, INC.
Part of C. Itoh & Co., Ltd., a firm with 118 years of international marketing experience.

CIRCLE 83 ON INQUIRY CARD

TECH BRIEF

Binary/BCD-to-ASCII Data Converter

Easier to expand and troubleshoot than ROM-implemented converters

A digital data converter inputs multiple precision binary words, converts the data to multiple precision BCD data, and routes these data back to the computer. The converter accepts two computer words from a 16-bit minicomputer (32 bits total) and converts them to 80 bits of BCD standardized (ASCII) data. Compared to previous data converters, this method reduces the required computer software, time, and memory.

The converter can readily change its conversion base. Unlike prior converters which use a ROM dedicated to base 10 only, the converter base can be readily changed without the need for a new gate structure for each base changeover.

Each decade of the converter, as partially illustrated, consists of a 7483 4-bit adder, a 74L95 4-bit parallel-in/parallel-out right shift register, and one-third of a 74H11 AND gate. The 7483 continually adds three to the contents of its associated shift register. If the contents are four or less, the most significant output bit is zero. If the contents are five or more, this bit is one.

The bit state controls the mode of the associated register. If the bit is one, then the sum of three plus the contents of the register is replaced but shifted one bit to the right. The least significant bit is either shifted in serially or loaded in parallel.

Support software has optional leading zero suppression and stores the results where desired, requiring approximately 100 locations of memory depending on the computer which is interfaced to this converter. Actual conversion time for 32 bits is 72 μs, and the range is zero to $(2^{32}-1)$. Master clock frequency is 500 kHz; conversion time is 36 pulses of this clock. If clock frequency is increased, conversion times (using faster registers) as low as 10 μs are possible. Time to execute one complete passthrough, and software for a 32-bit conversion and zero suppression is about 240 μs.



Two decades of data converter are shown to indicate how 7483 controls shift register in such a way as to be parallel loaded or shifted one place to the right

Note

This work was done by Anthony J. Miller of Goddard Space Flight Center. For further information, write to: Donald S. Friedman, Technical Utilization Officer, Goddard Space Flight Center, Code 704.1, Greenbelt, MD 20771.

Patent Status

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, John O. Tresansky, Goddard Space Flight Center, Mail Code: 204, Greenbelt, MD 20771. Refer to GSC-12044.

This document was prepared under the sponsorship of the National Aeronautics and Space Administration. Neither the United States Government nor any person acting on behalf of the United States Government assumes any liability resulting from the use of the information contained in this document, or warrants that such use will be free from privately owned rights.

Epiview opens a window to your datacomm line

EPIVIEW, a new data communications line monitor from Epicom, Inc., enables you to visually verify and analyze your datacomm dialog. Available in both portable and rack-mounted configurations, the instrument operates in full-duplex, synchronous or asynchronous, at communication speeds to 100,000 BPS. Users may select CRT display in ASCII, EBCDIC or hexadecimal pairs, with other disciplines optionally available. Character blinking or reverse imaging is used to annotate segments of the data when selectable events occur (such as RTS, TRUE, etc.).

EPIVIEW may be used as a stand-alone, real-time line monitoring device, or it may be teamed with an Epicom EPITAPE recorder (or other data-capture device) for deferred traffic analysis, trouble-shooting or other diagnostic procedures.

Best of all, EPIVIEW is easy to operate, can be connected to line or recorder with minimum cabling, and is available at a surprisingly low price.

For full technical details, contact Epicom, Inc. today.



EPICOM, INC.

592 North Douglas Ave., Altamonte Springs, FL 32701 Telephone 305/869-5000

CIRCLE 151 ON INQUIRY CARD

TECH BRIEF

Microprogramming for Real-Time Data Acquisition

Microprogrammed firmware asynchronously handles transmit and receive functions

A microprogramming (firmware) technique has a polling interval of 100 μs and satisfies the following requirements. It allows full data bus duplex operation; measurement data can be obtained by polling various hardware interface modules on a 1M bit data bus; polling functions are transparent to software operations; polling is accomplished on a cyclic basis with a fixed interval between polls; verification of the proper response is performed as part of the receive function; the transmit function is able to interrupt the receive function; and "off-the-shelf" processors are utilized.



Fig 1 Transmit microcode trap logic is conditioned by a preset clock. A measurement request or issuance of a command is controlled by a set of software-initialized polling tables



Fig 2 Receive microcode trap logic is conditioned by the transmit/receive hardware when a response is returned on the data bus

The firmware package is a trap-initiated microprogramming technique that asynchronously handles a transmit-and-receive (T/R) function as shown in Figs 1 and 2. In addition, microcode traps used to perform the assigned tasks require expansion of the computer direct-memory-exchange (DMX) trap capability to include recognition of a user-implemented trap. This technique may be implemented on any computer system having a user-writable control store and microcode trap logic.

The data bus is controlled by a transmitter/receiver which interfaces with the processor in control. Transmit microcode trap logic, as shown in Fig 1, is conditioned by a preset clock. Operations performed on the bus may be a request for a measurement or the issuance of a command. The sequence of these operations is controlled by a set of software-initialized polling tables. Multiple tables provide for a change of sampling rates.

The receive microcode trap logic, as shown in Fig 2, is conditioned by the T/R hardware when a response is returned on the bus. An input sequence acquires the data and performs certain validity checks. Any resultant errors from these operations are reported to software. Some of the errors, considered catastrophic, cause the microcode to inhibit all further operations on the bus.

Note

This work was done by Frank J. Patella of IBM Corp for Kennedy Space Center. For further information, write to: Raymond J. Cerrato, Technical Utilization Officer, John F. Kennedy Space Center, Code SA-RTP, Kennedy Space Center, FL 32899. (KSC-11027).

This document was prepared under the sponsorship of the National Aeronautics and Space Administration. Neither the United States Government nor any person acting on behalf of the United States Government assumes any liability resulting from the use of the information contained in this document, or warrants that such use will be free from privately owned rights.



Special connectors are an old family custom.

We've been designing and manufacturing connectors and interconnection systems for special and custom applications for the telecommunications and data processing industries for over two decades.

Over the years, we've developed the technical skills and knowledge of materials to produce reliable connector systems at competitive prices.

Stringent quality control is applied during in-house production, from the insulator body to the contact.

You make the choice:

Contact design—bifurcated bellows, cantilever or single-beam

Plating selection—gold dot, select plate, inlay or overall

Material selection—thermoplastic or thermoset

Call us before you start your design.

Contact GTE Sylvania, Connector Products Operation, Box 29, Titusville, PA 16354. Phone: 814-589-7071.

Remember, good connections run in our family.

GTE SYLVANIA

CIRCLE 51 ON INQUIRY CARD

THE WORLD'S A SOMEWHAT LESS

In the spring of 1962, Dataproducts began building printers.

And a reputation.

Today, we design and build printers (in the United States and Europe) for OEM's and their end-users the world over.

We are dedicated to producing the finest printers money can buy.

We will never copy.

We will never offer you a printer whose only virtue is low price.

We will never compromise with quality. And neither should you.

Everything from 80 CPS to 2000 LPM

We have a printer for every purpose.

We make fast printers and slow ones; big printers and little ones.

We make printers for high-volume EDP, for small business systems, for message terminals, and machine readable applications.

We make impact and nonimpact printers;

T-80 THERMAL PRINTER—80 CPS



B-180 BAND PRINTER—180 LPM

M-200 MATRIX PRINTER—200 LPM

2290 LINE PRINTER—900 LPM

2470 LINE PRINTER—1250-2000 LPM

2550 CHARABAND PRINTER—1500-2000 LPM

FINEST PRINTERS: THAN HUMBLE AD.

we make matrix and full character printers; and we make them for commercial as well as military systems.

We have what you need.

Our printers work and work and work

The computer industry is crowded with printer companies.

But only one dotes on dependability.

Only one consistently comes up with innovations like the Mark IV and Mark V friction-free hammers, the 14-wire dual-column matrix head, the unique self-cooling thermal print head, the Charaband horizontal font carrier, and many more.

And only one is the largest independent printer company in the world.

Dataproducts is the one.

We're not just a printer company.

We're *the* printer company.

And we're setting the stage for a whole New Era in printers.



B-300 BAND PRINTER—300 LPM

2230 LINE PRINTER—300 LPM

2260 LINE PRINTER—600 LPM

TEMPEST LINE PRINTERS—
300, 600, & 900 LPM

2910 MILITARIZED PRINTER—
356-1110 LPM

A NEW ERA

Dataproducts

THE PRINTER COMPANY

6219 DE SOTO AVE., WOODLAND HILLS, CA. 91365, TEL: (213) 887-8451
DARMSTAEDTER LANDSTRASSE 199, FRANKFURT, W. GERMANY, TEL: 681-034

CIRCLE 52 ON INQUIRY CARD

DESIGN NOTE

Two-Step Procedure Improves CRC Mechanism

Patrick J. Fortune

Argonne National Laboratory
Argonne, Illinois

A 2-step technique modifies conventional CRC error detection schemes to overcome the issues involved with erroneous leading or trailing 0 bits in bit-oriented protocols by setting the CRC shift register to all 1s and then transmitting the inverted remainder as check bits

Conventional usage of a cyclic redundancy check code to detect transmission errors in a data stream corresponds to appending check bits after each data block at the transmitter and comparing them to the computed bits using the data as detected at the receiver. That is, consider that N bits in a data message represent coefficients (0 or 1) of a polynomial of N − 1 degree, D(x), and that the remainder (the check bits) which results when D(x) is divided modulo-2 by a generator polynomial, $P_n(x)$ of degree n, is appended to the data. Hence, the actual transmitted message is

$$M(x) = x^n D(x) + R_{n-1}(x) \quad (1)$$

where $R_{n-1}(x)$ is defined by

$$x^n D(x)/P(x) = Q(x) + R_{n-1}(x)/P_n(x) \quad (2)$$

or

$$M(x) = Q(x)\, P_n(x) \quad (3)$$

and the division is understood to be modulo-2, equivalent to the Exclusive-OR function. The same operations are performed at the receiver, and since modulo-2 arithmetic is used (so that the results of addition and subtraction are the same), the remainder generated will be zero (by equation 3) if no detectable errors have occurred in transmission.

The indicated operations can be performed by hardware, software, or a combination of the two. Techniques used to carry out the division must, of course, be combined with techniques to determine where the data bits of a message begin and end, so that the division operation can be started and stopped appropriately. A hardware technique to determine R(x) given D(x) and $P_n(x)$ using a feedback shift register has been discussed.[1]

In essence this technique amounts to shifting bits out of a shift register which contains the remainder, Exclusive-ORing the bit shifted out with the next data bit, and Exclusive-ORing the result back in at the positions corresponding to the 1 bits in the generating polynomial. A diagram of the shift register approach for generating polynomial $P_5(x) = x^5 + x^2 + 1$ is shown in Fig 1. As noted in Ref 1, application of this technique as outlined can lead to problems when used with recently popular bit-oriented protocols, such as SDLC (synchronous data link control), HDLC (high level data link control), and ADCCP (advanced data communication control procedures). In particular,

(a) if in the shift register implementation alluded to above the contents of the register which contains the remainder are preset to zero, erroneous leading 0 bits will not be detected;

Want mass terminations for I/O interconnecting? We have the widest choice.



Now Scotchflex brand DELTA Connectors bring the proved labor-savings of 3M's mass termination system to subminiature connections. DELTA series components include pin and socket connectors, junction shells, 25-conductor flat cable and strain relief clips. These system assemblies interface directly with all other industry standard "D" series subminiature connectors. They're also compatible with all connectors in our complete Scotchflex line.



A family of Scotchflex male plug connectors is now available in sizes from 10 to 50 contacts to mate with Scotchflex socket connectors for T-tap or mid-span connections or rack and panel applications.

"Scotchflex" is a registered trademark of 3M Co.



Our broad line of Scotchflex socket connectors includes a variety of 12 different sizes and center spacings to fit standard wrap panels and custom configurations. Also offered are Scotchflex card-edge connectors in sizes for 20 to 50 conductors.

Only 3M offers you so wide a choice of mass terminating flat cable and system components for fast, economical assembly of I/O interconnections between modules or sub-assemblies in your equipment designs. Plus off-the-shelf availability from experienced distributors, and the unmatched experience of the people who pioneered electronic mass terminations.

For more information on Scotchflex products call 612-733-3350.

Scotchflex® systems from 3M. The source.

3M COMPANY

See our catalog in EEM, page 2256

You've already conceptualized and developed the software...

Introducing Tektronix' 8001 Microprocessor Lab: a total hardware debugging environment for the design of microprocessor-based products. Featuring multiple microprocessor support, in-prototype emulation, and real-time trace, the 8001 provides a comprehensive technique for exercising and debugging already developed software on your prototype.

In the tradition of the TEKTRONIX 8002, this new microprocessor design aid offers support for many types of microprocessors, including the Intel 8080, Motorola 6800, Texas Instruments 9900, and Zilog Z-80. The 8001 can support both 8 and 16-bit microprocessors.

The Microprocessor Lab also offers three emulation modes for system-controlled, partial, and full emulation . . . on the same microprocessor you'll be using in the finished product. A memory mapping technique for gradually releasing program functions to the prototype and systematically isolating program errors. A real-time trace option which allows you to monitor microprocessor activity at full speed.

And one other key feature: the comprehensive service and support that only an instrument company can provide.

...now put it to the test in a total hardware debugging environment.

A Typical Development Sequence Using The 8001

The initial design cycle has been completed. Software and hardware functions have been assigned; prototype hardware has been built and preliminary debugging checks have been run using the 8001; software has been developed and partially debugged on an external software development system. The program is downloaded to the Microprocessor Lab through any RS-232-C compatible medium (such as modem or paper tape), and the critical integration phase begins.

The program is first tested in system-controlled emulation (mode 0) on the 8001 *emulator processor.* This "dry run" enables you to detect any software errors that may not have shown up at the assembly level.

In partial and full emulation (modes 1 and 2), the program is exercised on the prototype with the 8001 *prototype control probe* connected to the

THE TEKTRONIX 8001 MICROPROCESSOR LAB



emulator processor at one end and plugged into the empty microprocessor socket in prototype circuitry at the other. This lets you integrate in stages while you maintain control through the 8001.

In partial emulation, the program runs using 8001 memory space and prototype I/O and clock. With the memory mapping feature, memory may be mapped over to the prototype by address blocks. This enables you to localize program errors . . . or even "patch" around a faulty bit or routine. Throughout partial emulation, program activity may be accessed via the powerful 8001 *debugging system,* which allows you to trace, set breakpoints, examine and change memory and register contents.

In full emulation, the program is exercised on the now stand-alone prototytpe; you still maintain complete control through the Microprocessor Lab. All I/O and timing functions are directed by the prototype; all memory has been mapped over to the prototype; and only the prototype control probe is still in place, emulating the target microprocessor. Although the prototype is effectively freestanding, then, you still direct program activity, at the prototype end of the probe, from the 8001.

Real-Time Trace

With the optional *real time prototype analyzer,* you can dynamically monitor the prototype address bus, data bus, and up to eight other locations on the prototype circuit board. Prototype activity is monitored at full speed, without stopping or slowing up the working microprocessor. This enables you to locate critical timing problems and hardware/software sequence problems during partial and full emulation.

In this way, the 8001 provides a *total hardware debugging environment* supporting each successive phase of the product development cycle. After downloading object code, the designer proceeds from hardware test and software debugging, to the sequential integration of program and circuit, to final integration and test of the stand-alone product. The real-time prototype analyzer enhances partial and full emulation by allowing the user to monitor and access prototype activity in real time.

A Commitment To Microprocessor Design Aids

A growing product family . . . a full line of options and peripherals . . . a staff of highly trained microprocessor design aid Specialists and Field Engineers . . . a comprehensive service program . . . and years of experience in designing our own microprocessor-based products: all these things are a measure of Tektronix' commitment to the 8001 Microprocessor Lab.

For a demonstration of this innovative new product or for more information, write Tektronix, Inc., P.O. Box 500, Beaverton, Oregon 97077.

Tektronix®
COMMITTED TO EXCELLENCE

For technical data, circle 54 on Inquiry Card.
For a demonstration, circle 55 on Inquiry Card.



Fig 1 Linear feedback shift register for implementing division by $P_5(x) = x^5 + x^2 + 1$. When data block to be transmitted passes through this shift register, it is effectively divided by the polynomial, producing either string of redundant check bits for end of message or indication of errors picked up during message transmission

(b) if the final state of the register is also zero (essentially because of equation 3), the erroneous trailing 0 bits will not be detected.

Appropriate solutions to these problems have been proposed.[1] One such solution will be discussed and clarified, indicating its implications regarding the design and implementation of error checking hardware to be used with the above protocols.

2-Step Technique

The sources of the above problems can be eliminated by using a 2-step implementation prescribed by the SDLC, HDLC, and ADCCP protocols. First, the contents of the shift register are preset to an all 1s state prior to computation of the cyclic redundancy check (CRC) bits; this permits the detection of erroneous leading 0s. Second, the CRC bits are inverted (ie, complemented) prior to transmission to permit the detection of erroneous trailing 0s. The second step results in a unique nonzero final state of the shift register at the receiver if no errors have occurred in transmission. This final state's specific form depends only on the generating polynomial. The issues involved in selecting a particular CRC polynomial include the maximum size of the transmitted data block, the probabilities of both random bit errors and burst errors in the communication channel, the rate of undetected errors which can be tolerated by the users, and the overhead incurred by transmitting the CRC bits along with the data bits. The determination of the error detecting properties of a given $P_n(x)$ is a nontrivial problem and is discussed by Peterson and Brown.[2]

To illustrate the 2-step procedure, consider a transmission in which the data bits are 00111011 and the generating polynomial is 100101. These data and CRC bits correspond to the polynomials $D(x) = x^5 + x^4 + x^3 + x + 1$ and $P_5(x) = x^5 + x^2 + 1$, respectively. The first step in computing the CRC bits, using equations 1 and 2, amounts to forming the quotient $x^5D(x)/P_5(x)$. The $x^5D(x)$ term is represented by the bits 0011101100000, as multiplication by x^5 amounts to appending five 0 bits to the right of the data bits. Now, to eliminate the problem associated with erroneous leading 0s, the procedure given by equations 1 and 2 has been modified by requiring that the shift register in Fig 1 be preset to an all 1s state. In terms of the data polynomial, this is equivalent to carrying out the modulo-2 addition of the polynomial $F(x) = x^8 (x^4 + x^3 + x^2 + x + 1)$ to $x^5D(x)$; in terms of the actual data bits, this amounts to Exclusive-ORing the first five bits of $x^5D(x)$ with the five bits 11111. Thus, computation of the CRC bits requires dividing the sum $F(x) + x^5D(x)$ by $P_5(x)$ using modulo-2 arithmetic.

In general, the generating polynomial is not a factor of the dividend; therefore, the division will not come out even, ie, there will be a remainder. It is this remainder, then, that is complemented and used to replace the five added 0s in $x^5D(x)$, thereby forming the final transmitted message. In the case at hand, the results are

TABLE 1

Shift Register States in CRC Procedure Used in Bit-Oriented Protocols

	Shift Register State		Data Message Bits	
Nonzero Initial State	11111			
	11011		0	
	11001		0	
	01100		1	
	10010	D(x)	1	M(x)
	11101		1	
	11010		0	
	11001		1	
Remainder—complemented and sent as CRC bits	01100		1	
	10010		1	
	11101	Inverted	1	
	11010	CRC	0	
	01101	Bits	0	
Unique nonzero final state	00110		1	

Note: CRC bits (11001) are inverted remainder bits which are concatenated to the data bits to form transmitted message M(x).

"After a head-to-head MTBF comparison, Digi-Data was Unitote-Regitel's choice"

George Groth — *Unitote-Regitel V.P., Engineering*

"When you make point-of-sales systems for retail stores, your customers won't tolerate excessive downtime. And, since our reputation as a P.O.S. system pioneer is in the balance, we make doubly sure our System 430 has a synchronous tape drive that will last.

Unitote, a Digi-Data user since 1963, faced a decision to consider switching to another tape drive used by Regitel, a company acquired in 1972. However, when actual field service records for both tape drives were compared head-to-head, Digi-Data was selected. Continuing field records now show that the actual 41-month MTBF of the Digi-Data drive achieves a 33% edge, while the Formatter's 60-month MTBF was 2½ times better than the other tape drive.

This MTBF advantage, plus prices under competitive drives made Digi-Data the clear-cut choice for all three Unitote-Regitel systems. Five different Digi-Data drives are used . . . each at a remote (in-store) or main (multi-store) central processor where reliability is paramount."

Through enhanced tape-handling features and ultimate design simplicity, Digi-Data drives are daily insurance against downtime for Unitote-Regitel P.O.S. systems customers. And that's what our business is all about.

DIGI-DATA CORPORATION
8580 Dorsey Run Road, Jessup, MD 20794
(301) 498-0200

® . . . First in Value!

CIRCLE 56 ON INQUIRY CARD

Motorola's introducing for low cost, high



the one-chip MC3870 volume applications

It's #72 on Motorola's list of over 100 new microcomputer components for 1977

Introduction of the MC3870, a contractual, mask-exchange 3870 second source, clearly meets Motorola's commitment to excellence in the low-end, one-chip microcomputer product segment. Coupled with Motorola's huge production capability, it maximizes cost-effectiveness for a wide range of low-cost, high-volume control and logic replacement applications.

The MC3870 superbly complements the soon-to-be introduced single-chip MC6801 and the present two-chip MC6802-MC6846 basic system, for outstanding total product coverage all the way from the low-end through the MC6800, MC68A00, and the MC68B00.

The MC3870—tops in its class because it features:

- ☐ Low Price—Well Under $10.00 in Plastic, 1,000 Quantity
- ☐ Full 2048-Byte Mask-Programmable ROM
- ☐ 32-Bits (4 Ports) TTL Compatible I/O
- ☐ 64 Bytes of RAM
- ☐ Programmable Binary Timer
- ☐ Single +5 V ± 10% Supply
- ☐ Crystal, LC, RC, External or Internal Time Base
- ☐ External Interrupt
- ☐ Low Power — 275 mW (typ)

It's available in both plastic and ceramic 40-pin packages.



Complete MC3870 support

System development support is a necessity for any microcomputer, and Motorola supplies it for the MC3870 in an EXORciser*-based package, with Cross Assembler and a plug-in emulator module. The emulator includes the debug software package and provides debug capability within the user's system.

M6800 Family continues expansion

New introductions include temperature and package versions of the MPU, ACIA, SSDA and memories. Faster versions of the 16K and 32K ROMs are also being introduced, as is the 1.5-MHz version of the Advanced Data Link Controller.

Let us demonstrate how we can serve your systems requirements. Use the coupon, today.

*Trademark of Motorola Inc.

CDMC3870

To: MOTOROLA SEMICONDUCTOR PRODUCTS, INC.
DIRECT ACTION
Motorola Microproducts, 3501 Ed Bluestein Blvd., Austin, Texas 78721

I have an immediate requirement. Please call me. Phone _____

My application is: _____

_____

NAME _____ TITLE _____

FIRM _____ DEPT. _____

ADDRESS _____

CITY/STATE/ZIP _____

MOTOROLA Semiconductors
The mind to imagine... the skill to do.

CIRCLE 57 ON INQUIRY CARD

$$\frac{1100001100000}{100101} = 0000011011110 + \frac{00110}{100101}$$

so that $\bar{R} = 11001$ and the transmitted message is 0011101111001.

This message is again divided by 100101 at the receiver and if no errors have occurred in transmission, the final result after division will be the unique nonzero remainder noted above. The states of the shift register at the receiver for this same example using the hardware of Fig 1 are presented in Table 1. The remainder (in the shift register) at the end of the data bits is 01100, with most significant bit (MSB) on the right so that it corresponds to $0(x^4) + 1(x^3) + 1(x^2) + 0(x) + 0(1) = x^3 + x^2$. Thus, the complement, 10011 is transmitted right-most bit first. Also, note that the final shift register state contains the result 00110 (x^0 through x^4), which represents the unique nonzero remainder.

This approach to the elimination of erroneous leading and trailing 0s can be clarified by using the following "longhand" technique to carry out the CRC computation that takes place at the receiver. Assume that it is known where the CRC bits start; the objective is to divide the 13 message bits (0011101111001) by the fifth-order generating polynomial (100101) one character at a time. Character size is defined to be one less than the number of bits in the polynomial; in this case, character size is five bits. Division is done by Exclusive-ORing each character with the previous remainder, padding the result with on all-0 character, and then Exclusive-ORing the result with the generator polynomial. If at the end of the data bits, less than a full character is left, the number of 0s padded is equal to the number of bits in the last group of data bits; then, the division is completed until the number of significant bits in the remainder is less than the number in the generating polynomial. To illustrate this technique, the results of the various steps, using the same message that was used in the first example, are presented in Table 2. The final nonzero result 0110 has its MSB on the left so that it corresponds to $0(x^4) + 1(x^3) + 1(x^2) + 0(x) + 0(1) = x^3 + x^2$. The final nonzero result 01100 (x^4 through x^0) in both tables is the same using either technique. This must be so, since the shift

TABLE 2

Longhand Generation of Final Remainder Using Eight Data Bits and CRC Polynomial $P_5(x)$

"Initial" remainder	11111
First character (first five data bits) plus padding (five 0s)	0011100000
	1100000000
$P_5(x) = 100101$	100101
	101010000
	100101
	1111000
	100101
	110010
	100101
Remainder after first character division	10111 (number of bits < divisor)
Second character (last three data bits) plus padding (five 0s)	01100000
	11011000
$P_5(x) = 100101$	100101
	1001100
	100101
Remainder R after second character division	00110 (number of bits < divisor)
Check character (five bits) plus padding (five 0s)	1100100000
$R + \bar{R}$ plus padding = reference polynomial	1111100000
$P_5(x) = 100101$	100101
	110110000
	100101
	10011000
	100101
Final nonzero result	01100 (number of bits < divisor)

WORTH FLIPPING OVER:



Pertec's 40-track double density Microfloppy®—compatible with Shugart's 35-track; comparable to no other μC disk drive.

Bottoms up. Here's where a second source leaps to the head of the class. Pertec's FD200 Microfloppy® offers big system performance—with no redesign—to OEMs using 5¼" diskettes. (For 8" applications, our FD514 is interface compatible with Shugart SA800.)

FD200: Fully compatible with Shugart SA400. Same dimensions, same mounting holes, same interface signals, same power connector. But unplug their 35-track drive, plug in FD200...and suddenly you're into the only double density, 40-track recording available to date for μC applications.

Plus flip-side storage. Up to 500,000 bytes per diskette, recording double density both sides. Up to 250 KB on one side—flip it over and store another 250 KB.

Compatible to IBM standard. Through our inventive electronics, it's the same proven read/write head that's built a solid track record for Pertec, in thousands of minicomputer flexible disk drives worldwide.

Easier to use and maintain. Options are switch selectable; power supplies are internationally-standard 5- and 12-volt DC.

And Pertec cuts the number of PCBs in half. Not two, but only one quick-disconnect board—to simplify field maintenance, boost system reliability, reduce spares stocking.

The cost-efficiencies of our FD200 Microfloppy are so indisputable, we expect fast turnovers with microcomputer OEMs. Jump in.

Please send specs for: ☐ FD200 Microfloppy.®
☐ FD514 8" Drive.
Send pricing for: _____(quantities) FD200's.
_____(quantities) FD514's.
☐ Contact us immediately for consultation.
Tel ( )_____ext_____
Name_____
Title_____
Clip coupon to company letterhead and return to Pertec, 9600 Irondale Avenue, Chatsworth, CA 91311.
Or call the Pertec regional sales office nearest you: Los Angeles (213) 996-1333. Ann Arbor, Michigan (313) 668-7980. Hudson, New Hampshire (603) 883-2100. England (Reading) 582115.

PCC PERTEC
a division of Pertec Computer Corporation

CIRCLE 58 ON INQUIRY CARD

TABLE 3

Representative CRC Polynomials and Final Results When Used With CRC Character Generation Schemes (Tables 1 and 2)

Generating Polynomial	Unique Nonzero Final Result
A) $x^{11} + x^{10} + x^6 + x^5 + x^4 + x^2 + 1$	$x^{10} + x^9 + x^8 + x^7 + x^6 + x^5 + x^4 + x^3 + x^2 + x + 1$ 11111111111
B) $x^{16} + x^{12} + x^5 + 1$	$x^{12} + x^{11} + x^{10} + x^8 + x^3 + x^2 + x + 1$ 0001110100001111
C) $x^{22} + x^{13} + x^2 + 1$	$x^{17} + x^{16} + x^{15} + x^{14} + x^{13} + x^6 + x^5 + x^4 + x^3 + x^2 + 1$ 00001111100000001111101

Note: Desirable error detecting capabilities of A and C may be found in Ref 1. B represents generating polynomial used in SDLC, HDLC, and ADCCP bit-oriented protocols.

register and longhand approaches correspond to the same division process.

It is clear from the second example that the result of Exclusive-ORing the remainder (R) at the end of the data in the absence of errors (see Eq 1) with the CRC bits is then $R + \bar{R}$, which represents a character of all 1s. Padding with zeroes and continued division is then equivalent to dividing a reference polynomial (the result of concatenating a character of all 1s with a character of all 0s) by the generating polynomial. This is seen explicitly in Table 2 in the step following the receipt of the remainder character, where $R + \bar{R}$ plus padding equals 1111100000. Since the result will always be of this form if no errors have occurred in transmission (but will have different lengths depending on the length of $P_n(x)$), the final contents of the shift register or the final result of completing the division will be a unique bit string. The specific bit string for a given $P_n(x)$ is then easily determined by dividing the reference polynomial by $P_n(x)$. The results of this operation for three different choices of $P_n(x)$ are presented in Table 3.



Fig 2 Diagram, comparing final result of CRC for several different polynomials containing at least four and at most eight bits, uses polynomial $P_5(x) = x^5 + x^2 + 1$. R2 contains bit pattern to be matched; R1 contains mask bits for unused bits in R2

This longhand approach represents a possible method for implementing CRC checking in software, especially when an integral number of characters is always transmitted. Note that in this case, the result of Exclusive-ORing R with $\bar{R}$ is sufficient to detect error conditions, and the division does not have to be continued. That is, in the absence of errors, $R + \bar{R}$ is equal to a character of all 1s. Thus, when a message delimiting (flag) character is received, $R + \bar{R}$ can be formed and compared with the all 1s state. Then, the problem with erroneous trailing 0s is eliminated without the need to continue the division process beyond this point. This can represent a significant computational savings. It is clear, however, that a mechanism

CIRCLE 59 ON INQUIRY CARD ⟶

We've lowered the cost of environmentally-qualified terminals.

Interstate Electronics has developed a new family of ruggedized plasma display terminals that cost significantly less than any comparable military terminals.

Because Interstate Electronics—and nobody else—gives you "next generation" plasma display electronics. Through innovative circuit integration, we've reduced terminal size, weight and electrical complexity. As well as price.

The PD Series can be specified for a variety of military environments—sheltered, shipboard and airborne.

Each model offers:

- *4,000 character display capability*
- *Complete graphics capability*
- *Extremely fast transfer rates (up to 50K baud)*
- *Inherent memory and selective write/erase to free computer time*
- *Extremely long panel life*

We also offer a complete selection of options, including:

- *Touch panel input*
- *Special function keys*
- *Programmable character generator*
- *Multiple input/output capability*
- *Software support packages*

Interstate can help you select the optimum terminal configuration for your requirements. Give us an opportunity to discuss your operational environment and performance needs.

Write or call Don Poulos, Products Manager, Computer Products, Interstate Electronics Corporation, 707 E. Vermont Ave., Anaheim, CA 92802. (714) 635-7210 or (714) 772-2811.

INTERSTATE ELECTRONICS CORPORATION

SUBSIDIARY OF **ATO**

Copyright 1977
Interstate Electronics Corporation

Some of these components will probably never The others will just come close.

The SR, XL, XK and AV are solid state position sensors featuring almost infinite life. All offer zero speed operation with some up to 100 Khz. ES current sensor utilizes Hall-effect IC and protects against damage from short circuits or overcurrent conditions.





Snap-action V3, SM and SX switches offer wide variety of actuators, electrical capacity and termination.

Mercury switches offer hermetic sealing, a variety of electrical capacity and broad temperature ranges at a low cost.



AML manual devices for low installed cost, electrical flexibility and attractive panel appearance. Series 8 miniature manual switches provide small size and wide variety of operators. DM offers inexpensive snap-in panel mount design.

Solid state keyboards provide high reliability no mechanical keyboard can offer. Panel sealed versions also available.



wear out.

The solid state keyboard, AML lighted pushbuttons and sensors you see here will probably never wear out. Because they're all solid state.

Each is based on a Hall-effect integrated circuit. A circuit that's been tested through billions of operations without failing. And proven by performance in thousands of applications.

The precision electromechanical components you see here come close. Simply because of the careful way they're designed and put together.

Like the long-life versions of our snap-action V3, SM and SX precision switches. Available in a wide variety of sizes, electrical ratings, terminals, actuators, contact forms and operating characteristics—some tested to a mechanical life of over 10,000,000 operations.

MICRO SWITCH will provide you with field engineers for application assistance and a network of authorized distributors for local availability. Write us for details or call 815/235-6600.

And find out how you can get a component that goes on forever. Or at least comes very, very close.

MICRO SWITCH

FREEPORT, ILLINOIS 61032

A DIVISION OF HONEYWELL

MICRO SWITCH products are available worldwide through Honeywell International.

that looks ahead for the CRC character must be employed in this case.

Hardware Considerations

In the design of ICs using the shift register approach, it follows that for bit-oriented protocols the ability to compare the final remainder with the contents of an additional register should also be included. Since the length of the various generating polynomials may be different, the use of another register (R2) to mask out the unwanted bits is implied. A possible approach is illustrated in Fig 2. Here, the contents of R1 are set up so that a logic 0 is loaded in those positions that correspond to bits in the CRC remainder shift register that can be ignored. For example, if a given line adapter were to be used with 16- and 24-degree polynomials, the equivalents of two 24-bit and one 16-bit shift registers would be employed. The contents of R1 would be all 1s for the 24-bit case, and would consist of eight 0s and eight 1s in the 16-bit case. The contents of R2 would be set in accordance with the specific polynomial as described above.

Conclusions

The discussion has presented a well-known mechanism used to eliminate problems relating to erroneous leading and trailing 0s in bit-oriented protocols; it consists of presetting the contents of a CRC shift register to an all 1s state and transmitting the inverted remainder as the CRC bits. Also described are hardware and software techniques to handle CRC computations, and features of ICs to be used in line controllers. Through elucidation of the basis of the method, a simple manuever is formulated for users/designers to determine the specific form of the final remainder at the receiver for any polynomial, without having to proceed through the various shift register states one bit at a time.

References

1. H. C. McKee, "Improved CRC Technique Detects Erroneous Leading and Trailing 0's in Transmitted Data Blocks," *Computer Design*, Oct 1975, pp 102-106
2. W. W. Peterson and D. T. Brown, "Cyclic Codes in Error Detection," *Proceedings of the IRE*, Jan 1961, pp 228-235

SOLVED!

YOUR BUS-RELATED DATA RECORDING PROBLEMS



With Dylon's new GPIB (IEEE-488) tape recorders, you can now transfer data directly from the Bus to ½"magnetic tape. With NO interfacing. Just plug it in.

Once on tape, data may be transferred to your computer for analysis. Or it can be read back through the Bus to any GPIB—compatible minicomputer or calculator.

There's more. Much more.

To find out how Dylon GPIB tape recorders can solve Bus-related recording problems in your data collection system, please call or write our director of marketing.

Dylon

The Dylon Corporation
3670 Ruffin Road
San Diego, California 92123
(714) 292-5584

CIRCLE 60 ON INQUIRY CARD



Digital announces a PDP-8 with an enormous memory.

Something big has just happened to the world's most famous small computer. In fact, something enormous.

Digital has just put 128K of memory into the PDP-8.

This act is brought to you by a powerful new memory management option called KT8-A. And by two new MOS memory modules that fit large amounts of memory into small amounts of space. Simply by adding these 16K or 32K modules in whatever combination you choose, you now expand your PDP-8/A into something bigger. What's even better, you can mix MOS and core. And that means you can protect your program in non-volatile core while you expand your data base in MOS.

And thanks to the KT8-A all this memory is under new management. Not only does the KT8-A let you address up to 128K words of memory, but it also offers you memory relocation and memory protection, while asking little in operating system overhead so you get faster system performance.

What's the cost of these enormous advancements? That's the next attraction.

The new PDP-8A MOS memory models are available at prices that are as crowd-pleasing as their performance. For a 16K 8A205 you'll pay as little as $3900 (quan. 1). 8A425 with 64K is as low as $11,000. And the top of the line 8A625 with 128K is yours for as little as $18,050.

They're the new big-memory Eights from Digital. Step right up.

Large memories aren't our only new trick.

New hardware and software improvements are also in the PDP-8 spotlight.

The VK8-A is a new low cost PDP-8A option that provides high quality video output plus keyboard and printer interfaces. Video character generation uses a super-sharp 9x9 dot matrix for high resolution on single or multiple CRT monitors up to one thousand feet away.

Also new for PDP-8 users is MACREL/LINKER—a sophisticated assembler with MACRO facilities that lets you implement, expand and update your system faster while reducing software development time.

And last but not least there's DECNET 8—a series of software protocols that let you form your own PDP-8 network.

The PDP-8. Bigger. Smaller. And better than ever.

A short while ago, we made big news with DECstation 78. A low-end system that set new highs for ease of use and simplicity.

Now we're expanding the PDP-8 family up, as well as down, and that means new opportunities for OEMs and end-users alike. Look into what's happening with PDP-8s. Call your nearest Digital sales office today.

Or send the coupon to PDP-8 Marketing Communications, Digital Equipment Corporation, 129 Parker Street, PK3-1/M34, Maynard, Massachusetts 01754. European headquarters: 12, av. des Morgines, 1213 Petit-Lancy/Geneva. In Canada: Digital Equipment of Canada, Ltd.

digital

PDP-8 Marketing Communications
Digital Equipment Corporation, 129 Parker Street, PK3-1/M34,
Maynard, MA 01754
Please send additional information about the PDP-8 family.

Name _____ Title _____

Company _____

Address _____

City _____ State _____ Zip _____

Phone _____ OEM _____ End-User _____

Application _____

CD117

Microcomputer Interfacing: Preparing Your Programs

Jonathan A. Titus
Christopher Titus
Tychon, Inc

David G. Larsen
Peter R. Rony
Virginia Polytechnic Institute & State University

One of the difficulties facing many microcomputer users is the preparation of software for their particular applications. Software examples contained in past columns were short enough to assemble by hand, ie, each mnemonic was translated into its octal, hexadecimal, or binary equivalent. Usually listed in sequential order on the rough draft, addresses for jumps, calls, and input/output devices can easily be added or changed since the computer programs are short. Unfortunately not all software preparation is this easy. Many application programs contain thousands of steps. This month's column initiates a discussion of microcomputer program development aids which are available.

The clear, concise statement of the problem and how it is to be solved is one of the largest problems in software development. All of the desired results, inputs, outputs, and complete program flow—including all decision-making steps—must be considered before programming is started. While outline or block diagram form is acceptable, a flowchart often proves to be much easier to follow (see Figure).

The next step is to make a decision: Is the program short enough to be easily translated by hand? In many cases, particularly where the programs are simple, hand assembly makes sense. In other cases software development aids called editors and assemblers are faster and more efficient (see Glossary of Terms).

To understand how editors and assemblers work, consider the analogous example of writing a manuscript. The first step is to outline the subject to ensure that it is well covered in the allotted space. The editing process requires the copy to be corrected and typed, perhaps several times; illustrations and examples are formulated and drawn separately. When the article is composed or assembled, direct references to tables and figures (eg, Table 5) are easier to follow.

Computer software is developed in much the same way. An editor program is used on either a microcomputer or timesharing system to edit individual program steps, which includes correcting, changing, inserting, and deleting steps. Since most editors can be used to perform many functions, the editor program generally is unaware that a computer program is being written. When an editor is used to prepare a program in mnemonic form, symbolic addresses are often assigned to software tasks within the program. In this way the actual value of the addresses for subprograms or subroutines is not needed; for example, the program may refer to the letters LOOP as the starting address of a time delay loop. This use of symbolic addresses for program steps allows a program to be changed without regard to the actual numeric values of addresses.

The assembler program must be such that it accepts information from the editor and generates an output in computer-compatible form. The assembler, which functions by performing one step at a time, contains a table

Glossary of Terms for Software Preparation

Editor	A program allowing such edit functions as addition of a line or character, insertion, or deletion to permit altering of a program. Input data can be anything from programs or reports to raw instrument data.
Assembler	The program that converts assembly language code into machine code, accepting mnemonics and symbolic addresses instead of actual binary values for addresses, instructions, and data.
Monitor	Controlling the operation of the various programs available, the monitor can access the editor, assembler, or other programs.
Debugger	A program which allows the user to observe the program flow and results of the program's operation in a step-by-step mode. It may be used to change data or instructions, alter registers, etc.
Breakpoint	This special instruction may be inserted in a program to break off the normal program control and return control to a debug-type program. When a breakpoint is executed, the debug program indicates what the computer was doing at that point.
Cross Assembler	A type of assembler program which generates binary code of a program for a computer other than the model it is being used with; eg, an 8080 cross assembler might operate on a PDP-8 minicomputer.

Software Listing of Typical Assembler Output

```
                        *003 000
003 000 061   START,    LXISP     /Symbolic address of START
003 001 377             377
003 002 003             003
003 003 333   LOOP,     IN        /Input data from port 5
003 004 005             005
003 005 376             CPI       /Compare it to 026
003 006 026             026
003 007 312             JZ        /If it matches, go to DETECT
003 010 015             DETECT
003 011 003             0
003 012 303             JMP       /If it doesn't match, go to
003 013 003             LOOP      /LOOP and check again
003 014 003             0
003 015 171   DETECT,   MOVAC
003 016 323             OUT
003 017 007             007
003 020 166             HLT
```



Typical flowchart with input, output, and decision-making steps

of mnemonics and their equivalent values. For example, an 8080 assembler would translate an MVIA instruction into 076 octal. The assembler also assigns real, 16-bit addresses to symbolic addresses, such as LOOP. The user must be sure to have a program step for each symbolic address and must assign an address if a symbol is used. The same "name" cannot be assigned to more than one address. Most assemblers recognize a redefined or undefined symbol and produce an error message indicating what needs to be corrected.

Final assembler output is in punched paper tape, cassette, or disc form ready to run on the system. Most assemblers also produce a listing of the program showing the address of each step, the data in each successive location, a symbolic address name, and the mnemonic plus any comments. A typical assembler output is shown in the Software Listing.

After a program is assembled, it probably will have to be debugged in order for it to operate properly. Program checkout and debugging can be a painful process without additional software tools. Computer control panels are often useful, but reading binary codes can become tedious and many computers do not have external controls and readouts. As an alternative, debugging programs are available for most microcomputers to allow the user to change instructions, list blocks of data or instructions, and single-step through a program.

Many debug programs feature the ability to establish a breakpoint in the software being tested. When the computer reaches a breakpoint, the instruction at that address is executed and an output device such as a teletypewriter lists the contents of important, internal CPU registers. Breakpoints are very useful since they indicate not only that the computer reached a certain point in the software, but also what the computer was doing when it got there. If a breakpoint is set in the normal program flow and is not reached, there is obviously something wrong with the program. In this case, the breakpoint would be moved closer and closer to the start of the program until the error is found. The error then may be corrected by using the debug program to change an instruction, data, etc.

Once the program is operating correctly, the debug program should be able to retain it on paper tape, cassette, or other medium, and also should be able to read such programs back into memory. In any case, when errors are found the software should probably be re-edited and re-assembled to produce a complete, error-free, documented listing.

Since most programs contain errors, it is valuable to have a permanent debug program with the computer, preferably stored in read-only memory (ROM) or programmable ROM (p/ROM). This is advisable since "run away" programs being tested might alter the debug software, necessitating its reloading. Many debug or monitor programs are available; Intel Corp's Insite software library lists at least four. Editor/assembler programs also may be resident in p/ROM. The low cost of both read/write memory and p/ROM chips suggests that many users will keep standard system programs such as editors, assemblers, and debug resident in their system. The alternative is a paper tape, cassette, or disc-based software package which must be read into memory before each use.

Cross assemblers also are available to generate an assembled program, but for some other computer. For example, a PDP-11 might be able to cross assemble 8080 microcomputer programs. Cross assemblers can be powerful since some also incorporate simulation programs to test the program.

For testing programs we use DBUG, an 8080 interactive debugger written by C. A. Titus (E&L Instruments, Inc, Derby, Conn, 1977); the assembler output shown in the program example is that produced by the Tychon editor/assembler (TEA). Both are resident in our 8080 system on p/ROM chips.

This article is based, with permission, on a column appearing in *American Laboratory* magazine.

Expansion of Microcomputer Family With System Modules and Software Is Aimed At OEM Applications

A range of high performance system modules and additional software have been specifically designed by Plessey Microsystems, Microcomputer Products, 1641 Kaiser Ave, Irvine, CA 92714 to enable fast realization of high performance OEM computing systems. Designated Miproc 16-AS (application system), the family consists of the standard 350-ns instruction time Miproc-16 CPU card supported by processor, memory, and interface modules, which are plugged into a 13-card bay with integral power supply.

The card bay modules can be enclosed in a 19″ (48-cm) rack-mounting chassis unit. It accommodates one or two card bay modules and has fan units and an operator's panel. The chassis can hold two card bay modules organized as independent systems, or the second card bay can be used as an extension of the first. A 3-bay version is available for multiprocessor configurations.



Enhancing its Miproc-16 microcomputer, Plessey has added processor, memory, and interface modules for OEM systems applications. Modules are plugged into 13-slot card bay with power supply; chassis unit can hold up to three card bay modules

Processor modules include the CPU, an optional index register/interrupt module, and optional hardware multiply peripheral for higher speed applications. Also available is a combined power monitor and real-time clock module which monitors both ac and dc power rails.

A high speed 2k bipolar RAM, high speed 8k bipolar p/ROM, and applications memory providing 4k p/ROM and 256-word RAM comprise the memory cards. Also included is a 2k CMOS RAM with integral battery to provide nonvolatile alterable peripheral storage. Interface cards include programmable serial line interface, 2-channel 16-bit parallel bidirectional I/O card, and 6-channel parallel input, as well as output, cards.

The PL-Miproc language, which resembles ALGOL in structure, is suited to structured programming; it reduces the time required to develop application software. The cross-compiler runs on DEC's PDP-11 computers under the RT-11 operating system. Compiled code is in the proper format to be loaded into the Miproc-16 prototyping system.

As an aid to program development at the testing and debugging stage, the Monitor module consists of a set of three cards that are housed either in the 16-AS chassis or the Miproc-PK real-time prototyping kit. It provides a facility to interrogate, inspect, and update program and data memories in the system via a teletypewriter or compatible device; programs are run in near real-time conditions. Using the Miproc processor to help diagnose errors, the monitor features multiple trace, multiple trap, and backward trace.

Circle 170 on Inquiry Card

Increased Functions of μComputer Family Support Added Applications

The MN1400 series of three microcomputers (models MN1400, 1402, and 1498) and an evaluator chip (1499) which can perform tests on the series offer more onchip functions to fill the application gap between 4- and 8-bit units. Built by Panasonic Electronic Components, One Panasonic Way, Secaucus, NJ 07094 with n-channel E/D MOS process, the chips incorporate functions previously included in auxiliary circuitry—an 8-bit presettable counter/timer, clock generator, 1024 x 8-bit instruction ROM (1400 model), 64 x 4-bit RAM with four directly addressable words, ALU, two 4-bit parallel input ports, 4-bit parallel output port, and 8-bit PLA decoded output port.

Other user-oriented features are two sense input lines, counter select input line, power-on reset input line, and 12 discrete output lines. With single power supply operation (4.5 to 6.0 Vdc), the units have a 10-ms instruction cycle time, 75 instructions, and subroutine nesting to two levels. Models are available in 28-, 40-, or 64-pin DIPS.

Circle 171 on Inquiry Card

Development System Stores 300k Bytes on Floppy Disc

A compact program development system, the Z80-PDS provides complete support for developing and debugging Z80 microcomputer programs. The standard system, expandable via options, includes a floppy disc drive with up to 300k bytes of online data storage, internal memory of 3k bytes of p/ROM and 16k bytes of RAM, and serial I/O with RS-232 or strappable current loop interface.

Zilog, Inc, 10460 Bubb Rd, Cupertino, CA 95014 also supplies software which includes disc resident operating system, editor, assembler, debugger, and file handling utilities. Consisting of a card enclosure and disc unit, the system sells for $2850 in single quantities.

Circle 172 on Inquiry Card

Digital Output Boards Are Compatible With 6800 Microcomputers

Memory mapped, plug-compatible 16- or 32-channel isolated digital output systems, MP701 and MP702, respectively, are available for Motorola Micromodule and EXORciser® microcomputer systems. Introduced by Burr-Brown, International Airport Industrial Pk, Tucson, AZ 85734, the systems contain all necessary control and timing circuitry, and include

NEC JUST MADE INTEL'S 8080A TWICE THE MICROPROCESSOR IT USED TO BE.

Introducing the μPD8080AF. From NEC Microcomputers.

Now you can get a microprocessor that's absolutely identical to Intel's 8080A.

And we can prove it.

In three separate tests using standard Intel programs, conducted by three independent laboratories, the μPD8080AF was demonstrated to be, both parametrically and functionally, exactly the same as the 8080A. (The certified results of the tests are available upon request).

Which means that now there's a microprocessor that's pin for pin and program compatible to the Intel 8080A. And available in plastic or ceramic.

Of course, we continue to offer our original μPD8080A—a microprocessor with enhanced arithmetic capability and logical flags.

With either an μPD8080AF or μPD8080A comes our complete line of standard peripheral chips. Plus state-of-the-art support chips like the 8K Electrically Erasable PROM (μPD458), a Universal Synchronous Receiver/Transmitter Data Communications Controller (μPD379), a 450ns 32K ROM (μPD2332) and a Floppy Disc Controller (μPD372) that can control up to four IBM 3740-compatible drives, and a complete line of the most reliable memories you can buy.

All backed up by applications support available nationwide.

The μPD8080AF from us. And the 8080A from them.

Even with a program, you won't be able to tell them apart.

NEC Microcomputers, Inc., Five Militia Drive, Lexington, MA 02173. (617) 862-6410.

NEC microcomputers, inc.



REPS: East—C&D Sales 301 296-4306, Contact Sales 617-273-1520, Harry Nash Assoc. 215-657-2213, Rome 516-249-0011, Tech-Mark 607-748-7473, 716-223-1252, 315-652-6229, Trionic Assoc. 516-466-2300; South—Perrott Assoc. 305-792-2211, 813-585-3327, 305-275-1132, 20th Century Mktg. 205-772-9237, Wolffs Sales Serv. Co. 919-781-0164; Midwest—Electronic Innovators 612-884-7471, W. Pat Fralia Co. 817-640-9101, 817-649-8981, 713-772-1572, Imtech 216-826-3400, 513-278-6507, K-MAR Eng. & Sales 816-763-5385, R.C. Nordstrom & Co. 313-559-7373, 616-429-8560, Technology Sales 312-438-3300; West—Cerco 714-560-9143, D/Z Assoc. 303-534-3649, Electronic Component Mktg. 714-879-9460, Summit Sales 602-994-4587, Trident Assoc. 408-734-5900, Tri Tronix 206-232-4993, 505-265-8409; Canada—R.F.Q. Ltd. 416-626-1445, 514-626-8324.

DISTRIBUTORS: ASI Electronics (Baltimore), Bell Ind. (Bellevue WA), Century Electronics (Albuquerque, Salt Lake City, Wheatridge CO), Diplomat (Chicopee Falls MA, Clearwater FL, Elk Grove Village IL, Farmington MI, Minneapolis, Mt. Laurel NJ, Salt Lake City, St. Louis, Sunnyvale, Totowa NJ, Woodbury NY), Future Electronics (Montreal, Ottawa, Rexdale Canada), Harvey Electronics (Fairfield NJ, Lexington MA, Norwalk CT, Woodbury NY), Intermark Electronics (San Diego, Santa Ana, Sunnyvale), G.S. Marshall (Sunnyvale), Mirco Electronics (Phoenix), Resco (Raleigh), R-M Electronic (Kentwood MI, Madison Hgts MI), Semicomp (Costa Mesa CA), Semiconductor Specialists (Burlington MA, Chicago, Dallas, Dayton, Farmington MI, Hazelwood MO, Indianapolis, Kansas City, Milwaukee, Minneapolis, Pittsburgh, Malton Canada), Sterling Electronics (Albuquerque, Dallas, Houston, New Orleans, Phoenix, San Diego, Seattle, Sun Valley CA, Watertown MA), Summit Distributors (Buffalo), Summit Electric (Rochester), Technico (Columbia MD, Roanoke VA), Western Microtechnology Sales (Sunnyvale), Zeus Components (Elmsford NY).



Complete 4k-bit ROM computer on one PC card, RCA Solid State Div's Cosmac video interface processor is based on CDP1802 microprocessor. Expandable hobby kit is useful for video games, graphics, and microprocessor control functions



For use with Motorola 6800 microcomputer systems, Burr-Brown's digital output microperipherals (either 16 or 32 channels) feature outputs isolated from computer bus up to 600 Vdc, and from channel to channel up to 300 Vdc. User-selectable address block occupied by each board can be placed anywhere in memory

contact-closure outputs rated at 28 V and 0.5 A (resistive load).

Mechanically and electrically compatible with Motorola systems, the units operate from the microcomputer's 5-Vdc supply. For ease of programming, the units are treated as memory by the CPU. Eight output channels occupy one memory location.

Each output channel is implemented with a protected reed relay, used to provide low "on-impedance," and high output current and isolation. Outputs are capable of switching inductive loads. Transient suppressors are used across each output switch to protect open contacts from voltage surges.

Circle 173 on Inquiry Card

Video Interface Processor Combines Low Cost With Expandability

With the Cosmac VIP video interface processor kit, a hobbyist can assemble a microcomputer with which to create and play video games, generate graphics, and develop microprocessor control functions. Priced at $275, the kit offers an operating system in 4k bits of ROM. Components include the CDP1802 microprocessor (see *Computer Design*, Apr 1976, pp 132, 134), a 2048-byte RAM which uses 4k-bit static RAMs, single-chip graphic video display interface, built-in hexadecimal keyboard, 100-byte/s audio tape cassette interface, and wall plug regulated power supply all on a single 8.5 x 11" (21.6 x 28-cm) PC card.

Output directly interfaces with a monochrome CRT display or, when used with an FCC-approved modulator, a TV receiver. The 512-byte ROM operating system simplifies such tasks as loading programs into RAM via the keyboard, recording RAM contents on cassette tapes, examining memory and registers, and displaying memory bytes in hexadecimal format on a CRT.

Chip-8 interpretive programming language has 31 instructions in a 2-byte format; it is capable of providing 16 1-byte variables and permitting subroutine nesting. Programs can be stored on cassette tapes.

RCA Solid State Div, Box 3200, Somerville, NJ 08876 has designed the processor for future expandability, both on the PC card and through connectors. RAM capacity can be doubled on the card to 4096 bytes by adding four 4k-bit devices. A 44-pin connector socket accepts added devices for up to 32k bytes of memory, as well as other circuitry. Parallel I/O expansion to 19 lines is possible.

Circle 174 on Inquiry Card

Development System Aids Design of 16-Bit Microprocessor Systems

Fully assembled on a PC board, the PACE low cost development system (LCDS) allows engineers to develop, test, and debug PACE hardware and software designs. To simplify program checkout, the unit operates in single-step or continuous mode with breakpoints. It also permits memory and register contents to be viewed, printed, and modified.

Contained on the card are a 16-bit PACE microprocessor, 1k words of RAM, sockets for 1k words of P/ROM, 20-key dual-function keyboard, 6-digit LED display, system timing element, I/O buffers, and bidirectional transceiver elements. A 20-mA current loop or RS-232 port is available.

Satisfy Your 8080 Microcomputer Design, Test and Service Needs

MUPRO 80 The complete solution

MUPRO FEATURES	YOUR BENEFITS
Real-Time Execution from emulator or users' system memory	More thorough and flexible system test capability
Multi-User/Multi-Task Disk Operating System (MUTE)	More efficient use of software personnel permits simultaneous use by up to four programmers
Block Structured Assembly Language (BSAL) and user oriented software packages	Saves software development and maintenance time while retaining the size, speed and flexibility of assembly language programs
Transparent Control/Display Console	Provides total use of microprocessor. No memory, I/O or interrupt restrictions
Compact and ruggedized system packaging	Single system provides total solution to development, test and field service needs

MANUFACTURERS OF INNOVATIVE OEM AND END USER MICROCOMPUTER SYSTEMS

MUPRO
424 Oakmead Parkway
Sunnyvale, California 94086
(408) 737-0500
TWX 910-339-9251

Circle 62 for demo and technical data

Circle 153 for technical data



Everything you need to

NORTH AMERICAN SALES OFFICES: Irvine, CA (714) 540-9945/Los Angeles, CA (213) 473-4581/Mountain View, CA (415) 965-1400/Schiller Park, IL (312) 671-4554/ Indianapolis, IN (317) 842-3130/Wheaton, MD (301) 949-1664/Waltham, MA (617) 890-2654/Minneapolis, MN (612) 881-0190/South Plainfield, NJ (201) 757-2211/Albuquerque, NM (505) 294-5790/Dallas, TX (214) 387-0229/Olympia, WA (206) 866-2201/Toronto, Canada (416) 661-3711/EUROPEAN SALES OFFICES: Hasselt (Antwerp) (011) 22.77.02/

know about DEC peripherals:

Plessey offers a complete line of DEC compatible products. Reliability, quick delivery and substantial cost savings are some of the reasons to make Plessey your supplier. For complete price and delivery information, please contact the nearest listed sales office.

Plessey Microsystems

Copenhagen (01) 12.48.03/Helsinki (080) 542.077/Paris (01) 727-4349/Munich (089) 351-6021/Neuss (Düsseldorf) (02101) 44.091/W. Berlin (030) 24.72.12/Milan (02) 688-2324/Turin (011) 61.63.33/Zeist (Utrecht) (03404) 21.344/Oslo (02) 15.00.90/Madrid (01) 252-37.22/Stockholm (08) 23.55.40/Geneva (022) 82.55.30/Zurich (01) 50.36.55/Towcester (Northants) (0327) 50.312/Tolworth (01) 330.4100. SERVICE CENTERS UNDERLINED

CIRCLE 63 ON INQUIRY CARD



Users are able to develop, test, and debug designs at low cost with National Semiconductor's PACE development system. Code for building application routines is entered through keyboards or external terminal. Firmware, resident in onboard p/ROMs, provides system monitoring capabilities and controls subroutines for I/O devices

National Semiconductor Corp's Microcomputer Group, 2900 Semiconductor Dr, Santa Clara, CA 95051 has designed the system so that its microprocessor can be isolated from the system bus, allowing an external PACE to use the LCDS memory and peripherals. Three sockets allow for added memory or extension of the interface bus. Unit costs $585. An IPC-16C/011 card supplies 1k x 16 bits of RAM, and the /012B card has sockets for up to 2k x 16 bits of ROM or p/ROM.

The 80-character, 24-line video output device features a character set with upper/lower case characters, punctuation, and underline. Characters can blink at a user-selectable rate, and can be made to appear brighter or in reverse field. Custom character sets are available.

Forms overlays, charts, graphs, or order entry forms can be generated on the screen. Continuous gray scale elements are displayed in any of nine levels in any of 1920 positions on the screen.

The 2-board, S-100 based system occupies 2k of RAM address space and two I/O ports. Timed screen updates occur only during retrace when the screen is totally blanked.

Software support includes machine language code with fully commented source listings, and a BASIC software package. A link program is provided in BASIC. Assembly language drivers allow the system to be customized. Kit price is $285.

Circle 176 on Inquiry Card

Upgraded Single Card 8080A-Based System Doubles Memory Capacity

The PLS-888 programmed logic system offers 1k of RAM, and sockets for an added 1k of RAM and 8k of TMS-2716 p/ROM. The 4.5 x 6.5" (11.43 x 16.51-cm) card includes an 8080A microprocessor, crystal clock, built-in power-on reset, 16 lines of TTL input, and 24 lines of TTL output. Pro-Log Corp, 2411 Garden Rd, Monterey, CA 93940 has designed the card to be plug-compatible with its PLS-881 4k ROM card.

Circle 175 on Inquiry Card

Disc and Video Display Systems Are Compatible With S-100 Bus Devices

The MSDD-100 disc and MSDV-100 video display systems are intended for hobby and small business applications using the S-100 bus. A Shugart SA-400 minifloppy™ drive and LSI controller are utilized by the low power, single card floppy disc system. Up to three drives, supported by the synchronous controller, provide all disc timing functions so that no software timing loops are required. Three modes of programmed I/O (no DMA) are a simple command I/O, standard interrupt, and switch-selectable facility to vector the processor to any Restart location upon generation of an interrupt.

The drive has 89,600-byte maximum data capacity and 35 tracks. Average access time is 600 ms (random R/W). Power requirements are 8 V, 200 mA max; 15 V, 20 mA max; and −15 V, 10 mA max.

Software provided by Micro Systems Development, Inc, 2765 S Colorado Blvd, Denver, CO 80222 includes two diskettes—for user programs and files, and for an array of system programs. An 8080 monitor permits formatting of diskettes and diagnostic checks. A bootstrap loader, memory-to-disc routines, and disc I/O routines are provided. Mits BASIC software can be run with the system via a link; a BASIC program is also included. Price is $499.

High Speed Verifier and Library Upgrade Logic Simulation Software

Upgrading of the Logcap logic simulation software system, which simulates an entire microcomputer system down to the gate level, has been accomplished with the addition of a high speed fault verifier along with a full set of user commands, and a proprietary library including the Advanced Micro Devices 2901 bipolar microprocessor. The fault verifier analyzes up to 1k faults at one time.

Logcap, jointly owned by Ungermann Associates, 832 Nash Rd, Los Altos, CA 94022 and RRC International, Inc, Troy, NY 12181, can verify stuck-at-one and stuck-at-zero faults on inputs and outputs to any node. Addition of the Am 2901 to the library helps define that logic element and assures correct representation of the circuit.

Circle 177 on Inquiry Card

The complete $655 line printer.

It's ready to plug in, has an 80-column format, a remarkable MTBF and is 14 times faster than a teletype!

Breaking the hardcopy barrier

It's finally happened! The Axiom EX-800 provides full performance hardcopy at a price compatible with today's low cost micros. This little 80-column machine zips along at 160 characters per second (14 times faster than a teletype)—at a breakthrough single quantity price of $655 for a complete printer.

When we say complete we mean it

The EX-800 is a stand-alone unit with case, power supply, 96 character ASCII generator and interface, paper roll holder, infra-red low paper detector, bell, and multi-line asynchronous input buffer. You won't find these standard features on any other printer, regardless of price!

Our only option

Our printer is so complete, that we offer only one option. A serial interface (RS 232C or current loop) good for 16 baud rates from 50 to 19,200 and thoughtfully provided with a switch for either Centronics or Tally compatibility. Might we call it a Tally-whacker? At $85.00 it certainly should be!

Built-in LSI microprocessor



The heart of the EX-800 is a printed circuit card, containing a custom LSI chip made by Intel to Axiom specifications, which controls all printer functions. Microprocessor power means flexibility. Such as the built-in self test routine and variable character size. It also means reliability. Several industry surveys have shown LSI to be many times more reliable than equivalent conventional circuitry.

Light, small, quiet, reliable, and versatile

Our EX-800 weighs in at 12 pounds, is just 9½ inches wide, 4 inches high, and 11 inches deep, and is delightfully quiet which makes it ideal for office and other low noise environments. The simple print mechanism is virtually maintenance free. In fact, tests show an incredible MTBF, many times greater than impact printers. This versatile printer is the ideal mate for micros, minis, CRTs, instruments and systems.

THIS LIFE-SIZE SAMPLE SHOWS THE 80-COLUMN PRINTOUT FROM AXIOM'S EX-800 PRINTER
There are 3 character sizes (upper and lower case) which can be MIXED.
This can have the same effect as UNDERLINING or changing COLOR.

The advantages of electrosensitive printing

The EX-800 can print 80, 40, or 20 characters across the five inch wide electrosensitive paper. Under software control, single characters or words may be printed larger for emphasis. The permanence of the hardcopy is archival, because once the aluminum coating has been removed, there is no way to put it back. It's unaffected by sunlight, moisture or heat. Although the printer doesn't provide multiple copies, excellent quality photocopies can be made from the high contrast printout. Also, the paper is inexpensive and readily available, costing about 1¢ for an 8½ x 11" equivalent.

Just unbox and plug it in

That's all you have to do to the Axiom EX-800 — apart from pay for it, and at $655 that's almost a pleasure.

Send to: AXIOM
5932 San Fernando Rd.,
Glendale, CA 91202

- ☐ Urgent. Please phone me at ext ____
- ☐ Have rep contact me
- ☐ I'd like to have a demonstration
- ☐ Send lit including sample of printout

Name _____
Company _____
Dept _____
Address _____
City _____ State _____
Zip _____ Telephone _____

AXIOM AXIOM CORPORATION
5932 San Fernando Rd., Glendale, CA 91202 • (213) 245-9244 • TWX 910-497-2283

CIRCLE 64 ON INQUIRY CARD



Grayhill ends contact contamination

complete protection during wave soldering and PC board cleaning

- terminals welded ultrasonically into switch body
- reusable protective cap seals switch plunger
- tripod stand-offs provide solvent flow area under switch

These economical pushbutton switches are ideal for 'on board' press-to-test or front panel applications. Occupying under ½" square, they provide momentary action, long life with low contact bounce and trifurcated gold plated contacts. Terminals are on .100" centers for easy prototype breadboarding and accommodation of board drilling equipment. Circuitry is SPDT (two circuit); operation from logic levels up to ¼ amp.

The new switches (Series 39-251) are available from stock in prototype quantities and 5-7 weeks for production requirements. For complete information, write Grayhill for Bulletin 248 at 561 Hillgrove Avenue, La Grange, Illinois 60525, or phone (312) 354-1040.

Grayhill INC

MICRO PROCESSOR COMPUTER DATA STACK

Fully Integrated 16-Bit µComputer System Delivers Power of LSI-11

The SS-11/15 is a cost-effective, dual or quad disc-based system packaged in a 10.5" (26.7-cm) rack or table-top mounting enclosure. Hardware includes a 15-quad slot backplane, integral switching mode power supply, an LSI-11 CPU with EIS/FIS MICROM, 20k- to 28k-word RAM, console interface, diagnostic/bootstrap p/ROM, bus terminator, console switch register, distributed refresh controller, and front panel controls/displays. Compatible with operating system software such as RT-11 and RSX-11/S, the system from Unicomp, Inc, 8950 Westpark, Suite 312, Houston, TX 77063 features an array of source languages including Multi-User BASIC, FORTRAN IV, and Macro-11.



Circle 178 on Inquiry Card

Packaged Microcomputer System Offers APL Capabilities

The APL/X3 microcomputer system consists of the DEC LSI-11™ CPU packaged in a 16-slot backplane with 28k words of MOS memory, extended instruction set, and floating point arithmetic. General Robotics Corp, 57 N Main St, Hartford, WI 53027 has fabricated the system with a 10M-byte cartridge disc (one fixed, one removable platter), APL CRT with 24 lines of 80 char, and an APL printer with 132 columns and speed of 60 char/s. Software is DEC RT-11™ and APL/RT-11™ with licenses.

Circle 179 on Inquiry Card

Call your nearest ISC sales representative.

If your state is not listed call 800/241-9888.

ALABAMA: Huntsville
W. A. Brown Inst. Inc. 205/539-4411
ARIZONA: Phoenix
Thorson Co. 602/956-5300
CALIFORNIA: Goleta
Thorson Co. 805/964-8751
CALIFORNIA: Los Angeles
Thorson Co. 213/476-1241
CALIFORNIA: Mountain View
Thorson Co. 415/964-9300
CALIFORNIA: San Diego
Thorson Co. 714/298-8385
CALIFORNIA: Tustin
Thorson Co. 714/544-5121
COLORADO: Denver
Thorson Co. 303/759-0809
FLORIDA: Ft. Lauderdale
W. A. Brown Inst. Inc. 305/776-4800
FLORIDA: Melbourne
W. A. Brown Inst. Inc. 305/723-0766
FLORIDA: Orlando
W. A. Brown Inst. Inc. 305/425-5505
FLORIDA: Valparaiso
W. A. Brown Inst. Inc. 904/678-7932
GEORGIA: Atlanta
W. A. Brown Inst. Inc. 404/939-1674
LOUISIANA: Gretna
W. A. Brown Inst. Inc. 504/366-5766
MARYLAND: Bethesda
Bartlett Assoc. 301/656-3061
MASSACHUSETTS: Framingham
Bartlett Assoc. 617/879-7530
MICHIGAN: Madison Hts.
WKM Associates 313/588-2300
NEW MEXICO: Albuquerque
Thorson Co. 505/265-5655
NEW YORK: White Plains
Bartlett Assoc. 914/949-6476
NORTH CAROLINA: Durham
W. A. Brown Inst. Inc. 919/682-2383
OHIO: Cleveland
WKM Associates 216/267-0445
OKLAHOMA: Norman
Data Marketing Assoc. 405/364-8320
PENNSYLVANIA: Pittsburgh
WKM Associates 412/892-2953
PENNSYLVANIA: Wayne
Bartlett Assoc. 215/688-7325
SOUTH CAROLINA: Columbia
W. A. Brown Inst. Inc. 803/798-3297
TENNESSEE: Knoxville
McCoin Elec. Equip. 615/584-8411
TEXAS: Austin
Data Marketing Assoc. 512/451-5174
TEXAS: Dallas
Data Marketing Assoc. 214/661-0300
TEXAS: Houston
Data Marketing Assoc. 713/780-2511
TEXAS: San Antonio
Data Marketing Assoc. 512/828-0937
WASHINGTON: Bellevue
Thorson Co. 206/455-9180
AUSTRALIA: Mt. Waverly, Victoria
Anderson Digital Elec. 03-543-2077
CANADA: Montreal
Cantec Rep. 514/620-3121
CANADA: Ottawa
Cantec Rep. 613/225-0363
CANADA: Toronto
Cantec Rep. 416/624-9696
EUROPE: England
Techex, Ltd. 0202-293-115
EUROPE: France
Peritec 749-40-37
EUROPE: Switzerland
Intertest, AG 031-224481
JAPAN: Tokyo
Munzing International 586-2701

ISC
Intelligent Systems Corp.®

$995



Unretouched photograph of screen

Get the jump on your competition without outspending your competition. We're Intelligent Systems Corporation, and we've just lowered the price of our Intecolor 8001 to $995. So now you can upgrade the terminals in the systems you're marketing to color at black and white prices.

The fact is that the Intecolor 8001 has the best price-performance ratio of any intelligent data entry terminal on the market—color or black and white. And that can really add some punch to your sales story. So can color, not because it looks better, but because it communicates better than black and white.

And if you're marketing your systems by promoting the stand-alone capabilities of your terminals, we've got a list of options that'll give you just about any degree of sophistication you want. Including disk storage devices, bi-directional desk-top line printers and a brand new 2708/2716 PROM programmer.

Contact the ISC rep nearest you. We guarantee delivery of your Intecolor 8001 evaluation unit for $995 (cash-with-order) within 30 days or your money back. Or if you've seen the Intecolor 8001 in action and you're already sold on the price and performance, we'll give you the same $995 price for orders of 100 units or more. Get the jump on your competition without outspending your competition. Get the Intecolor 8001.

ISC

Intelligent Systems Corp.®

5965 Peachtree Corners East
Norcross, Georgia 30071
Telephone 404-449-5961 TWX: 810-766-1581

CIRCLE 66 ON INQUIRY CARD

TV Course Aimed At Industry Teaches 6800 Microprocessor

A TV microprocessor course consists of 30 half-hour color video cassette sessions—15 introductory and 15 laboratory sessions each cover a particular portion of the 6800 microprocessor system. Based upon the Micro-68 training computer, it was produced for industry by Electronic Product Associates, Inc, 1157 Vega St, San Diego, CA 92110 in conjunction with Colorado State University. Documentation includes a study guide, Micro-68 lab and user's manuals, 6800 programming and system design reference manual, and "Understanding Microprocessors" textbook.
Circle 180 on Inquiry Card

Cassette Interface For μProcessor Programs Operates at 2400 Baud

The Wince cassette interface enables microprocessor programs and data to be loaded and dumped from an audio cassette eight times faster than standard 300 baud. Announced by Wintek Corp, 902 N 9th St, Lafayette, IN 47904, the device interfaces directly to the Motorola 6850 ACIA. The 2.5 x 5" (6.35 x 12.7-cm) module also supports 300-baud Kansas City standard operation and contains an RS-232 interface for standard baud rates from 150 to 9600.
Circle 181 on Inquiry Card

F8 Macro Cross Assembler on Diskette Improves Software Development

An assembler for the F8 microprocessor operates on any Intel MDS-800 development system capable of supporting the ISIS-II operating system. Source programs are compatible between this assembler and those available with the F8 Formulator and from several timesharing networks.

Xener Corp, Suite 211, 6641 Backlick Rd, Springfield, VA 22150 has supplied the assembler with added capabilities of conditional assembly directives and complete macro facility with local and global label generation. Supplied on a single- or double-density diskette, the assembler offers utilization of system peripherals to print listings and enter data into ROMS. Error codes for source program errors are printed on the assembly listing.
Circle 182 on Inquiry Card

Board Brings Debugging and Real-Time Processing To 8080 Systems

Added capabilities of debugging hardware and software, providing timing functions for real-time processing, and implementing timesharing for Altair/Imsai microcomputers is available from the plug-compatible Better Bug Trap (BBT) PC board. Combining the ability to detect addresses with the generation of time intervals, the board provides software programmable functions that operate transparently to applications programs.

Central features are four hardware breakpoint address registers for inserting instructions at up to four ROM locations and a 16-bit clock counter running at $\frac{1}{256}$ the system clock rate which can be read as a memory location for timing or as a random number. Breakpoint capability enables the device to stop the processor at an address or generate an interrupt. A real-time clock, interval timer, automatic single-step function, or watchdog timer are possible. The BBT also generates and services its own interrupts.

No modification of programs for timesharing applications is necessary; a simple software routine is included with the BBT so that the system can switch from executing one program to the other rapidly and efficiently. Addressed as if it were 16 bytes in memory, the BBT is commanded from software or front panel.

Micronics, Inc, PO Box 3514, Greenville, NC 27834 includes a standard software package (IBB) with interactive terminal commands, extensive error checking, and commands to set all BBT functions and registers. It also sets and maintains a time-of-day clock. It is supplied as an 8080 assembly language source listing. Assembled and tested, the BBT costs $160 including documentation package and routine IBB.
Circle 183 on Inquiry Card

Formatting Program Offers Capability of Word Processing

Designed for 8080 microcomputers using iCOM floppy discs, the text formatting program comes in hexadecimal ASCII object format on a data diskette ready to run under iCOM's FDOS (II or III). Program input is created under the system's text editor and contains formatting commands and text. Formatted output is written back onto a diskette. Input and output file names of the program from Ortronics, 4753 Irvine Ave, North Hollywood, CA 91602 are specified in a RUNGO command to FDOS.
Circle 184 on Inquiry Card

Multiprocessing Disystem Series for Control Features Floppy Disc

Available as a complete turnkey system or as individual components from Systemathica Consulting Group Ltd, 4732 Wallingford St, Pittsburgh, PA 15213, the 8080-based multiprocessing disystem series consists of a single-board computer; system controller board; a multiplexer supporting two, four, or eight floppy disc drives; and 64k memory subsystems. The computer features 4k static RAM, 4k ROM, two TTY or RS-232 serial ports, six 8-bit parallel ports, buffered bus lines, and memory addressing up to 64k.

A communication and arbitration module, memory cross-access unit, and intelligent multidrive floppy disc controller unit comprise the controller board. Subsystems are a buffered memory decoding motherboard and 16k 8-bit or 8k 16-bit word static RAM boards. Compatible with other 8080 systems, the components are available in various standard configurations. □
Circle 185 on Inquiry Card

From only 90 seconds of transmission time, HP's new graphic plotter drew this chart in four colors, picked up its pens, and put them away.



Neat, isn't it.

Getting this kind of graphics from complex computer data has always been a long drawn-out problem. Now, arcs, circles, dashes, dots, and alphanumerics—routine shapes that normally take lengthy programs—are quickly drawn by single commands.

And, with only one transmission, any series of shapes and moves can be stored in the plotter's memory and repeatedly executed as macroinstructions.

But the neat trick is the way our plotter instantly changes colors via a programmable command or front panel control. Four long-life HP pens stay tucked away until the plotter picks one out, draws, and puts it back (with the cap on).

You have to see it to believe it. HP's remarkable new Model 7221A (RS 232C interface) uses an internal memory and 40 commands that plot efficiently to save you money in computer and transmission time. All for just $4,600, domestic USA price only.

See your Hewlett-Packard representative for complete details on how you can have economical high quality multicolor charts and diagrams of your computer-generated information with the new Model 7221A Graphic Plotter. It's the neat solution to the problem of long, drawn-out hard copy graphic displays. 11712

CIRCLE 67 ON INQUIRY CARD

HEWLETT hp PACKARD

1507 Page Mill Road, Palo Alto, California 94304

For assistance call: Washington (301) 948-6370, Chicago (312) 255-9800, Atlanta (404) 955-1500, Los Angeles (213) 877-1282

Charge-Transfer Devices — Part 1: The Technologies

Eric R. Garen

Integrated Computer Systems, Inc
Culver City, California

Charge-transfer devices have been one of the most rapidly advancing large-scale integration technologies in recent years. While the most publicized of these devices have been charge-coupled device digital memories, the technology and its implications are far more extensive. For example, charge-transfer devices are also finding widespread application in analog signal processing, digital logic, and solid-state image sensing. In this first in a series of three columns, the basic charge-transfer device technologies are described and compared. The next column will describe the history and current status of charge-coupled device memories, and the third will be devoted to signal processing and imaging devices and applications.

To accomplish these diverse tasks, several subsets of charge-transfer device (CTD) technology have been devised to handle analog as well as digital information. The first of these is the charge-coupled device (CCD) itself. A CCD is functionally a shift-register memory for either analog or digital information in which the data are represented as stored charges. The charges in a CCD are stored in a linear array of "potential wells," with the potential of each well controlled by a voltage applied to an isolated metal-oxide semiconductor (MOS) capacitor above the well. By applying a "traveling voltage wave" to this linear array of capacitors, any charges within the wells are pushed along from well to well (Fig 1).*



Fig 1 Shift control in a linear array of closely spaced MOS capacitors. Three-phase voltage (upper left) applied to series of cells (upper right) causes accumulated charge to move from cell to cell (lower right)

For a digital memory, the potential wells are either uncharged or fully charged to represent 0 and 1. To implement an analog memory, the charge is varied linearly in proportion to the sampled input voltage. Thus, analog delay lines as well as digital memories are implementable with CCD technology. Furthermore, as will be detailed in part 3 of this series of columns, analog CCD shift registers can be integrated on the same chip with other electronics to build image sensing arrays and other complex integrated devices.

Related in function, but differing in principle of operation, are bucket-brigade devices (BBDs). The essential difference in performance between CCDs and BBDs is that CCDs are faster and transfer virtually all electrons from cell to cell, while BBDs may lose a small fraction of the number of electrons present, typically 0.1%.

BBDs transfer stored charges from one physical capacitor to another by opening and closing a sequence of field-effect transistor (FET) switches which separate the capacitors (Fig 2). The input to the BBD is an n-channel MOS transistor switch. When energized by clock ϕ_1, it connects the analog input signal to input capacitor C_s. This charge is then transferred from C_s to the first stage capacitor by clock ϕ_2, which energizes the transistor switch between C_s and C_1. Clock ϕ_2 also provides a positive bias to C_1, thus "pulling" electrons away from C_s. Similarly, clock ϕ_2 then transfers the charge sample from C_1 to C_2, etc. Thus two capacitor stages are required for each charge sample and the samples are passed on clock ϕ_1 from odd to even stages, and on ϕ_2 from even to odd.

In practice, not quite all of the charge is transferred in such devices and this is often the factor which limits the signal-to-noise (S/N) ratio. Because of this, in practical applications typical S/N ratios are between 40 and 50 dB (ie, between 7- and 8-bit accuracy) even though the BBDs may be rated closer to 70 dB (12 bits). It now appears that CCD technology will largely replace BBDs because of an approximately 20-dB improvement in S/N ratio over BBD as well as simpler, more compact, and therefore less expensive structures. Part 3 of this series of columns will

*H. R. Crouch, J. B. Cornett, Jr, and R. S. Eward, "CCDs in Memory Systems Move Into Sight," *Computer Design*, Sept 1976, pp 75-80

Announcing another new 6250 bpi tape transport...

For minis!

Engineering breakthroughs enable Telex to bring big computer storage and reliability to OEMs at a fraction of the size and cost.

The long-awaited 6250 bit-per-inch (bpi) tape drive for minicomputers is here.

The Telex Model 6250.

It offers minicomputer users nearly four times the tape capacity of the previous 1600 bpi drives. Yet it takes up only one-fourth the space and costs only about half as much as the worldwide accepted, big box 6250 bpi units Telex has supplied to IBM users for years.

The four-to-one size reduction wasn't easy.

It took three years and a whole new standard of design to pack all that technology in a 19-inch frame. Parts innovations. Creative placement of needed elements. New materials. All have led to a remarkable achievement in simplicity and reliability.

The machine meets all the stringent requirements of true high density, 0.3-inch inter-record gap recording in both read and write operations.

In addition, the drive:

- Handles all three standard data formats—NRZI, PE and the new GCR.

- Runs reliably at speeds to 125 inches per second (models are also available at 45, 75 and 100 ips).
- Transfers data at the high speed of 781 kB per second (so off-loading can be done at nearly disk speeds).

- Rewinds a full 2400-foot tape reel in less than a minute. (That's 500 inches per second!)
- Reduces the complexity and cost of field maintenance (all work is done from the front).

Remarkable new capstan weighs only 1.9 grams.

To feel this Supr-Lite™ capstan is to believe its engineering achievement.



Not only does its lack of weight reduce inertia, it lets us use a smaller motor. Heat is reduced. Cooling blowers and hoses are eliminated.

Capstan walls are only 1/1000-inch thick, yet its unique manufacturing process* assures strength, absolute roundness (and users a more consistent data rate).

Telex tape path gets you up to speed in a hurry.

Perhaps the most dramatic example of how Telex miniaturized the 6250 is its tape path*. The path is very compact, yet it retains four vacuum columns (just like big brother).

It brings new efficiencies in tape dynamics and reduces the length of tape required between head and primary vacuum columns.

Combined with our new capstan, friction and mass are cut down so much that the unit runs tape full speed forward to full speed reverse in a mere 0.13 inches (a new record).



Special vacuum buffers and fixed air bearings gently handle tape at the high program rates possible with short inter-record gap operation. They eliminate long spans of unsupported tape, thus avoiding harmful tape oscillations that can restrict programming.

And we're so confident of tape servo reliability that we covered up the tape path with the operator's panel (further reducing space requirements).

New controller/formatter handles up to eight drives.

It includes the same proven logic design as our big controller, only miniaturized to fit a 10 ½-inch-high, rack-mounted box. And it's flexible enough to intermix all four tape speeds and all three densities—800, 1600 and 6250 bpi—in the same subsystem.

A built-in microprocessor handles extensive diagnostic routines.

When maintenance is required—on either controller or drive—the machine helps the technician quickly isolate faults down to board level for simple replacement. Given on-hand parts, a disabled machine should take less than an hour to fix. And all maintenance is done from the front.

Plug it in and go, it's that simple.

A common wall socket is all that's needed. And no special air conditioning. You can even operate it from a truck.

Design innovations with a goal of simplicity have enabled Telex to bring OEM's this remarkable new tape transport and controller. Large minicomputer users need this 6250 bpi mass storage capacity. Models are available now in dual density 800/1600 bpi. Full 1600/6250 bpi units will ship in the first quarter of 1978. Be the first to offer it.



Write or call Mr. Dan O'Neill, Telex Computer Products, Inc., 6422 E. 41st Street, Tulsa, Oklahoma 74135. Telephone: (918) 627-1111.

* patent pending

TELEX®

Miniaturization...in a big way.

CIRCLE 68 ON INQUIRY CARD



Fig 2 Typical BBD structure. Input signals charge C_S during ϕ_1, after which ϕ_2 clock transfers charge to C_1 by energizing FET switch 1 and "pulling up" C_1 to attract minority carriers away from C_S. Next, ϕ_1 clock transfers this charge to C_2. This continues until the charge reaches final storage cell C_N which controls the output switch and is discharged on ϕ_2 through V_{DD}



Fig 3 Example of 4 x 4 CID imaging array. Each cell consists of two capacitors, one attached to row control line (X), other to column control (S). Initially, all charges are stored under row electrodes. Readout is accomplished by precharging column electrodes to V_S, and then removing row voltage. As shown in X_3 row, charges then transfer to column electrodes. Column voltages can then be sequentially connected through selection switches Y_1 through Y_4 to video preamplifier Q_1

discuss how BBD delay lines, nevertheless, have already found widespread usage in analog (especially acoustic) processing.

A third basic charge transfer mechanism is charge injection which has been applied to image sensing devices. In charge-injection devices (CIDS), the charge is stored in an X-Y addressable array of potential wells. For image arrays, the charge for each of the cells is generated by an associated photodiode. In early CIDS, readout of the array was accomplished by addressing a single cell and injecting the stored charge into the substrate. The resulting displacement current was detected and amplified to create an output voltage. Thus, the "detection" or readout mechanism was directly achieved by the injection process which simultaneously cleared each cell (ie, destructive readout).

(*Continued on p* 152)

CIRCLE 69 ON INQUIRY CARD →

Unlike fabricated metal, GE Engineering Structural Foam can show a beautifully simple side plus an incredibly complex side together, in one piece.

Take the outside. In GE Engineering Structural Foam resin, the total effect is a clean, integrated, contemporary look. And it stays that way with excellent impact, heat or chemical resistance. Yet, while the outside looks like a work of art, the other side works. And works hard.

That's because GE Engineering Structural Foam is so rigid, strong and stable, it supports internal components and assemblies all by itself. Costly secondary parts, materials and operations are eliminated. What's more, GE Engineering Structural Foam is double-insulated and can meet UL 94 V-O*. Best of all, its simple one-step molding process eliminates metal's numerous, costly production steps, and its lighter weight reduces shipping costs.

For more information, write Structural Foam Resins Section 300, Plastics Division, General Electric Company, One Plastics Ave., Pittsfield, MA 01201.

Or talk to NCR, TRW and Datapoint.

GE ENGINEERING STRUCTURAL FOAM RESINS BEATS METAL WHERE IT COUNTS:



STYLING FREEDOM OUTSIDE

COST REDUCTION INSIDE.

*This rating is not intended to reflect hazards presented by this or any other material under actual fire conditions.

WHAT THE WORLD IS COMING TO: GE ENGINEERING STRUCTURAL FOAM
LEXAN® NORYL® VALOX®

GENERAL ELECTRIC

Choose an INSTANT-PERIPHERAL™ for highly reliable cassette recording in microprocessor-based systems.

Now there's a ready-made solution for your low-cost digital storage needs. And EPI's Speed Tolerant Recording (STR®) technique provides error rates of less than 1 bit in 100 million for high data reliability.

The STR-150 and 300 interface easily with your microprocessor-based systems. Use them for automatic bootstrap, backup memory and field retrofit resident loaders—wherever you need fast, reliable program loading to restore lost programs, change programs or run diagnostic routines. The STR-300 is also ideal for data storage applications such as intelligent terminals, allowing you to store transaction data and remotely access for off-line data processing.

Look into an INSTANT-PERIPHERAL™ for your program loading and data storage needs. Contact Electronic Processors, Inc., 1265 W. Dartmouth Avenue, Englewood, Colorado 80110. Phone (303) 761-8540.



STR-150 provides full remote signal or character control of all transport functions. It includes read-write electronics, control and logic, and motor-control logic. Just supply a mounting location, power supply and interface with the controlling I/O device. $374 in 100's.



STR-300 is microprocessor based for added flexibility. Like the STR-150, it is fully remote controlled and easily interfaced, but includes a buffer memory for incremental or character-by-character recording and play-back. $685 in 100's.

ELECTRONIC PROCESSORS INCORPORATED

The INSTANT-PERIPHERAL™ Company

More recently, this technology has been advanced by the General Electric Research and Development Laboratories by separating the functions of detection and injection, making nondestructive readout possible. Fig 3 shows the basic structure of a 4 x 4 array of storage cells, and also shows an example of signal-charge stored beneath each capacitor. Initially, all charges are stored beneath the "row" capacitor of each storage cell. To read the cells, the column capacitors are first "cleared" by applying the reference voltage, V_s, to the column lines, which are then allowed to float. Voltage is then removed from the capacitors in the row selected for readout (X_3), causing signal charges at each cell in that row to transfer from the potential well beneath the row electrode to the well beneath the column electrode. The resulting change in voltage caused on each of the floating column lines is then sequentially detected and amplified.

Following this line readout operation, all charges on the selected line can be injected (cleared) simultaneously by driving all column voltages to zero. Alternatively, for nondestructive readout the injection operation is not performed. Instead the row voltage is simply reapplied, thus attracting the signal charges back to the row capacitor. Using this interesting technology, General Electric has developed a 244 x 248 element imaging array and has applied it in a low cost camera system (to be described in part 3 of this series).

These three different charge-transfer technologies—CCD, BBD, and CID—make possible an extremely wide range of devices that are now finding applications throughout the electronics industry. History, current status, and applications of the devices will be discussed in the next two columns.

SYSTEMS ENGINEER

You will perform and/or conduct system evaluation related to performance characteristics of computer based Point-of-Sale systems and subsystem elements (terminals, computers, peripherals, etc.) Candidates must be familiar with micro and minicomputer systems hardware and they should bring 2 or more years experience including exposure to isolating and solving problems related to RFI-EMI.

LOGIC DESIGN ENGINEER

For digital implementation of algorithm required for video signal processing using TTL and/or microprocessor circuits.

NCR's P.O.S. division is located in east central Ohio and offers an inviting work and family living environment.

Robert W. Donovan
Terminal Systems Division
NCR Corporation
Box 728
Cambridge, Ohio 43725
614/439-0293

NCR

An Equal Opportunity Employer

Sperry Univac's new mainframe-on-a-board: What you do with it is your business.



Whether your systems business is scientific, instrument control, or data communications, know this:

Our new V77-200 delivers more computing power than any other computer-on-a-board you can buy. Handling up to 32K/16-bit words of 660ns MOS memory.

Reason enough to call it the world's first mainframe-on-a-board. But there's more.

Because our new V77-200 comes loaded with "big machine" features. Like 8 programmable registers with byte, word and double word manipulation. Up to 32-bits of arithmetic precision. A powerful set of 187 instructions. Hardware multiply/divide. Direct memory access. Programed I/O. Multi-device automatic program loaders. A real-time clock. And a teletype/CRT controller. All standard. And all on a single 10.8" x 17" board.

There's even Virtual Console Logic that eliminates the need for a programmer's console by allowing you to control the V77-200 from a teletype or CRT keyboard.

You get "big machine" performance, too. Example: a microinstruction cycle time of 165ns that allows multiplication functions to be handled in just 4.9 microseconds—divide in just 8.

Plus your choice of OEM-tailored options. Like a variety of connector planes and general purpose interface boards for custom I/O designs. Three different 660ns memory boards (in 8K, 16K, and 32K-word modules). An operator's console. Power-fail detect and data save. Memory parity. Hardware for up to 64 priority vectored interrupts. An integral or modular power supply. And a system chassis. All the "unbundled" pieces you need for quick and easy system integrations.

The new V77-200 also saves you time and money by allowing you to use Sperry Univac's well-established floppy or disk-based VORTEX real-time operating system. In effect, allowing you to concentrate on the development of your application software.

And giving you access to Sperry Univac's extensive library of software subsystems, language processors, and system utilities.

Best of all, the world's first mainframe-on-a-board has a base price of just $1200. Plus a discount plan designed to give even modest-volume OEM buyers a big break. And you can take delivery in a matter of days—not months.

No matter how you configure it, the new V77-200 is the most economical Sperry Univac yet. Delivering the kind of price/performance value that just makes good sense. No matter what business your systems are in.

For more information on the world's first mainframe-on-a-board, please contact: Sperry Univac Mini-Computer Operations, 2722 Michelson Drive, P.O. Box C-19504, Irvine, California 92713, Telephone (714) 833-2400.

SPERRY UNIVAC

SPERRY UNIVAC IS A DIVISION OF SPERRY RAND CORPORATION

CIRCLE 71 ON INQUIRY CARD

Rockwell introduces the R6500.



R6500: the third generation microprocessor system

Now you can move up to the proven 2 MHz performance of an NMOS 8-bit microprocessor, the R6500 from Rockwell.

Third-generation R6500 architecture and instructions with 13 powerful addressing modes make it easier for you to design more functions in, more cost out. And the R6500 is design-compatible with systems you may now be using.

R6500 economics are on your side

Smaller R6500 chips and single 5V power supply keep costs down as performance goes up. To get the right fit, choose from 10 software-compatible CPUs, eight versatile I/Os, ROMs, RAMs, and memory-I/O-timer circuits.

R6500 CPU Options

	40-Pin DIP		28-Pin DIP				
	R6502	R6512	R6503 R6513	R6504 R6514	R6505 R6515	R6506	R6507
Memory Address Space	65K	65K	4K	8K	4K	4K	8K
Interrupts — Maskable — Non-Maskable	Yes Yes	Yes Yes	Yes Yes	Yes No	Yes No	Yes No	No No
SYNC — Output indicates op code fetch cycle	Yes	Yes	No	No	No	No	No
RDY — Single step and slow memory synchronization	Yes	Yes	No	No	Yes	No	Yes
ϕ_1 Clock Output	Yes	Yes	No	No	No	Yes	No
DBE — Extended Data Bus Hold Time	No	Yes	No	No	No	No	No

I/O Devices

PART #	NOMENCLATURE	DESCRIPTION
R6520	Peripheral Interface Adapter	2, 8-bit bidirectional I/O ports; 4 peripheral control/interrupt lines.
R6522	Versatile Interface Adapter	PIA functions plus 2, 16-bit programmable interval timers/counters.
R6530	ROM-RAM-I/O-Timer	1024 x 8 ROM, 64 x 8 static RAM; 2, 8-bit bidirectional data I/O ports; 2 programmable data direction registers; 8-bit interval timer.
R6532	RAM-I/O-Timer	128 x 8 RAM; 2, 8-bit bidirectional data ports; 2 programmable data direction registers; 8-bit interval timer.

PLUS ROMS, RAMS...AND MORE ON THE WAY

Rockwell adds solid development support

For fast and efficient system design, Rockwell offers SYSTEM-65 — one of the smartest and lowest-cost, disk-operating, complete development systems available. It's equipped with two mini-floppies, resident two-pass assembler, text editor and monitor/debug package.

KIM-1, TIM, timeshare, complete documentation, plus extensive applications engineering are also available.



Rockwell is delivering in volume now

R6500 circuits are already being produced in quantity with Rockwell's N-channel, silicon-gate, depletion load process.

R6500 devices and SYSTEM 65 development microcomputers are now available at your local Hamilton-Avnet or Schweber distributor.

And new chips are in design. The first, a fully static 32K ROM, is now in production.

For your R6500 brochure write: D-727-A, Marketing Services, Microelectronic Devices, Rockwell International, P.O. Box 3669, Anaheim, CA 92803, U.S.A. or phone (714) 632-3729.

Rockwell International

...where science gets down to business

CIRCLE 72 ON INQUIRY CARD

Universal Controller Interfaces Printer to Mini/Microcomputers

Control of and interface to any standard impact, thermal, or electrostatic 5 x 7 dot-matrix printer having a print speed up to 200 char/s is now possible with the model CY 480 universal printer controller. The controller interfaces between a printer and any microcomputer or minicomputer system through standard 8-bit ports, accepts either RS-232-C (serial) or parallel ASCII from the host system data channel, and has ready lines for full asynchronous communications with handshaking.

Features of the controller, which is a product of Cybernetic Micro Systems, 2460 Embarcadero Way, Palo Alto, CA 94303, include a dot-matrix character generator and optional foreign language character generator, full 96-char ASCII font, and 48-char buffer expandable to 96 characters. In addition, the low power device provides a forward or backward printing command at 8, 10, or 12 char/in density, and feeds paper in an up or down direction, handles 2-color ribbons, and allows variable horizontal and vertical spacing in graphics mode. Moreover, images can be displayed in true as well as mirrored form using the forward/backward and up/down print capability in graphics mode. The controller comes in a 40-pin DIP, and operates from a single 5-V supply.

Circle 360 on Inquiry Card



Instructions to Motorola MC14500B industrial control unit (ICU) enter via pins 4 through 7, while 1-bit data move into ICU via data bus, route through logical unit, and leave via multiplexer

Control Unit Offers Alternative to Combinatorial Logic

The MC14500B industrial control unit (ICU), a single-bit CMOS processor for systems requiring decisions based on successive 1-bit data, when used in a system with program counter forms a stored program that replaces combinatorial logic. A repertoire of 16 instructions, 11 of which perform control functions within or external to the ICU, enable the device to perform several logic operations on data occurring on a 1-bit bidirectional bus and on data in a 1-bit accumulating result register. By operating on inputs and outputs one at a time and by using a looping (rather than jumping) program flow, an ICU-based system can control decision making electronic and electromechanical devices in microprogram-control sequencers; serial bit-stream communications; telephone dialing systems; and peripherals such as printers, keyboards, discs, and controllers.

Logical operations executed by the device include AND, OR, exclusive-OR, complement, complement OR, and complement AND. Data can be routed unchanged through the device as well. All logical operations occur in a logic unit (LU) on the ICU (see Figure). Operands enter the LU from the data bus and from the result register (RR) which also holds the output from the LU after a logical operation completes. True and complement outputs of the RR are routed to a multiplexer which, under program control, directs one of the two RR outputs to the data bus. Besides its logic operation capability, the ICU can generate a write level, an O flag, an F flag, a jump indication, and a return indication.

The ICU, produced by Motorola Semiconductor Products Inc, 3501 Ed Bluestein Blvd, Austin, TX 78721, contains its own oscillator circuit. It operates from dc to mHz with V_{DD} set at 5 V and executes one instruction per clock cycle. The four instruction inputs to the device are TTL-compatible, while its output lines can drive one low power Schottky load or two low power TTL loads. Other features include a typical noise immunity of 45% over a 3-Vdc to 18-Vdc V_{DD} range and a low current drain—quiescent current drain is typically 5.0 μAdc with V_{DD} = 5 V.

Circle 361 on Inquiry Card

CMOS A-D Converter Provides BCD Output

Latched, non-multiplexed, parallel BCD from the 8750 3½-digit CMOS analog-to-digital converter enables application in LCDs and gas discharge displays. Moreover, its typical power dissipation of only 20 mW, which results in a 2-mA drain on its ±5-V supply, permits the monolithic converter to serve also for battery-powered operation. It offers monotonic operation—it uses no missing codes—as well as high linearity, noise immunity, and 3½-digit resolution with ±0.025% error.

During A-D conversion (see Figure), the analog input current to the converter, I_{IN}, flows into an integrator comprising resistor R_{IN} and capacitor C_{INT}, at the input of an operational amplifier. Concurrently, a reference current, I_{REF}, which is opposite in

Now... the Coolest Fastest Biggest Bipolar Multipliers you can buy

feature MIL chips in commercial temperature ranges (at no increase in price)

MPY-8AJ
130 ns
8 x 8 bits



Only $70 in 100's

MPY-12AJ
150 ns
12 x 12 bits



Only $115 in 100's

MPY-16AJ
160 ns
16 x 16 bits



Only $175 in 100's

We've cut out all excess power . . . to offer you MIL chip reliability and performance in commercial temperature range parts. Consider these advantages for Digital Signal Processing:

- low power
- no air flow requirement (0°C to 70°C in still air)
- high reliability (for example a recent test indicated an MTBF greater than 200 years at max. oper. temp.)
- reduced output delay

No increase in price! A great increase in reliability! We have the details in our new reliability brochure. For your copy, send the coupon today. Or you can call us at (213) 535-1831.

TRW LSI Products
An Electronic Components Division of TRW, Inc.
P.O. Box 1125
Redondo Beach, CA 90278

☐ **Please send Reliability Brochure and updated data on your "cool" Multipliers.**

NAME _____

COMPANY _____

DIV/DEPT _____ MAIL CODE _____

ADDRESS _____

CITY _____

STATE _____ ZIP _____ CD-11

TRW LSI PRODUCTS

For Digital Signal Processing

CIRCLE 73 ON INQUIRY CARD



*Components chosen for V_{IN} (full scale) = 10V, V_{REF} = −6.4 V

Teledyne 8750 conversion technique switches number of current pulses needed to zero analog current at input of op amp and thus, by counting number of pulses used, determines digital equivalent of incoming analog

polarity to I_{IN}, is switched into the integrator by converter internal clock and control logic and integrated with I_{IN}. I_{REF} is switched for one clock period into the integrator just frequently enough to maintain the input to the op amp at zero.

The total number of I_{REF} pulses needed to maintain the op amp input at zero is counted by one of two converter counters, a data counter, and the resulting BCD count for a given analog input is read into the output latches. After the conversion process is started by the initiate conversion input, the second of the two counters, a clock counter, counts a prescribed number of pulses defining the conversion time of the device and, then, initiates an end-of-conversion sequence in the converter.

A positive signal generated internal to the converter strobes the initiate conversion input to start an A-D conversion. At this time, the busy line latches high, the counters are reset, and the integrator is discharged. A-D conversion begins immediately afterwards and continues until the clock counter initiates the end-of-conversion sequence or the data counter overflows. During the end-of-conversion sequence, the valid output falls to a low for approximately 10 μs, during which time the latched BCD output changes to reflect the output resulting from the conversion just performed.

In normal operation, the initiate conversion input is a 500-ns (typ) pulse which enables the converter to function. By applying a constant high on this input the converter can operate in a freerunning mode producing a typical 100 conversions/s.

Manufactured by Teledyne Semiconductor, 1300 Terra Bella Ave, Mountain View, CA 94043, the converter affords a maximum differential nonlinearity of 0.025% with temperature drift of typically ±2.5 ppm/°C, a gain variance of ±2% of normal and a gain temperature drift of ±25 ppm/°C. Furthermore, the device provides a zero offset of typically ±10 mV with I_{IN} = 0, a zero temperature drift of ±30 μV/°C, and a conversion time of 10 ms. It is available in plastic DIP for operation over the 0 to 70°C temperature range and in ceramic DIP for operation over the −40 to 85°C range.

Circle 362 on Inquiry Card

Companding DAC Meets Bell μ-255 Law

Companding digital-to-analog conversion designed for telecommunication applications is now also available with the Am6072 DAC produced by Advanced Micro Devices Inc, 901 Thompson Place, Sunnyvale, CA 94086. A pin-for-pin replacement for the Precision Monolithics, Inc DAC-86, the device complies with the Bell System u-255 companding law by using 15 linear chords, each defined by a sign bit and three chord select input bits, and, within each chord, 16 uniformly spaced linear steps, each defined by four step select bits. Thus a 72-dB dynamic range, equivalent to that of a 12-bit linear converter, is achieved using only eight bits. The DAC is available in commercial and military temperature range units.

Circle 363 on Inquiry Card

New DIRECTROL™ Multiplexer. Signaling new directions for industrial control.

Cutler-Hammer's new DIRECTROL . . . finally, here's a multiplexer that's practical for industrial control application. DIRECTROL achieves startling advantages in project simplification, system productivity and plant versatility.



DIRECTROL's loop configuration permits "on-the-fly" modifications (adding terminal station #8) without system shutdown. Accelerates minor revisions and extensive system expansions.

Project simplification. DIRECTROL is designed and applied in a conventional control manner. But unlike the conventional, it substantially reduces wiring costs and project complexity—easily adapting to unanticipated requirements. For the first time, DIRECTROL offers control multiplexing in easy-to-apply, easy-to-order, easy-to-install modules.

System productivity. DIRECTROL's innovative approach provides high-yield features like monitoring of multiplexer performance on every signal scan, high security data handling routines, self-diagnostic/self-correcting characteristics, integral high noise immunity and multiple redundancy options to name only a few. Plus the unique ability to add new stations "on the fly" without affecting system operation.

Plant versatility. DIRECTROL's 4,096 signal capacity and 5,000 foot distance between stations combine with "stand-alone" independence or computer compatibility to add dramatic equipment selection flexibility for future needs.

Why not set a new course for your industrial control requirements? Write Milwaukee, Wisconsin 53201 for descriptive brochure.



CUTLER-HAMMER

Best by Design

CIRCLE 74 ON INQUIRY CARD

Is your computer smart enough



A 3M peripheral drive which uses 3M data cartridges is better than any drive which uses punched cards or paper tape.

And, if you'd take the time to ask it, your computer would probably tell you so.

It's simple logic.

Cartridges are faster than cards.

Cards and paper tape are slow. It takes hundreds of cards for a single computer program.



Cards must be read one at a time.

Or hundreds of feet of paper tape.

And each program must be punched, verified and read one card at a time.

With our drive system, on the other hand, programs are stored on a single tape cartridge.

Cartridges offer much faster data storage, program loading, data transfer and faster access to the computer.

So you save time and money.

Cartridges take less space.

It would take a stack of cards almost sixteen feet high to store all the information you can store on a single 3M DC-300A data cartridge.

With cartridges, you can store all of your programs in a fraction of the space you'd need for cards or paper tape.

Your filing system is simplified and overhead is greatly reduced.

One DC-300A cartridge equals almost 16 feet of cards.



Cartridges won't fold, spindle or mutilate.

Unlike paper cards, you need never touch the media. It's well

to choose our cartridge drive?



One formatter can control eight drives at once.

protected inside the cartridges, so it's virtually impossible to damage.

You can carry a DC-100A cartridge with an entire program in your shirt pocket.

Even if you drop it, the program will survive unscathed.

Remember that the next time you drop a stack of cards.

Don't take our word for it. Ask your computer.

If you'll send us the coupon, we'll send you the specifications for all three of our drive systems.

Ask your computer to compare them with any other type of drive system.

We'll bet your computer will prefer ours.

Maybe it'll choose our famous DCD-3 drive. It's people-proof, jam-proof and wear-resistant.

Or maybe your computer will decide upon our DCS-3000 series, an ANSI-formatted system that allows one formatter to control up to eight drives.

The DCS-3000 is extremely easy to integrate into your system. Only one cable to the user's logic is required.

But if you require compact size, your computer will probably choose our unique DCD-1. It offers many of the features of our bigger systems, yet it will fit inside a five-inch cube.

The cartridge alone measures just 2.4 x 3.2 x .5 inches.

See for yourself.

Send us the coupon. There's much more we can tell you about our drive systems.

Study the information carefully. If your computer isn't smart enough to choose our drive systems, we'll bet you will be.

Send me more information.

Name _____ Title _____

Firm _____ Address _____

City _____ State _____

Zip _____

Phone _____

3M COMPANY

Mail to: 3M Company
Data Products, Dept. 125
Mincom Division, Bldg. 223-5F
3M Center
St. Paul, Minnesota 55101

CIRCLE 75 ON INQUIRY CARD

The IC Switching Regulator that has everything!



The Ferranti Model ZN1066E Pulse Width Modulator for use in:
Switching Regulated Power Supplies, Motor Speed Controllers, DC/DC Converters and much more.

Features:
- High Efficiency
- 0-100% duty cycle control
- Zero overlap of external output transistors guaranteed
- Single ended or complimentary output drive
- Up to 120 mA output drive
- Output frequency adjustable to 500 KHz
- On-chip amplifiers for voltage and current control
- Short circuit protected
- 2.6 V stable reference, ±50 PPM/°C
- Soft start capability
- Inhibit and synchronizing inputs
- Major circuit functions externally accessible



better by design

FERRANTI semiconductors

FOR COMPLETE SPECIFICATIONS, CONTACT: FERRANTI ELECTRIC, INC. / SEMICONDUCTOR PRODUCTS
EAST BETHPAGE ROAD, PLAINVIEW, NEW YORK 11803 PHONE: (516) 293-8383 / TWX: 510-224-6483

CIRCLE 76 ON INQUIRY CARD

AROUND THE IC LOOP

Multiplier Offers 100 ns/ 1 W Speed/Power Product

Multiplication of two 8-bit signed 2's complement, unsigned uncomplemented, or a combination of both operands is possible with the 57558/67558 8 x 8 combinatorial multiplier which accepts rounded operands and provides a 16-bit product and an inverted most significant bit output. Having the most significant bit in both true and complement form enables signed product expansion. In addition, the outputs of the device are 3-state, thus allowing the multiplier to serve in pipelined systems.

The device, which multiplies at 100 ns while dissipating only 1 W, serves such digital signal processing functions as fast Fourier transform and speech and signal processing. Other applications include calculations in computer-aided tomography (brain and body scanning) and fast floating-point processors.

Multiplier specifications include a minimum high level and maximum low level input voltage of 2 and 0.8 V, respectively, a maximum low and high level output current of −2 and 8 mA, respectively, and a maximum −10-mA output short circuit current. The device, which is made by Monolithic Memories Inc, 1165 E Arques Ave, Sunnyvale, CA 94086 and second sourced by ITT Semiconductors, operates over a temperature range of 0 to 70°C with a supply voltage in the range of 4.5 to 5.5 V.

Circle 364 on Inquiry Card

Low Power EPROM Operates From Single Supply

Fast access time, rapid and simple programming, and single 5-V supply requirement are key features of the 2758 1k x 8 UV-erasable programmable read-only memory. Low power dissipation derives from the 525-mW maximum active power requirement falling 75% to a low 132 mW when memory is placed in a standby state. Unaffected by the standby state is the memory's fast 450-ns maximum access time. Programming speed complements the operating speed: 1024 bytes can be programmed in less than a minute, claimed to be twice as fast as for other EPROMs; a single byte can be programmed in 50 ms, 10 bytes in 0.5/s.

Non-dependence on multiple supplies permits it to serve in systems structured around single-supply, single-chip microcomputers. Also, the memory can operate off an MOS or TTL supply.

The EPROM contains ten address lines, eight data outputs, and chip select ($\overline{CS}$), power down/program (PD/PGM), and select reference input level (A_R) inputs. All are TTL-compatible during both read and program operations. Also, the output lines are 3-state, thus allowing OR-ties with the output lines of other EPROMs. The high impedance state emerges when the $\overline{CS}$ input deselects the memory.

During read, data are available 450 ns after the address on the address line stabilizes and $\overline{CS}$ is in the low (enable) state. When $\overline{CS}$ goes high, disabling the EPROM, a logic high level on PD/PGM selects the power down mode. It is possible for the $\overline{CS}$ and PD/PGM lines to be driven by the same level. Finally, the A_R input contains low voltage level for reference during all memory operations.

This EPROM is made by Intel Corp, 3065 Bowers Ave, Santa Clara, CA 95051 and is compatible with other company EPROMs and masked ROMs.

Circle 365 on Inquiry Card

Now you can expect even more from Lear Siegler.



Printers.

Introducing Lear Siegler's new 200 series printer.

Our revolutionary Ballistic™ printer head design makes us unique among printer manufacturers. Unlike other matrix printers, there are no solenoids, and thus no moving cores attached to the wires. The Ballistic™ head uses small "swatters" that ballistically propel the matrix wires. This simplified system has eliminated clogging with inks, dust and paper fibers – so the Ballistic™ head requires no preventive maintenance. If you have a requirement that calls for continuous printing, and the cost of service is important to you, our 200 series printers will give you the lowest cost of ownership.

Lear Siegler's new 200 series printers are designed to have at least 10 times better reliability than presently existing printers. Remarkably, the Ballistic™ heads are capable of printing up to 1 billion characters before needing a replacement. And with a fully-buffered input for bi-directional printing, you can print an original and 5 copies at 180 cps. With no head adjustment.

Compare this with the up-to-now-best printer's head, which needs constant adjustment, and lasts only for about 100 million characters. If you were lucky. And many times you weren't.

So if you're tired of depending on luck, and need non-stop output, you owe it to yourself to look into our new printers.

You'll like what you see.

LSi®

Lear Siegler, Inc./Electronic Instrumentation Division, Data Products, 714 N. Brookhurst St., Anaheim, CA 92803; (800) 854-3805. In California (714) 774-1010.

CIRCLE 77 ON INQUIRY CARD

Low Power p/ROM Offers 96% Programmability

Key characteristics of the MB7055/7060 1024 x 8 electrically field programmable read-only memory made by Fujitsu America Inc, 2945 Oakmead Village Ct, Santa Clara, CA 95051 include 150-ns typical access time and 0.044-mW/bit power dissipation. Moreover, inputs and outputs to the device, including a chip enable input which affords typical 60-ns and maximum 150-ns access times, are fully DTL/TTL-compatible. Such features as these make the device an enhanced replacement for such parts as the earlier Intel 2708 and the Fujitsu MB 8518.

Programming the p/ROM, which involves the avalanche induced migration technology, is available through Data I/O and Pro-Log offices. 96% programmability is achieved using special circuitry that permits post-packaging tests for ac, dc, and programming parameters. The devices are available in 24-pin ceramic DIPs.
Circle 366 on Inquiry Card

Design Kit Facilitates Custom IC Design

For the electronic engineer without previous experience in IC design, all necessary information to design linear or digital custom circuits is available in the Mo-K design kit from Interdesign, Inc, 1255 Reamwood Ave, Sunnyvale, CA 94086. An updated and expanded version of the company's Monochip design kit, this package contains an overview of IC design on a 30-minute audio cassette; a 212-page handbook containing sections on component parameters, computer analysis, predesigned functional blocks, IC layout, and chip selection; and several design tools and 20 DIP parts for breadboarding. Included in the $59 kit price are free layout sheets, consultation from the company's IC design group, and monthly application note updates.
Circle 367 on Inquiry Card

Monolithic Voltage Controlled Filter

Specifications for the SSM2040 voltage controlled filter (VCF) include better than 75-dB signal/noise levels, 0.1% distortion levels, and a guaranteed control rejection characteristic over its 10,000:1 sweep range. Elements of the filter include an exponential generator, four 3080-like voltage controlled amplifiers, and four high impedance buffers that offer four flexible tracking filter sections. The VCF can serve in any type of active filter including lowpass, bandpass, highpass, allpass, notch, biquad, and state variable. Other applications include parametric equalizers and tracking filters. The device is offered by Solid State Music, 2102A Walsh Ave, Santa Clara, CA 95050.
Circle 368 on Inquiry Card

Op Amps Feature Low Power Dissipation

Four internally compensated op amps, ULN4136A through ULN4436A, offering such capability as 300-V/mV typical open loop voltage gain, 90-dB typical common mode rejection, 120-dB typical channel separation, and 2-MΩ input resistance, meet or exceed industry standard μA741 amplifier specifications. They can directly replace LM124, LM148, and MC3404 series devices. The amplifiers, which serve in such applications as active filters and multichannel amplifiers, also offer continuous output short circuit protection and come in low power models that dissipate typically 60 mW of power. Total power consumption is 625 mW.

The devices, manufactured by Sprague Electric Co, 555 Marshall St, North Adams, MA 01247, feature monolithic construction to allow very close thermal tracking, 1-mV typical input offset voltage, 30-nA typical input bias current, 0.6-V/μV slew rate, input voltage range of ±14 V typical, and operating temperature range of 0 to 70°C. They are available in 14-lead DIPs conforming to JEDEC outline TO-116 as well as in 88-mil square chips for use in hybrid circuit devices.
Circle 369 on Inquiry Card

Op Amps Feature Lower Offset Voltages

Two op amps introduced by Precision Monolithics Inc, 1500 Space Park Dr, Santa Clara, CA 95050, the OP-08 and OP-12, are improved replacements for the LM108/308-type amplifiers. Both offer three times lower offset voltage (350 μV worst case over −55 to 125°C compared to 900 μV for the part it replaces) and two times lower offset voltage drift (2.5 μV/°C). Each drives a 2-kΩ load. Both devices serve in low power airborne controls and battery-powered applications, as well as 4- to 20-mA industrial control current loops.

A third op amp, the OP-11, is a precision quad device which offers an input offset voltage as low as 500 μV and replaces the LM148/HA4741-type amplifier. Guaranteed matched common mode rejection ratio of 94 dB minimum and offset voltage of 750 μV maximum enables it to serve in instrumentation amplifiers.

Because each amplifier affords symmetrical slew rates in positive- and negative-going directions, it can be used in audio systems as well. Other applications for the amplifiers, each of which offers low noise, low drift, and long term stability, include active filters and those requiring minimum space and low cost.

Each op amp is available in both military and commercial versions with each version having a number of models to meet varying operating requirements.
Circle 370 on Inquiry Card

Op Amp Offers High Slew Rate

Typical and guaranteed minimum slew rates of 60 and 40 V/μV, respectively, are characteristics of the SE/NE538 op amp which also offers a 2-mV input offset voltage, a 60-mA input bias current, and a 90-dB common mode rejection ratio over the −55 to 125°C temperature range. In addition, the device is internally compensated for gains of five or greater with a gain bandwidth product of 6 MHz and has an improved input structure that makes possible both upgrading of system speed performance and minimizing of errors.

The op amp accepts input signals in the range of ±13 V across a typical input resistance of 6 MΩ, provides a large signal voltage gain of 200 V/mV with a 2-kΩ load resistor and a ±10-V supply, and offers a 100-Ω output resistance and an output voltage swing of ±14 V. A product of Signetics, 811 E Arques Ave, Sunnyvale, CA 94086, the device can be used in digital-to-analog and analog-to-digital applications and in telecommunications and test and medical instrumentation. Because of features such as 2.2-mA typical power supply current and wide bandwidth, the amplifier can replace the LM318 amplifier in applications where required gain is greater than +5 or −4. □
Circle 371 on Inquiry Card

How to get a lot more into a lot less.







First, with 3 rows of contacts on .100 centers, Viking's unique Nordic 2-piece P/C board connectors and I/O I.C. panel plugs get a lot more contacts into a lot less space.

Second, our unusual polarizing system lets you key each mating pair to prevent cross mating with adjacent connectors of the same type. You can stack a series of Nordic connectors next to one another in cramped space and not worry that they might be cross mated.

Our full line includes 64 and 82 contact models as well as the 120. Contacts on I/O connectors are crimp, snap-in, removable, gold plated and use MIL-T- 22520 tools.

Diallyl Phthalate is the insulator in most models. And all connectors are designed to meet conditions of MIL-C-55302.

If you need them right now, our distributors have most models in stock. For details, use the coupon and get our latest catalog.

O.K. Send me: ☐ Your latest catalog with details on the two-piece PC connectors ...and your nearest rep. I have some questions for him.

Name: _____

Position: _____

Company: _____

Address: _____

City: _____ State: _____ Zip: _____

Viking CONNECTORS

Viking Industries, Inc., 21001 Nordhoff Street, Chatsworth, CA 91311

CIRCLE 78 ON INQUIRY CARD

A little knowledge about computers can be expensive. A lot can be free.

1. The inside story on how our full PRODUCT LINE makes the difference to you.
Reader Service # 301

2. How Commercial ECLIPSE Systems answer the diverse demands business makes today on a data system.
Reader Service # 302

3. The secret of having computer power where your business needs it. Our book on CS/40 SMALL BUSINESS SYSTEMS tells.
Reader Service # 303



4. Describes seven important SUPPORT SERVICES that get systems up and running, then keep them there.
Reader Service # 304



5. Find out how our Real-Time Disc Operating System SOFTWARE can get you on-line fast, and keep you there.
Reader Service # 305

6. IT'S SMART BUSINESS to know how our way of doing business benefits our customers.
Reader Service # 306



7. How OEM's solve the dilemma of keeping their system costs down with our NOVA 3 COMPUTER FAMILY.
Reader Service # 307



8. What you need to know about getting everything for a DATA ACQUISITION and CONTROL system from one place.
Reader Service # 308

9. The last word in microprocessor-based microNOVA systems with full 16-bit NOVA architecture.
Reader Service # 309



10. The amazing story behind our unique heuristic MULTI-PROGRAMMING operating system.
Reader Service # 310



11. What to do when you need fast, fast access to MASS STORAGE.
Reader Service # 311

12. NOVA 3 systems, software and support let you customize a system to your application.
Reader Service # 312

13. A wealth of information about how our computers are being used in actual APPLICATIONS.
Reader Service # 313



14. Wonder what sets the benchmark for big performance computer systems? Wonder no more, it's ECLIPSE S/230.
Reader Service # 314



15. Is there a sensible way to use computers in DATA COMMUNICATIONS? The message comes through clear.
Reader Service # 315



16. What's the most you can expect to get from a mid-range mini today? What you get with an ECLIPSE S/130 — the standard setter.
Reader Service # 316



17. You want terminals that work the same way you do? You want the facts on our DASHER TERMINALS.
Reader Service # 317

18. Our whole SPARE PARTS catalog. They're too important to be kept a mystery.
Reader Service # 318

19. 1976 was a very good year. Our ANNUAL REPORT could be good for you.
Reader Service # 319

Mail to: Data General, Westboro, MA 01581 CD-11

☐ Yes, I'd like to pick your brains. Please send me the brochures I have circled.

☐ I'm in a hurry. Have your sales representative bring in the brochures I have circled.

Brochure numbers: 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19

Name Title

Company

Address Tel.

City State Zip

Data General, Westboro, MA 01581, (617) 366-8911. Data General (Canada) Ltd., Ontario. Data General, Europe, 15 Rue Le Sueur, Paris 75116, France, 50-006-06. Data General Australia, Melbourne (03) 82-1361.

© Nova and ECLIPSE are registered trademarks of Data General Corp., 1977. DASHER is a trademark of Data General Corporation.

Data General
It's smart business.

© Data General Corporation, 1977

PRODUCT FEATURE

Diskette Drive Provides 4-Sided, Double-Density Capability

Although it retains the same physical outline as the company's standard dual diskette drives, the model 299 diskette drive introduced by PerSci, Inc has a maximum unformatted capacity of 25.6M bits. Fundamentally it is an enhanced version of the model 270/272/277 drives with the capability to read and record single or double density on present diskettes or on both sides of 2-sided diskettes. Four read/write heads are provided, one for each diskette surface. Two index sensors distinguish between single- and double-sided diskettes. Unlike earlier models, ac spindle motor power must be supplied.



Operating Characteristics

The electrical interface between drive and host system is maintained through three connectors. One handles all signals for the drive, the second provides dc power, and the third supplies ac power and frame ground. All of the lines in the signal interface are TTL.

Diskette select I/O lines, when activated to a logical 0 level, enable the various multiplexed signal I/O lines. Only the diskette or read/write head dedicated to the active select line will respond to the input lines and gate output lines. Normal, factory-installed connections establish individual diskette select input lines that activate the interface signals for each diskette and each side.

Options

A number of customer-installable options are available. These include multiplexing either four or eight 2-sided diskettes (two or four drives) using the four diskette select I/O lines as well as a side select I/O line. The side select signal line, not used in normal, factory-supplied configurations, defines which side of a 2-sided diskette is used for data transfer.

Standard connections allow head loading to occur when the diskette is selected if the diskette is present. However, an option that is useful in copying between diskettes allows loading of the heads independent of the state of the diskette select I/O lines if the diskette is present. A logical 0 activates the head load circuitry for the selected diskette. Heads will be loaded and stable, and data transfer may be initiated 35 ms after application of head load or side select signals.

In standard configurations, the manual eject inhibit I/O line is not connected. An option, however, allows this line, when activated to a logical 0 level, to inhibit operation of the unit's manual diskette ejection pushbutton as an OR function with the head load line. It also causes an LED to turn on for the selected diskette as an OR function with the diskette select line.

The remote eject I/O line is also not normally connected. Still another option allows this line, when activated, to energize a circuit that ejects the selected diskette. A 1-μs pulse to the logical 0 level activates the ejection circuit.

Summary of Specifications

Unformatted capacities for single and double densities, respectively, are 12.8M and 25.6M bits/drive, 6.4M and 12.8M bits/diskette, and 41.7k and 83.4k bits/track. IBM format capacities in single density are 8.0M bits/drive, 4.0M bits/diskette, and

ORION-60

A New Intelligence in the Nebula

Are you seeking a bright, high-contrast display – without jitter and distortion; one that combines unlimited vector length without flicker – with full alphanumeric capability, dynamic motion, and selective edit/erase?

If so, your answer is the ORION-60 graphics display terminal from Magnavox Display Systems – the pioneer producer of plasma display terminals.

Now, because of its modular design, the ORION-60 can be upgraded to a standalone, intelligent graphic configuration. The terminal, starting at $5995, may be converted to full standalone operation with many flexible options including: resident BASIC with graphics extensions, up to 56K bytes of user memory space, floppy disc for local mass storage, communication with external host via RS-232 interface, touch panel permitting user data entry by pointing at the screen with the finger, and optical rear projection using an integral 35mm computer-addressable random access projector.



FOR A DEMONSTRATION OF THE STANDALONE ORION-60 WRITE OR CALL US AT

2131 S. Coliseum Blvd.
Fort Wayne, IN 46803
(219) 482-4411 Ext. 6675 or 6680

Magnavox
DISPLAY SYSTEMS

CIRCLE 79 ON INQUIRY CARD

Intel delivers PDP-11 memory for people who can't afford to wait.

When you're in a hurry for more semiconductor memory for your PDP-11, call Intel. We deliver memory for the full PDP-11 line. And because we're the largest manufacturer of semiconductor memory in the world, delivery is when you want it.

Why wait? Since you've chosen the leader to supply your minicomputer, it makes sense to go to the leader for memory, too. That's us.

Intel memory systems save you more than time. Our in-1670 add-on memory for the PDP-11/70 is one example. It gives you four times the capacity in the same frame compared to the DEC MJ11-A core memory. And built in Error Correction Code (ECC) and Error Logging improve up-time and reduce maintenance time by automatically correcting and recording single-bit failures and detecting and recording double-bit errors.



For PDP-11 add-in memory go with our in-4711 plug in boards. You'll get memory that's even faster than DEC's. 16K words per hex-wide board. With or without parity. To further expand PDP-11 memory and reduce UNIBUS™ loading choose our in-4011 add-on. With memory management you can expand to 128K words in 16K increments. And since the in-4011 requires only one UNIBUS load, you get added system flexibility.

Get more memory for your LSI-11 and PDP-11/03 in less space with our in-1611 add-in memory. You get up to 32K words, in 8K increments, on a single, two-wide, board. That's up to eight times the memory you get with a DEC board.

When you can't afford to wait call us at 800-538-8476. In California and Canada, call 408-734-8102, x575. We'll save you time, and much more.

intel delivers.

CD-11

Intel Memory Systems
1302 N. Mathilda Avenue
Sunnyvale, California 94086

I can't wait! Must have delivery in ☐ 5 Days ☐ 30 Days ☐ _____ Days

☐ Please call me at _____/_____ Ext. _____

☐ Please send me information on semiconductor memory for the following:

☐ LSI-11, PDP-11/03
☐ PDP-11/04
☐ PDP-11/05
☐ PDP-11/34
☐ PDP-11/35
☐ PDP-11/40
☐ PDP-11/45
☐ PDP-11/55
☐ PDP-11/70

Name/Title _____
Company _____ Mail Station _____
Address _____
City/State/Zip _____

UNIBUS is a trademark of Digital Equipment Corp. Maynard, Mass.

intel® MEMORY SYSTEMS

U.S. AND CANADA SALES OFFICES

ALABAMA
Col-Ins-Co
Huntsville
(205) 881-9512
Glen White Assoc.
Huntsville
(205) 883-9394

ARIZONA
Intel Corp.
Phoenix
(602) 242-7205
BFA Corp.
Scottsdale
(602) 994-5400

CALIFORNIA
Intel Corp.
Santa Ana
(714) 835-9642
Intel Corp.
Sunnyvale
(408) 738-3870
Earle Assoc.
San Diego
(714) 278-5441
MAC-I
Berkeley
(415) 843-7625
MAC-I
Cupertino
(408) 257-9880
MAC-I
Fountain Valley
(714) 839-3341
MAC-I
Woodland Hills
(213) 347-1374

COLORADO
Intel Corp.
Denver
(303) 373-4920
BFA Corp.
Denver
(303) 837-1247

CONNECTICUT
Intel Corp.
Danbury
(203) 792-8366

FLORIDA
Intel Corp.
Ft. Lauderdale
(305) 971-7200
Intel Corp.
Orlando
(305) 628-2393
Col-Ins-Co.
Orlando
(305) 423-7615

GEORGIA
Col-Ins-Co
Stone Mountain
(404) 299-2138

ILLINOIS
Intel Corp.
Oak Brook
(312) 325-9510
Data Electronics
Chicago
(312) 283-0300

INDIANA
Data Electronics
Indianapolis
(317) 784-6360

IOWA
Technical Reps. Inc.
Cedar Rapids
(319) 396-5662

KANSAS
Technical Reps., Inc.
Olathe
(913) 782-1177

LOUISIANA
Col-Ins-Co
Baton Rouge
(504) 292-1755

MARYLAND
Intel Corp.
Timonium
(301) 252-7742
Glen White Assoc.
Timonium
(301) 252-7742
Mesa, Inc.
Rockville
(301) 881-8430

MASSACHUSETTS
Intel Corp.
Chelmsford
(617) 256-4131
Computer Marketing, Inc.
Waltham
(617) 890-1776

MICHIGAN
Intel Corp.
Southfield
(313) 353-0920
Lowry and Assoc., Inc.
Brighton
(313) 227-7067

MINNESOTA
Intel Corp.
Bloomington
(612) 835-6722
Data Electronics
Minneapolis
(612) 786-9666

MISSOURI
Technical Reps., Inc.
Hazelwood
(314) 731-5200

NEW JERSEY
Intel Corp.
Edison
(201) 985-9100

NEW MEXICO
BFA Corp.
Albuquerque
(505) 292-1212
BFA Corp.
Las Cruces
(505) 523-0543

NEW YORK
Intel Corp.
Hauppauge
(516) 231-3300
Intel Corp.
Rochester
(716) 328-7340
Intel Corp.
Poughkeepsie
(914) 473-2303
Measurement Tech., Inc.
Great Neck
(516) 482-3500
T-Squared, Inc.
Pittsford
(716) 381-2551
T-Squared, Inc.
Syracuse
(315) 463-8592

NORTH CAROLINA
Col-Ins-Co
Winston Salem
(919) 748-0297
Glen White Assoc.
Raleigh
(919) 787-7016

OHIO
Intel Corp.
Dayton
(513) 890-5350
Intel Corp.
Euclid
(216) 289-0101
Lowry and Assoc., Inc.
Cleveland
(216) 464-8113
Lowry and Assoc., Inc.
Dayton
(513) 435-4795

OREGON
ES/Chase Co.
Portland
(503) 620-9616

PENNSYLVANIA
Intel Corp.
Ft. Washington
(215) 542-9444
Lowry and Assoc., Inc.
Pittsburgh
(412) 922-5110
Q.E.D. Electronics, Inc.
Hatboro
(215) 674-9600

TENNESSEE
Glen White Assoc.
Germantown
(901) 754-0483
Glen White Assoc.
Johnson City
(615) 928-0184

TEXAS
Intel Corp.
Dallas
(214) 241-9521
Mycrosystems Mktg., Inc.
Austin
(512) 472-2492
Mycrosystems Mktg., Inc.
Dallas
(214) 238-7157
Mycrosystems Mktg., Inc.
Houston
(713) 783-2900

UTAH
BFA Corp.
Salt Lake City
(801) 466-6522

VIRGINIA
Glen White Assoc.
Lynchburg
(804) 384-6920

WASHINGTON
ES/Chase Co.
Seattle
(206) 762-4824

CANADA
Intel Semiconductor Corp. of Canada
Ottawa
(613) 232-8576
Multilek, Inc.
Ottawa
(613) 825-4553

EUROPEAN MARKETING HEADQUARTERS BELGIUM
Intel International
Brussels
Tel: (02) 660 30 10
Telex: 24814

ORIENT MARKETING HEADQUARTERS JAPAN
Tokyo
Tel: (03) 426-9261
Telex: 781-28426

26.6k bits/track; this format is not applicable in double density.

Transfer rates are 250k bits/s single density and 500k bits/s double. Average latency is 83 ms and head load time is 35 ms for both densities. Seek times are also the same for both: 10 ms track to track and 100 ms for 76 tracks. There is no settling time after speed.

For both densities rotational speed is 360 r/min, flux density is 6816 fc/in, and track density is 48/in. Recording densities are 3408 bits/in single density and 6816 bits/in double. Encoding methods are FM for single density, M^2FM for double.

Single-sided, soft-sectored media are IBM Diskette I or equivalent for both single density and ID or equivalent for double; single-sided, hard-sectored media are Dysan 101 or equivalent for single density and 101D or equivalent for double. Two-sided, soft-sectored media are IBM Diskette II or equivalent for single density, IID or equivalent for double; two-sided, hard-sectored are Dysan 101/2 or equivalent for single density, 101/2D or equivalent for double.

Environmental limits are 40 to 115°F (5 to 45°C) at 20 to 80% relative humidity. Ac power requirements at 50/60 Hz ±0.5 Hz are 90 to 127 V at 0.4 A typ or 180 to 253 V at 0.2 A typ; dc requirements are 24 V ±5%, 1.2 A typ; 5 V ±5%, 1.9 A typ; and −5 V ±5%, 0.15 A typ (option −7 to −16 V). The unit measures 4.38 x 8.72 x 15.00″ (11.13 x 22.15 x 38.1 cm) and weighs 22 lb (10 kg).

Reliability predictions include MTBF of 6000 h under typical usage, component life of 15,000 h, and media life of 3.5 x 10^6 passes/track and >30,000 insertions. Error rates are 1 per 10^9 bits soft read, 1 per 10^{12} bits hard read, and 1 per 10^6 seeks. MTTR is claimed to be 30 min.

Price and Delivery

Single unit price for the model 299 diskette drive without options is $1425. OEM discounts are available. Production deliveries will begin in February. PerSci, Inc, 12210 Nebraska Ave, West Los Angeles, CA 90025. Tel: (213) 820-3764.

For additional information circle 199 on inquiry card.

New from EECO!



LOW COST PUNCHED TAPE READER

EECO's 2001 Series Reader/Spoolers for Machine Control and Test Equipment applications...

- **Reads tape 200 cps**
- **High Speed Rewind**
- **Wide opening cover for easy tape loading**
- **Optoelectronic Read Circuitry**
- **A full line of Readers and Reader/Spoolers**

Send for literature on EECO's 2001 Series

The future in Tape Readers

EECO

1441 East Chestnut Avenue
Santa Ana, California 92701
(714) 835-6000

PRODUCTS



Smart Data Generator Offers Keyboard Entry and CRT Display in a Variety of Formats

Data generator features a hexadecimal keypad and scratch-pad memory that directs the integral CRT display in hexadecimal, octal, binary, and timing formats to show programming of 1024 serial bits or 64-word, 16-bit parallel channels as they are formulated for loading into a transmit memory. To test microprocessors, IC development, computer simulation, and related applications, the self-contained model 720 includes all data generation, display and interface electronics. In operation, the unit generates an algorithmic pattern to pinpoint faults in hardware and software. Output data rates to 20 MHz are generated internally or fed in from an external source. Choice of 1-bit, 1-word, start-stop bits, or continuous run at true pos and neg, TTL levels is offered. Options provide interface and handshaking with other systems and controllers. **Moxon, Inc,** 2222 Michelson Dr, Irvine, CA 92715.

Circle 200 on Inquiry Card

Desktop Multifunction Workstation Is Integrated Microcomputer Terminal System

Benchmark results for the Microterm II Z80 microcomputer-based CRT terminal workstation, designed to measure efficiency of the BASIC interpreter in conjunction with the systems architecture, and to test the speed of completing large numbers of memory accesses and arithmetic speed of the processor, were superior to those of 21 other microcomputers. Designed around two 4-MHz Z80s with up to 48k bytes of RAM storage, the system features minimized access and wait times and can handle simultaneous functions. The desktop unit has a 24 x 80-char, 12″ (30-cm) CRT; 2200-char/s nonimpact printer; and single or dual minidiskettes. Internal and external printers, dual diskettes, and memory expansion beyond 16k bytes are optional. Applications software to run with the interactive disc operating system can be programmed in extended BASIC or Z80 assembly language and debugged from the keyboard. **Digi-Log Systems, Inc,** Babylon Rd, Horsham, PA 19044.

Circle 201 on Inquiry Card

Complete 12-Bit Data Acquisition Systems Are Fabricated With Thin-Film Hybrid Technology



Circle 202 on Inquiry Card

Complex hybrid data acquisition systems are available with 16-channel single-ended (HDAS-16) or 8-channel differential (HDAS-8) inputs. Featuring a throughput rate of 50-kHz at 12 bits resolution, the devices incorporate a CMOS multiplexer, programmable gain instrumentation amplifier for gains of 1 to 1k, sample-hold, 12-bit A-D converter, 10-V buffered reference, address register, and digital control logic in a 2.3 x 1.4 x 0.24″ (58.4 x 35.6 x 6.1-mm) 62-pin package. Performance equals that of larger, modular systems. Specs include 100-MΩ resistance, 200-pA max input bias current, and 10-μV/°C X gain offset drift. Acquisition and conversion times are 9 μs. Three modes of operation are free-running sequential, triggered sequential, and random addressing. A hermetically sealed, full military temp range model, operating over −55 to 125°C, is available. **Datel Systems, Inc,** 1020 Turnpike St, Canton, MA 02021.

HP9830A/B and Infotek...

If you use the HP9830A/B, you know that it has great potential.

Now you can extract the full measure of 9830 capabilities with Infotek's Memory, ROMs and Peripherals.

Memory. The EM-30, 32,192 byte memory for the '30, pioneered by Infotek, is one of the most significant contributions to increasing the '30's power.

EM-30B, in conjunction with Infotek's Mass Memory II ROM multiplies the speed of the 9880B Mass Memory System by avoiding redundant disc operations. A must for the 9880B user!

Fast Basic ROMs. The Fast Basic ROM series provides 54 statements, functions and commands. With these ROMs your '30 acquires versatility and speed superior to any other desk top computer. Here's just a few examples of Fast Basic Power.

*** Dimension arrays any size you like. Sort or search any array that will fit in your memory!**

- Move information in or out at 10K bytes per second . . . fabulous for instrumentation and control applications.
- Interrogate and amend variables without halting the program, just like a live keyboard.
- Suspend any program including mass memory operations to cassette or floppy for future completion.
- Interrupt capability — a peripheral can now demand service, branch or initiate program execution.
- Edit program test and super-secure both program and data files.

If this is the kind of added capability that you can use in your '30 then read on, there's more!

The FD-30 Series Floppy Discs. Each of the FD-30s stores 305K bytes. Organize this information any way you like up to 2387 files. Best of all, you can talk to the FD-30s without any software changes because the FD-30 series obeys *every* 9830 cassette instruction.

The series consists of the FD-30A single disc unit, FD-30S slave drive, FD-30M multiple disc drive which contains a master and up to three slave drives, and the FD-30SR slave drive system which will accommodate one to four drives.

A single master will support up to seven slaves and only one I/O slot is used.

Peripherals. Infotek has applied the same level of ingenuity reflected in the ROMs and floppys to the development of extremely high quality and reliable peripherals tailored to the needs of the 9830A/B. Now available are:

- LP-30, a 200 line per minute matrix printer
- CP-30, a 45 character per second character printer/plotter
- PS-30, a paper tape punch/reader
- TC-30 and RT-30 time clocks
- RS-30, a 9600 BAUD RS 232-C interface with 7 quartz reference rates.
- FI-30, a 10K byte/sec TTL I/O

Contact us now for the name of your local Infotek representative. Discover why more than a thousand 9830 users working with Infotek enhancements believe that the 9830 and Infotek are made for each other.

World-wide service and distribution centers back up Infotek's liberal warranty and service commitment.

At Infotek we're dedicated to making good computers better.

Infotek Systems

1400 NORTH BAXTER STREET • ANAHEIM, CALIFORNIA 92806 • (714) 956-9300 • TWX 910-591-2711

The 9830A/B is a product of Hewlett-Packard Company.

CIRCLE 82 ON INQUIRY CARD



Introducing "THE MIXER"*

There are a lot of packaging systems around. We're introducing another one, but it won't add to the confusion because there simply isn't another system that offers the designer the flexibility of design options as "The Mixer".

Modular Flexibility

You can now subdivide your logic system or new microprocessor system with no restrictions on functional size. Boards or panels with IC capacities of 60, 108, 120 up to 192 may be mixed in the same rack assembly. Panels with 8, 14, 16, 18, 22, 24, 28, 40, 42 IC sockets exist in all sizes.

Voltage Supply Requirements

Panels in all sizes have one, two or three voltage planes for distribution of multiple voltage IC requirements. Connector backplanes containing committed or uncommitted multiple voltage planes complement the variety of panels.

Analog/Digital Separation

Three independent backplanes permit the modular separation of analog and digital grounds and voltage supply requirements for greater noise immunity.

Input-Output

All panels have high I/O pin count to IC count ratios. Panels contain from 108 to 540 input-output pins so that the system may be subdivided or functionalized without restrictions of I/O pin limitations.

*Product of the Year Award
Electronic Products Magazine

MUPAC®

"The Innovative Name in Microelectronic Packaging Systems"

**For Additional Brochures on Related Products write to:
646 SUMMER ST. • BROCKTON, MASS. 02402 • TEL. (617) 588-6110**

PRODUCTS

FLEXIBLE DISC SYSTEM



An integrated hardware/software unit, disc system connects directly to the PDP-11 Unibus; software modules allow it to operate in an RT-11 environment, using either std DEC RX-01 26-sector format or a 16-sector format which increases storage capacity by 25%. Up to four flexible disc drives can be included in the -11 installation. A single rackmounted unit contains controller/formatter circuitry, power supply, disc storage bin, and space for two drives. **Ex-Cell-O Corp, Remex Div,** 1733 Alton St, PO Box C-19533, Irvine, CA 92713.
Circle 203 on Inquiry Card

S-100 BUS-COMPATIBLE LOGIC ANALYZER BOARD



Specifically designed to support troubleshooting on the S-100 bus, the model 150 Bus Grabber can monitor, analyze, and display the 16-bit address bus; 8-bit data bus; and MPU control, status, and interrupts without disassembly of the computer. 56 bus signals are monitored simply by plugging the PC board into any available computer slot. Eight additional user-defined signals are available for monitoring other points or ICs inside the computer. **Paratronics, Inc,** 800 Charcot Ave, San Jose, CA 95131.
Circle 204 on Inquiry Card

COLOR GRAPHICS TERMINAL

An intelligent color graphics terminal uses a permanently converged CRT, optimized for digital color displays. Configured as a standalone terminal or rackmount unit with detached keyboard, it features std ASCII alphanumerics, bar graphics, reverse video, blink, and up to 800 special symbol graphics, 512 of which are microprogrammable. Individual foreground/background selection in any of eight colors is made on a char-by-char basis. **Industrial Data Terminals Corp,** 1550 W Henderson Rd, Columbus, OH 43220.
Circle 205 on Inquiry Card

CIRCLE 152 ON INQUIRY CARD

When we installed our first minicomputer disk system, we talked a lot about RELIABILITY.

4000 systems later, our customers tell the story.

Reliability. We do more than just talk about it. We deliver it. That's one of the main reasons we're now the world's largest independent supplier of minicomputer disk storage systems.

We've delivered more than 4,000 systems since we installed our first one in 1971. That's strong evidence of hardware reliability and product acceptance.

There's a lot more to the story. Behind our reliable hardware is a reliable company that keeps delivery commitments, provides total software support and responds quickly to customer service requirements. Ask our customers.

We make good disk drives work better through *Extended Emulation*.™ This powerful approach adapts software to emulate the CPU manufacturer's operating systems—while still taking full advantage of the unmatched performance offered by our disk system. Whether you need disk storage for mini or micro, you need to know about the important benefits *Extended Emulation* can provide.

The diverse applications for our disk systems are regularly described in our quarterly newsletter, *The Bit*. If you'd like to be on our complimentary mailing list, use the coupon today. We'll send you the current issue. And if you need product data, or help with a specific application, contact the System Industries sales/service office nearest you.

System Industries

an equal opportunity employer

525 Oakmead Parkway
P.O. Box 9025
Sunnyvale, California 94086
(408) 732-1650, Telex: 346-459

☐ **Please add my name to your mailing list for *The Bit*. Send product data on the follow disk systems:**

☐ **2.5 MBytes** ☐ **10 MBytes** ☐ **300 MBytes**

Name _____ Position _____

Company _____

Address _____

City _____ State _____ Zip _____

☐ My need is urgent. Have an applications specialist phone me today: (_____) _____ ext. _____

Sales/Service Offices:
Boston: (617) 492-1791. **New York:** (201) 461-3242; (201) 694-3334; (516) 751-8686; (716) 385-3021.
Washington, D.C.: (202) 337-1160. **Cincinnati:** (513) 661-9156. **Los Angeles:** (714) 752-8904.
Houston: (713) 465-2700. **Atlanta:** (404) 491-0161. **Sunnyvale HQ:** (408) 732-1650.
Germany, Dusseldorf: 0211-400606. **Sweden, Stockholm:** 08-236-640.
United Kingdom, Woking: (4862) 70725.

CIRCLE 84 ON INQUIRY CARD

Canon

Camera Quality in d.c. Motors for Computer Peripherals



You probably know us for our line of fine cameras. But did you know that we are also one of the world's largest manufacturers of subfractional h.p. (below 1/50) permanent magnet d.c. motors?

We produce a very broad line of high quality motors equally as respected among OEM users as our cameras are in their field.

Our line includes

- **Diameters from 22 to 38 mm**
- **Stall torques to 35 oz.-in.**
- **Tachometers, a.c. and d.c.**
- **Gearheads**

If you need a reliable source for subfractional h.p. d.c. motors noted for reliability and long life, call Canon. We probably have a model to fit your need and certainly can respond quickly to meet a custom requirement.

Send for FREE catalog. In a hurry? Call 516-488-6700 and ask for Electronic Components Division.

Canon® U.S.A., Inc.

Electronics Components Div.
10 Nevada Drive,
Lake Success, L.I., N.Y. 11040

516/488-6700
Telex No. 96-1333
Cable—Canon USA LAKS

CIRCLE 85 ON INQUIRY CARD

PRODUCTS

STANDALONE PAPER TAPE READER



Having greater capacity than earlier models, model 612 has the ability to read 5- to 8-level tape and transmit 7 to 11 frames/char at 50 to 9600 baud. The standalone paper tape reader also features starting and stopping on char at all speeds; choice of manual control or X-on, X-off; 90- to 260-V, 50- to 60-Hz power; and even, odd, or no parity. RS-232, current loop, or parallel outputs are available. **Addmaster Corp,** 416 Junipero Serra Dr, San Gabriel, CA 91776.

Circle 206 on Inquiry Card

SELECTOR CHANNEL EMULATION UNIT

High performance IBM (or IBM plug-compatible) peripheral devices attach to a medium-scale minicomputer system with the SCEU emulation unit for increased performance. Unit generates protocol sequences required by the IBM PCU in response to operational commands of the minicomputer CPU. It also converts IBM selector channel's 8-bit data path into 16- or 32-bit word-path size for host CPU. Up to 255 device control units are supported at combined data transmission rates of >2.4M bytes/s. **Information Products Systems, Inc,** 6565 Rookin, Houston, TX 77074.

Circle 207 on Inquiry Card

PRESSURE-SENSITIVE POSITION SENSOR

A finger, ballpoint pen, or similar stylus can be used to select or determine positions on an underlying image with the E270 transparent position sensor which is a plate glass substrate coated with semiconductive metal oxide. An electrically isolated plastic cover sheet with a transparent conductive coating is placed over the substrate. Pressure applied to the cover sheet makes contact between the two. X and Y coordinates are converted from analog to digital by an ADC. **Elographics, Inc,** 1976 Oak Ridge Tpk, Oak Ridge, TN 37830.

Circle 208 on Inquiry Card

AT UNDER $2000, THE MODEL 40 OEM PRINTER NOT ONLY COSTS LESS TO BUY–IT ALSO COSTS LESS TO OWN.



It costs less to buy because for less than $2000 you get a 300 lpm printer that's completely operational. All you furnish are 115 VAC and the serial signal source.

Once on-line, our model 40 OEM printer costs less to own. Not only is it highly reliable, it requires little maintenance.

Even when maintenance is needed, the MTTR averages only ¾ hour, thanks to built-in diagnostics that help pinpoint trouble quickly. And with only seven modular mechanical assemblies and one CMOS logic card, repairs are simple.



This modularity and diagnostic capability also cut the cost of training service personnel.

To reduce your logistics problems and spare parts inventory, there's an 80% parts commonality between all model 40 printers. Plus Teletype offers an exchange repair service that can save you up to 50%.

For more information about our model 40 OEM printers, send in the coupon. Or call 312/982-2000.

THE TELETYPE® MODEL 40 OEM PRINTER. NOTHING EVEN COMES CLOSE.

TELETYPE®

Teletype
Corporation
Dept. 71-0
5555 Touhy Ave.
Skokie, IL 60076

Please send me additional information about the model 40 OEM printers.

Name_____

Title_____

Company_____

Address_____ Phone_____

City_____ State_____ Zip_____

Teletype is a trademark and service mark registered in the United States Patent and Trademark Office.

CIRCLE 86 ON INQUIRY CARD

BOEING

CAD/CAM Specialists

The Boeing Company in Seattle, Washington is seeking CAD/CAM specialists to support the development and operation of sophisticated industrial computing applications in an interactive graphics/distributed network systems architecture. Experienced CAD/CAM specialists are needed in the following areas:

- **Scientific Data Base and DBMS Design**
- **Engineering/Manufacturing Data Base Administration**
- **Systems Architecture and Communications Networking**
- **Distributed Computing Systems Specification and Development**
- **2-D and 3-D Interactive Graphics System Development**
- **Systems Configuration Control Management**
- **CAD/CAM Systems Operation and Support**
- **Systems Testing and Certification**
- **Geometric Systems Research and Development**
- **Master Dimensions (Lofting) Systems Development and Support**
- **Advanced Numerical Control Methods**
- **Engineering Technology Systems and Applications Programming**
- **CAD Systems Development Management**

Candidates must have a BS degree or higher in Engineering, Computer Science or Mathematics and a minimum of three years experience in the development or application of scientific computing systems.

Attractive salary, fringe benefits and moving allowances will be offered selected candidates. And, living is a pleasure in the unspoiled Northwest with its many recreational and sports activities and relaxed life-styles.

Send your résumé to The Boeing Company, P.O. Box 3707-BKL, Seattle, WA 98124.

An equal opportunity employer.

BOEING

Getting people together

PRODUCTS

RS-232 TO CURRENT LOOP/ TTL ADAPTER

ADApter has two circuits—one converts RS-232 signal to a 20-mA current loop signal, and the other converts 20-mA current loop signal to RS-232 signal. Device permits teletypewriter ports to be used to drive an RS-232 terminal, or vice versa, without modification of the port; it can also be paralleled to drive a teleprinter or RS-232 printer while using the computer's regular terminal. Device does not alter baud rate and uses std power supplies with low current requirements. **Connecticut Microcomputer,** Pocono Rd, Brookfield, CT 06804.

Circle 209 on Inquiry Card

FLOPPY DISC DRIVE POWER SUPPLIES



Open frame power supplies designed for ac-powered floppy disc drives include the 2BXFD, which is aimed at systems incorporating the Shugart Mini Floppy (or equivalent) drive; 2PFD and 2QXFD supplies are intended to operate single and dual floppy disc drives. All outputs are adjustable and regulated to ±0.15% for line or load variations with 10-mV pk-pk ripple except for the two low power (0.5/0.6 A) 5-V outputs that have a total tolerance of ±3%. **Alpha Power, Inc,** 20536 Plummer St, Chatsworth, CA 91311.

Circle 210 on Inquiry Card

MICROHYBRID 2-QUADRANT DIVIDERS

A transconductance dividing element, stable reference, output amp with specified accuracy internally trimmed for feedthrough output zero and gain trim comprise the 500 series of microhybrid dividers. For microprocessor-based systems, 503 through 506 divide in two quadrants with a transfer function of −10X/Y. For 0 to 70°C operation, they are specified for dividing errors of 1, 0.5, 0.25, and 0.10% at 25°C. Output provides ±10 V at 5 mA, and is short-circuit protected. **SGR Corp,** Neponset Valley Industrial Pk, PO Box 391, Canton, MA 02021.

Circle 211 on Inquiry Card

EMERGENCY/EMERGENCY/FIRE IN TANK NUMBER FOUR...PRESSURE DROPPING/CLOSE VALVE ONE FOUR/REPEAT/CLOSE VALVE ONE FOUR... BLOOD PRESSURE UP, ROOM TWO ONE TWO...

At work around the clock...around the world... MSC's Solid-State Programmable Voice Readout System Model 1650 is preventing accidents, saving lives, conserving time, energy and natural resources.

We've made tape systems obsolete! The Model 1650 has no moving parts. No tapes to replace. No wasted time "accessing" the message, because it ALWAYS starts at the "beginning" of the message you want, all the time, everytime! All this at tape system prices.

With the Model 1650, MSC did what couldn't be done. We combined natural quality reproduction of the human voice with solid-state reliability. This unique system uses solid state integrated circuits for its storage base. Programmable Read Only Memories (PROMS) allow MSC to provide customer-specified words to achieve the desired vocabulary without incurring special set-up charges.

The modular design of the MSC Model 1650 accommodates 14 plug-in circuit boards to expand the required vocabulary up to 192 words in the standard 1/2 ATR rack. Each additional circuit board used expands the vocabulary another 16 words.

Applications are virtually unlimited. This binary addressable solid-state voice readout system, with power-saving CMOS circuitry, is currently used in critical applications throughout the world... in hospitals to alert doctors and nurses to patients' needs...as warning systems in aircraft...refineries... chemical plants...and in telecommunication and information systems of every kind.

In short, if you need audible operator alert or information, the MSC Model 1650 provides the only alternative to mechanical tape systems at practically the same cost with far greater reliability.

So why not let MSC's Model 1650 have a voice in your operation?



MSC

Worth Switching To

Master Specialties Company, 1640 Monrovia Ave., Costa Mesa, CA 92627 · Telephone (714) 642-2427

CIRCLE 88 ON INQUIRY CARD

LARGE LED ALPHANUMERIC DISPLAY



For use in illuminated displays, the "Datablox" alphanumeric LED matrix display provides alphanumeric digits 4 x 3" (10 x 7.6 cm) and uses 35 (5 x 7 matrix) high intensity LEDs mounted in individual reflectors. With wide angle viewing, digits can be read at distances of 200 ft (61 m) in normal office lighting conditions. Features include low power, long life, and ruggedness. Compatible with solid-state drive, they can generate the full 64-char ASCII set. **Chicago Miniature Lamp Works, General Instrument Corp,** 4433 N Ravenswood Ave, Chicago, IL 60640.
Circle 212 on Inquiry Card

10-CHANNEL RTD SCANNER

A modular scanner in a card-mounted, shielded package, the SL115 connects 10 platinum resistance thermometers directly to a user's high level A-D converter, and excites, lead compensates, continuity tests, linearizes, amplifies, and filters the signals. Remote calibration features give online calibration of the scanner at the ice point. Control logic is DTL/TTL/CMOS-compatible. The unit gives output sensitivities from 1 to 100 mV/°C. **San Diego Instrument Laboratory,** 7968 Engineer Rd, San Diego, CA 92111.



Circle 213 on Inquiry Card

IMPACT DOT MATRIX PRINTER



As a standalone unit, the model SP-302 5 x 7 impact dot matrix, 40-col intelligent printer features a microprocessor controller that allows double width printing and double and triple space format; tab functions are also std for simple software control from a host device or computer. Unit prints 50 char/s and has multiple copy capability. Inputs include RS-232 and a 20-mA current loop. Input baud rate of 110 is std; other rates can be internally set. **Syntest Corp,** 169 Millham St, Marlboro, MA 01752.
Circle 214 on Inquiry Card

Need a DEC Floppy System?

MF-11



The MicroFlop-11 is Your PDP-11V03 . . . in Half the Space . . . and at Half the Price.

Functionally identical to the PDP-11V03, and using only 10-1/2" rack space, the MF-11 houses the Shugart dual floppy system, the backplane for the LSI-11 with associated peripherals, and all needed power . . . at considerable dollar savings.

- Compact Version of PDP-11V03
- Totally Software Compatible
- RT-11 • Fortran IV • Basic
- Bootstrap Loader
- Optional Double Sided Drive
- Optional Extended Backplane
- 3740 Format

UNIT PRICE
$3440.00

$4290.00
with LSI-11

FD-11



Our FD-11 Dual Floppy System Does Everything DEC's RX-11 Will Do . . . and a Few Things More . . for a Lot Less.

FD-11 Dual Floppy Disk system with its Controller/interface card offers you total software, hardware and media compatibility for all DEC PDP-11 and LSI-11 systems . . . and in addition:

- Over 35% Price Savings
- 8080 Based Controller
- Industry Standard Drives
- Write Protect Switches
- Unit Select Switches
- Bootstrap Loader
- Formatter and Self-test Routine
- Optional Double Sided Drives

UNIT PRICE
$2750.00

For more details and pricing, contact: Marketing Department
CRDS Charles River Data Systems, Inc., 235 Bear Hill Rd., Waltham, MA 02154,
Tel. (617) 890-1700

FOR MF-11, CIRCLE 89

FOR FD-11, CIRCLE 90

The CRT terminal for the systems designer

You can change it to fit your system—instead of vice versa.

New microtechnology, new systems, new applications. It's all changing quickly. Our challenge: design a CRT terminal flexible enough to keep up with your ideas —one to help you make the most of your latest system, not compromise it.

The 480/25 is the result.

Need an intelligent CRT terminal?

O.K. The 480/25 is an addressable/pollable intelligent CRT terminal that can accommodate a variety of protocols. It offers local editing, protected field formats, block transmission, and more.

It can save time; no time-fill characters needed, even at 9600 bits per second.

It offers cursor positioning by—and reporting to—the host computer. And, of course, it can store forms locally and automatically check formats.

Need a cluster controller or a microcomputer?

Fine. One 480/25 can control a series of terminals and also communicate with a host computer. Or, you can add a disc, a printer, and expanded memory to a 480/25—and you've created a true microcomputer with integrated CRT and keyboard.

Etc., etc., etc.

The fact is, combine your software and the right peripherals and you can have 480/25 doing all kinds of handsprings for you. So instead of clamping a lid on your system, it can spring loose some great ideas.

Get the details.

It's easy, just ask.
Call (213) 966-3511. Or write.
CONRAC, 600 N. Rimsdale Avenue,
Covina, CA 91722

CONRAC

PRODUCTS

PROCESS CONTROL SYSTEM



A flexible, microprocessor-based system, which includes a complete software package for supporting up to 16 control loops and 16 additional inputs with alarm limits, controls such parameters as temp, pressure, and flow rate, and provides monitoring and control of variable high or low analog conditions. System interfaces easily to peripherals such as CRT terminals, printers, and floppy disc drives. Programming is done in BASIC with some subroutines written in assembly language. **Digitek, Inc,** 5950 6th Ave, S Suite 101, Seattle, WA 98108.
Circle 215 on Inquiry Card

PROCESS MINICOMPUTER SYSTEM PERIPHERALS AND CPUs

A wide range of products for the 300 process computer systems include five peripherals and three CPUs based on the 330 model. The 330-R10, R20, and R30 minicomputers and the 340-R40 multiprocessor system are CPU units whose quantitative specs vary. They have identical instruction set, including bit, byte, field, 32-bit fixed-point and 64-bit floating-point instructions; powerful autonomous I/O processors; and same interface structure for peripherals. **Siemens AG,** Postfach 3240, D-8520 Erlangen 2, Federal Republic of Germany.
Circle 216 on Inquiry Card

AC LINE REGULATOR

OEM-3150 line regulators use the company's patented multiprimary switching regulator circuit which operates at 99% efficiency and generates no noise or distortion. Response time for worst case, complete correction is 0.5 cycle, and regulators are insensitive to frequency and power factor changes. The package has been optimized for easy installation. Dimensions are 4.5 x 4.8 x 8″ (11.4 x 12.1 x 20.3 cm) and a 1.5-kVA regulator weighs 12 lb (5.4 kg). **Power-Matic, Inc,** 8076 Engineer Rd, San Diego, CA 92111.
Circle 217 on Inquiry Card

PHOTOELECTRIC SCANNER

A solid-state chip for self-contained reflective scanning combines miniaturized LED and phototransistor elements in a 0.375″ (0.95-cm) diam unit. Operating with the company's "M" series modulated amps, LP-400 has a 0.5 to 3″ (1.3 to 7.6-cm) adjustable range to detect objects as small as 0.010″ (0.025 cm) in diam. Response time is 1 ms. Due to wide field of view and adjustable amp sensitivity, it is easy to set up and keep aligned. **Banner Engineering Corp,** 9714 10th Ave N, Minneapolis, MN 55441.
Circle 218 on Inquiry Card

0.5″ PLANAR GAS DISCHARGE DISPLAY

Accommodating up to 16 char in a package measuring 1.55 x 8.90″ (39.4 x 226.1 mm), SP-451 is based on 14-segment design. Messages consist of numerals, letters, and special symbols to satisfy POS and instrumentation displays. Character size, variety, brightness, and 130-deg viewing angle provide readability in bright, dark, or otherwise difficult conditions. Designed for edgeboard mounting, the display requires only 0.8″ (2.0 cm) mounting depth, including tubulation. **Beckman Instruments, Inc,** 2500 Harbor Blvd, Box 3100, Fullerton, CA 92634.
Circle 219 on Inquiry Card

Two New Refreshing Alternatives

MEGRAPHIC 5000 & 7000 SERIES







Dollar For Dollar, The Best Performing, Most Powerful, Intelligent Graphics Systems

DYNAMIC REFRESH

All MEGRAPHIC Systems feature 100% vector refresh. Sharp, bright lines with 12 bits of screen resolution. Individual vectors or symbols can be erased, translated, rotated, or scaled in real-time. No need to blank the entire screen to change one, one hundred, one thousand, ten thousand, or more points!

Local minicomputer power eliminates the host or minimizes its support requirements.

TEKTRONIX®* COMPATIBLE

Our 5014 emulates all Tektronix® 4010/4014™ Series storage terminals. MEGATEK's EDS™ adds powerful local edit capabilities, not available on a storage tube.

Easy to use, easy to pay for. Flexible, cost effective systems, backed by MEGATEK engineering and software support. PDP-11, DATA GENERAL, and OEM interfaces available. We listen to your problems and solve them with quality products.

MEGATEK CORPORATION
The Refreshing Alternative™

1055 Shafter Street
San Diego, California 92106 (714) 224-2721

*"TEKTRONIX" is a registered trademark of Tektronix, Inc., use of which in no way constitutes endorsement.

10 nsec. $69.95

Meet CSC's LP-3. The multi-family logic probe that's as fast as a high-speed memory scope. At about 1/100th the price.

You won't want to be without this compact, enormously versatile test and troubleshooting tool that does the work of a level detector, pulse detector, pulse stretcher and memory probe. It gives you instant, positive indications of circuit conditions—capturing one-shot and low-rep-rate pulses (down to 10nsec) that are barely visible, even on a fast scope.

Easy to use. No sync, polarity or circuit loading to worry about: just set a switch to the proper logic family, connect two clip leads to the circuit's supply and touch the probe tip to the node under test. You get an instant picture of circuit conditions: Separate LED's indicate logic "1", logic "0" and all pulse transitions. To store single-shot and low-rep-rate pulses, simply set the PULSE/MEMORY switch to MEMORY.

At $69.95, LP-3 simplifies testing, debugging and servicing all types of digital circuits, with pulses as fast as 10nsec. See your CSC dealer today. Or call 203-624-3103 (East Coast) or 415-421-8872 (West Coast) for the name of your local stocking distributor and a full-line catalog.

Logic Family Switch—TTL/DTL or CMOS matches Logic "1" and "0" levels; CMOS position also compatible with HTL, HiNIL and MOS logic.

PULSE/MEMORY Switch & LED—PULSE position detects and stretches pulses as narrow as 10 nanoseconds to 1/10 sec.; MEMORY stores single-shot and low-rep-rate events indefinitely; HI/LO LED's remain active.

HI/LO LED's—Display level (HI-logic "1", LO-logic "0") of signal activity.

Interchangeable probe tips—Straight tip supplied; optional alligator clip and insulated quick-connecting clip available. Optional input ground lead.

Plug-in leads—24" supplied, with alligator clips. Virtually any length leads may be connected via phono jack.

*Manufacturer's Recommended Resale

© 1977 Continental Specialties Corp.

Specifications

Input impedance 500,000Ω

Thresholds (switch selectable)	**DTL/TTL**	**HTL/CMOS**
logic 1 thresholds (HI-LED)	2.25V ± .10V	70% Vcc ± 10%
logic 0 thresholds (LO-LED)	0.80V ± .05V	30% Vcc ± 10%

Min. detectable pulse width 10nsec. guaranteed

Pulse detector (PULSE LED) in PULSE position of PULSE/MEMORY switch, 1/10-sec. pulse stretcher makes high-speed pulse train or single events (+ or − transitions) visible; in MEMORY position, first transition lights and latches LED

Operating temperature 0-50°C

Physical size (l x w x d)
5.8 x 1.0 x 0.7" (147 x 25.4 x 17.8mm)

Weight 3oz. (.085Kg)

Power leads removable 24" (610mm) with color-coded insulated clips; others available

Input protection overload, ±25V continuous; 117 VAC for less than 10 sec.; reverse polarity, 50V



CONTINENTAL SPECIALTIES CORPORATION

44 Kendall Street, Box 1942, New Haven, CT 06509
203-624-3103 TWX 710-465-1227
West Coast: 351 California St., San Francisco, CA 94104
415-421-8872 TWX 910-372-7992
Great Britain: CSC UK LTD
Spur Road, North Feltham Trading Estate,
Feltham, Middlesex, England
01-890-8782 Int'l Telex: 851-881-3669

CIRCLE 93 ON INQUIRY CARD

NEW LP-3!

PRODUCTS

MULTIPOINT, NONCONTACT GAUGING SYSTEM



Electronically scanning production parts and instantly displaying their critical dimensions, the microprocessor-based speedgage system reduces time and cost. A part is scanned in <2.5 s by an array of up to 240 noncontact capacitive-type sensing probes, and compared with dimensions stored in an internal memory. Errors then appear as a step trace on the CRT screen. Nine push-button-selected vertical sensitivities range from 20 μin (0.5μm)/div to 10,000 μin (250μm)/div. **Gould Inc, Instrument Systems Div,** 3631 Perkins Ave, Cleveland, OH 44114.
Circle 220 on Inquiry Card

SINGLE STATION PC SWITCH

Designed to provide a gating function on a PC board, stackable design for multifunction switching features a low 0.028" (0.07-cm) profile, large, sturdy lever wheel for positive wiping action, and large, easily read characters. Housing is black thermoplastic polyester, 30% glass-filled. Base is black, type 6/6 nylon, 30% glass-filled. Mechanical performance is rated at 2000 switching operations for each spst station; electrical performance is rated 50 Vdc at 100 mA, nonswitching. **Stanford Applied Engineering, Inc,** 340 Martin Ave, Santa Clara, CA 95050.
Circle 221 on Inquiry Card

RAM BOARD IN SEMIKIT FORM

Offered fully assembled and wave soldered with pretested ICs, semikit memory modules eliminate common kit-building problems such as bad solder joints, heat damaged components, and faulty ICs. Features of the 16KRA include a 16,384-byte memory, invisible refresh, and worst-case access time of 400 ns. Each 4096-word block is independently addressable for max system flexibility. Power is typ 5 W; backup power connection is built-in. **Processor Technology Corp,** 6200 Hollis St, Emeryville, CA 98608.
Circle 222 on Inquiry Card

MINICOMPUTER EXTENDED MEMORY UNIT

A solid-state, plug replacement unit for DEC RF/RS-11, the EMU™ requires 2.1-μs access time to set up control registers and initiate transfer of information to and from main memory. Information is transferred at a 1-μs data rate. Design utilizes interchangeable memory modules, each consisting of 64k x 9 bits of 16k RAM. Dual port UNIBUS® interface allows access by two processors and incorporates card interchangeability. **Monolithic Systems Corp,** 14 Inverness Dr, Englewood, CO 80110.
Circle 223 on Inquiry Card

WIREWRAP PCBs

For users who want to build their own LSI-11 type I/O and memory systems, board, uncommitted and designed for insertion of wirewrap pins, accommodates approx 130 std 14- and 16-pin DIPs, plus necessary passive components. Featuring ±12 V on ground, board is fully grounded on one side with grounded shield at circuit size. Half-size version (WW-11.5) measures 5.255 x 8.4" (13.272 x 21.3 cm), while full-size version (WW-11) measures 10.450 x 8.4" (26.54 x 21.3 cm). **Artec Electronics, Inc,** 605 Old County Rd, San Carlos, CA 94070.
Circle 224 on Inquiry Card

MDB SYSTEMS presents...The Printer Connection

From DEC's PDP-11 & 8*, Data General NOVA*, Interdata and Hewlett Packard 21MX Computers, Plus the DEC LSI-11 Microcomputer to these popular model Line Printers:

DEC LA 180 · Centronics · Data Printer · Data Products · Data 100 · Mohawk · Printronix · Tally

New! **Diablo 2300 Series**



- ☐ Low-cost line printer controllers
- ☐ Completely software transparent to host computers
- ☐ Runs host computer diagnostics

MDB Systems controllers provide user flexibility in line printer selection with no change in host system software. Just plug-in the MDB module and connect your line printer. Each controller is a single printed circuit board requiring one chassis slot. Fifteen foot cable length standard.

Transparent to the host computer, the controller is completely compatible with diagnostics, drivers and operating systems. Operation and programming considerations are exactly as described by the host computer manufacturer.

More than three dozen computer-to-printer controller combinations are available from MDB Systems as well as modules for other compatible parallel interface printers.

A long-line parallel operation option is available for most printers permitting full speed operation up to 3000 feet.

MDB Systems has an extensive repertoire of general purpose logic modules, device controllers and accessories for the computers listed. Your inquiry will receive a prompt response.

MDB
MDB SYSTEMS, INC.
1995 N. Batavia St., Orange, California 92665
714/998-6900 TWX: 910-593-1339
*TMs Digital Equipment Corp. & Data General Corp.

"See us at Mini/Micro, Anaheim."
CIRCLE 94 FOR DEC; 95 FOR NOVA; 96 FOR INTERDATA; 97 FOR LSI-11; 156 FOR HP.

If you're this kind of systems OEM,

You're building complex turnkey projects.

You need more than "iron".

You know that your best buy is not a mixed bag of bottom-priced components, but a proved system, with all essential support, from a supplier who becomes your working partner.

we're your kind of computer systems source.

We're different. Instead of selling you black boxes, we supply complete computer systems. We've been doing this for seven years.

We have a state-of-the-art line of standard processors, memories, I/O devices, terminals and other peripherals. Plus proved system operating software that speeds your application programming. Advanced network and transaction software. And we'll quote special hardware and software where needed.

You'll like our systems engineering help, because we understand system problems. And we don't love you and leave you, but supply full support — field service, documentation, personnel training, even sales support.

What you get from MODCOMP is a fully checked-out system, factory burned-in, ready to bring on-line quickly and efficiently.

Get the full MODCOMP OEM story, by asking for the brochure, "Power Tools For Building OEM Systems". Modular Computer Systems Inc., 1650 W. McNab Road, Fort Lauderdale, Fla. 33309. (305) 974-1380.

MODCOMP

The systems store.

European Headquarters:
Export House, Woking,
Surrey, England
Phone: (04862) 71471

CIRCLE 98 ON INQUIRY CARD

Two Modcomp IV and four Modcomp II processors are the center of a new digital traffic control system for the city of Baltimore, engineered by TRW Inc. The TRW system has the capacity to control signals at 1200 key intersections in the city, and also provide surveillance of a five-mile section of the Jones Falls Expressway.

PRODUCTS

MODULAR OPTICAL ENCODER



Model 720 is a kit that consists of easily installed photohead and disc assembly. It provides a means of sensing rotary speed or angular position in applications where space is at a premium and little inertia and no additional torque can be added to the system. Features include solid-state LED sources, phototransistor sensors, optical quality glass commutator disc, and direct DTL, TTL, CMOS, and discrete component compatibility. Std resolutions range from 24 through 2540 cycles. Voltage options are 5, 12, 15, and 24 V. **Litton Systems, Inc, Encoder Div,** 20745 Nordhoff St, Chatsworth, CA 91311.

Circle 225 on Inquiry Card

DOT MATRIX IMPACT PRINTER



Ready-to-use, tabletop dot matrix impact printer for mini or microcomputer systems prints up to 120 char/s with 80 to 132 char/line. Features include an RS-232 and current loop serial interface and enhanced mode (double width) char. Multiple copy capability on both fanfold and roll paper is std. Serial baud rates of 110 to 1200 bits/s are selectable; parallel interface capability is also provided. A 5 x 7 dot matrix is used to print std 64-char ASCII set. **Integral Data Systems, Inc,** 5 Bridge St, Watertown, MA 02172.

Circle 226 on Inquiry Card

SC/MP BIPOLAR p/ROM CARD

Designed to be bus- and card-size compatible with the National ISP or the company's PDC family of cards, PDC-311 replaces complex erasable p/ROMS with multiple-sourced, simple to program bipolar p/ROMs. The card uses std open-collector or 3-state 256 x 4 or 512 x 4 bipolar p/ROMs, with 2k of memory from 256 x 4 p/ROM and 4k from 512 x 4 p/ROMs. It has full 65k address decoding and is complete with p/ROM sockets. A 5-V supply is required. **MilerTronics, Div of George Miler Inc,** 303 Airport Rd, Greenville, SC 29607.

Circle 227 on Inquiry Card

12- OR 16-BUTTON KEYBOARD FAMILY



A choice of 12- or 16-button arrays plus circuitry, mounting means, and legending is offered by this keyboard family. Circuitry options include matrix coding, single pole/common bus switching, 2-out-of-7 or 2-out-of-8 code. Either 3 x 4 or 4 x 4 array is available with post mounting or screw type flange mount. Std keyboard arrangements have molded-in legends, hot-stamped legends to customer order, and snap-on caps for self-legending of prototypes. **Grayhill, Inc,** 561 Hillgrove Ave, La Grange, IL 60525.

Circle 228 on Inquiry Card

Teledisk from Teleray!

You'll Love this Little Smart ASCII Minifloppy Disk!

Add local editing, storage and forwarding to ANY ASCII TERMINAL!

...with this all-new micro-processor-based minifloppy terminal.
- Stores 37 screens of 24 x 80 characters, or 13½ pages of 8½" x 11" printed data (71,680 characters) in non-volatile memory!
- Uses new minifloppy 5¼" media
- Two RS232 interfaces, terminal and modem
- Selectable CRT or Printer Edit Modes
- Basic functions: read, record (pack or line mode), erase, find, address, answer back, insert ("Go To" operation)

Teledisk is your answer for decreasing computer connect time, decreasing telephone connect time and the answer to unattended recording of data. Add more terminals to your computer *without* adding more ports. Call collect: 612-941-3300 and ask for TELEDISK!

TELERAY DIVISION RESEARCH INC

BOX 24064 MINNEAPOLIS, MINNESOTA USA 55424

You won't find a better family of printers for the price.

It's that simple.



The New Centronics 700 Series.

Now, the features that make our model 700 the best, lowest-priced serial printer are available in a *family of seven* models: uncomplicated modular construction; the reliability of fewer moving parts; high parts commonality; and low price. All of which means a lower cost of ownership.

The new 700 family covers a full range of serial printer requirements: 80- and 132-column format; 60 to 180 cps speed range; bi-directional and logic-seeking operations; and 110-300 baud KSR and RO teleprinters.

Like all Centronics printers, the 700 family is better because we back them with a wide choice of customizing options and accessories. More than 100 sales and service locations worldwide. Centronics' financial stability, and dependability proven by more than 80,000 printers installed.

Simplicity of design, full range capabilities, and better back-up make our 700 series printers simply better. Centronics Data Computer Corp., Hudson, N.H. 03051, Tel. (603) 883-0111. Or Centronics Offices in Canada and throughout the world.

CENTRONICS® PRINTERS
Simply Better

CIRCLE 100 ON INQUIRY CARD

PRODUCTS

MODULAR DATA ACQUISITION SYSTEM



Data acquisition 1000 system series for industrial and scientific applications consists of a rack drawer, card cage/backplane assembly which holds up to 11 8.5 x 10″ (21.6 x 25.4 cm) or 22 8.5 x 5″ (21.6 x 12.7 cm) or any mixture of DEC LSI-11 bus-compatible PC cards. Standalone system has LSI-11 microcomputer and min 4k RAM for up to 700 high level analog input channels, 128 low level analog input channels, or up to 700 digital I/O functions. **Adac Corp,** 15 Cummings Pk, Woburn, MA 01801.
Circle 229 on Inquiry Card

ADVANCED FAULT RESOLUTION CAPABILITY

Advanced fault resolution (AFR) option for Capable 4000 logic testers finds both component and production defects in microprocessor circuits and also indicates exactly which component to replace or etch to repair. Step-by-step instructions on a video display terminal tell the operator where to place a current sensing probe. At the same time, the tester injects a controlled current pulse into the signal bus; the package controls both current pulse and current sensor. **Computer Automation, Inc, Industrial Products Div,** 18651 Von Karman, Irvine, CA 92713.
Circle 230 on Inquiry Card

DISKETTE WRITE PROTECT OPTION

A write protect option available on the 9512 micro-disc allows the user to protect data files stored on any diskette via a small hole punched in the diskette jacket. A sensor and associated circuitry within the 9512 inhibit activation of the write mode when this hole is open. To re-enable recording on a protected diskette, the hole can be covered with black opaque tape such as electrical tape. **Techtran Industries, Inc,** 200 Commerce Dr, Rochester, NY 14623.
Circle 231 on Inquiry Card

MULTIPLE-OUTPUT DC POWER SUPPLIES



SPS-D and -T models provide power for memories, floppy discs, op amps, microprocessor circuitry, logic, and transistorized circuitry. Std adjustable voltages range from ±5 to ±28 Vdc (±10%). Currents are available from 1.0 to 12 A. Features include complete isolation between outputs, 115/230 Vac, 47- to 440-Hz input, temp compensated circuitry, output voltage adjust, and current limit short-circuit protection. Line and load regulation is ±0.1; ripple is 0.1%; response time is 50 μs. **Standard Power, Inc,** 1400 S Village Way, Santa Ana, CA 92705.
Circle 232 on Inquiry Card

HIGH RESOLUTION SHAFT ENCODER



Providing 1M count capacity with 6-decade BCD or 22-bit binary resolution, encoder consists of ruggedized NEMA 12 electromagnetic transducer and solid-state electronic converter connected by six wires. Also available is a 1.1″ (2.8 cm) diam transducer. A 1-line instant reset sets all decades or bits to zero; preset control is provided. For BCD units, resolution/turn is 3 decades or 1k counts with total capacity of 1k turns; for binary units, counts/turn is 10 bits with a total of 4096 turns. **Astrosystems, Inc,** 6 Nevada Dr, Lake Success, NY 11040.
Circle 233 on Inquiry Card

VARIABLE DELAY LINE

Minitrim variable delay line, for precise delay adjustments, provides max delays from 10 through 300 ns, attenuation of <0.5 dB, and resolution of <1 ns. Std features include precious metal bifurcated contacts, O-ring seal, stainless steel shaft, epoxy fiberglass case, 2-point terminal embedment, and internal PC board. Units are 0.35″ (0.89 cm) high x 0.70″ (1.78 cm) wide and either 2.25 or 4.00″ (5.7 or 10 cm) long; TD/TR ratios are 4:1 and 7:1, respectively. **Kappa Networks, Inc,** 165 Roosevelt Ave, Carteret, NJ 07008.
Circle 234 on Inquiry Card

CDM-77/03
LSI-11 & PDP-11/03
Compatible Memory



The CDM-77/03 features—

Up to 32K words in a *single* option slot.

Available in 16K or 32K word configurations.

Functions with burst (CPU) refresh or distributed (DMA) refresh.

Addressable as a contiguous block in 2K word increments.

Completely LSI-11 hardware and software compatible.

Off-the-shelf deliveries.

Full one year parts and labor warranty.

MTBF in excess of 100K hours.

Distributor inquiries invited.

The first in low cost DEC Compatible peripherals . . .

CYBERCHRON CORPORATION
5768 Mosholu Avenue
Riverdale, New York 10471
TEL 212/548-0503
TWX 710/593-6543

What price boredom?

ACDC will bore you for less. Much less.

Because we've reduced prices on our open frame power supplies to an all-time low. Thanks to new manufacturing facilities. The latest engineering advances. And an insane desire to increase our sales.

But what's all this talk about boredom? Aren't low prices exciting? Certainly.

It's our open frame power supplies that are boring. Boring because they're so dependable. (In fact, our entire open frame line just received UL recognition.) Boring because when you put one in your product, you never have to worry about it again. And boring because they're just sitting on the shelf—waiting for your order.

If you'd like to know all about our boring products and exciting, low prices, send for our new catalog. Or call us at (714) 757-1880.

SOME OF OUR BORING POWER SUPPLIES.



acdc electronics

401 Jones Road, Oceanside, California 92054

EMERSON ®

We made a science out of boredom.

CIRCLE 102 ON INQUIRY CARD

Intel compatible data acquisition system for only $495*

The low-cost ADAC Model 735 series of data acquisition systems is mounted on a single PC board that plugs into the same card cage as the Intel SBC-80/10, and SBC-80/20 single board computers and also the Intel MDS-800 microcomputer development system. The Model 735 bus interface includes a software choice of program control or program interrupt and a jumper choice of memory mapped I/O or isolated I/O.

The basic 735 OEM system which is contained on a single PC board (12″ x 6.72″ x 0.4″) consists of 16 single-ended or 8 differential analog input channels, either voltage or current inputs (4-20 mA or 5-50 mA), 12 bit high speed A/D converter, sample and hold and bus interface. The throughput rate of the Model 735 is 35 KHz. Optionally available is the capability of expanding on the same card to a total of 64 single ended or 32 differential voltage/current inputs. up to two 12 bit D/A converters, software programmable gain amplifier with auto zero circuit, scope control and third wire sensing.

ADAC Corporation, 15 Cummings Park, Woburn, MA 01801.
(617) 935-6668

*Price in quantities of 1 to 4.



GSA Contract Group 66

adac corporation

PRODUCTS

MULTILEVEL BREADBOARD



Offering a distribution system consisting of three distribution strips, two levels of PCs, and three front-mounted binding posts, Breadboard II has been expanded to replace the earlier version. With 3208 solderless plug-in tie-points on a universal 0.1 x 0.1″ (0.254 x 0.254-cm) matrix, the board accepts all DIPs and components with leads up to 0.032″ (0.08 cm) diam. The matrix is comprised of 2776 tie-points while the distribution matrix provides 432. **A P Products, Inc,** 72 Corwin Dr, Box 110, Painesville, OH 44077.
Circle 235 on Inquiry Card

MILITARIZED BACKPANEL SYSTEM

A militarized version of the Fabri^{R}-Pak backpanel system for severe environment and high speed applications features "tuning fork" connector patterns, press-fitted into a PC backpanel, and covered with an insulated housing to receive blade-type contacts. It eliminates wirewrapping, provides vibration-resistance, and allows discrete circuitry on the board. Capacitance is provided through ground and power planes. Individual contacts are removable. **National Connector Div, Fabri-Tek Inc,** 9210 Science Ctr Dr, Minneapolis, MN 55428.
Circle 236 on Inquiry Card

LINE CONTROLLER

Remote terminal costs in communications networks are reduced by up to 50% with the terminal line controller model TLC. Designed for IBM, Burroughs, Univac, and Honeywell computer systems, 2740 MOD II protocol emulator permits use of nonintelligent RS-232-C ASCII terminals without modification of host software. The controller provides protocol emulation, buffering, and addressing. Data communications is asynchronous at speeds from 150 to 1800 bits/s. **C. D. Johnson & Associates Ltd,** 56 Sparks St, Suite 100, Ottawa, Ontario K1P 5A9, Canada.
Circle 237 on Inquiry Card

Software Engineers

Our expanding product lines have opened several challenging positions to qualified software engineers in the following disciplines:

Project Engineer

To develop the architecture for a modular system, which also contains resident diagnostics using microprocessors. BSCS or BSEE and experience in system design. Hardware familiarity helpful.

Evaluation Engineers

To evaluate diagnostic routines for testing Microprocessor Development Aids and similar products. Minimum of BSCS or BSEE with hardware and software knowledge. Design or evaluation experience necessary.

Design Engineer

Software engineer for microprocessor system programming. Will interact with digital design engineers and operating system programmers to develop software support for a variety of microprocessors. BSCS or BSEE and familiarity with digital hardware. Extensive assembler language software experience, microprocessors or minicomputers helpful.

Diagnostic Programmer

Maintain existing diagnostic programs and work closely with digital design engineers during development cycle. Write diagnostic program for circuitry under development. BSCS or BSEE and ability to read digital schematics to the gate level. Assembler language background necessary.

Salary is open. Benefits include liberal insurance, educational support and profit sharing programs.

Send detailed resume and salary history to Mary Walhood, TEKTRONIX, INC., P.O. Box 500, CD81, Beaverton, Oregon 97077.

An Equal Opportunity Employer M/F/H.

Tektronix
COMMITTED TO EXCELLENCE





Hewlett-Packard Versatec

Immortality for two cents.

Now that your HP 2640 series terminal has that picture on-screen, don't lose it. Not when you can immortalize that image for only two cents a copy.

The Versatec 1640 hard copy system is designed specifically for HP terminals. Just plug it in.

One system serves up to eight terminals. It delivers ready-to-use copies in just ten seconds. And most important, it provides the best copy quality at the lowest copy cost.

The best copy lasts. No fade. No deterioration. True archival quality at one-fourth the cost of dry silver paper.



You can store paper at room temperature. Make up to 1000 fanfold copies without a refill, or use an interchangeable continuous roll. Another nice advantage. You can write on this paper in pen or pencil without a slip or a smudge.

Need more justification? Optional controllers let you print and plot directly from any popular computer. Print 1000 LPM or plot three square feet per minute. Then, upon request, make any number of copies from your HP terminals. That's utilization!

Archival quality. Lower cost per copy. And maximum machine utilization. All from the one complete hard copy system for HP display terminals—The Versatec 1640.

So check our readers' service number or use the coupon. It could immortalize your image.

VERSATEC
A XEROX COMPANY

2805 Bowers Avenue
Santa Clara, CA 95051
(408) 988-2800

Tell me more about hard copy from . . .

☐ Hewlett-Packard 2648A or other 2640 series terminal

☐ Other displays and video sources _____
(manufacturer and model)

☐ Send samples

name telephone

organization

address

city, state & zip



Data Display: YOUR Way

Ann Arbor makes over 1000 standard RO and KSR display terminal models. Alphanumerics. Graphics. Or both.

We also thrive on *tough* CRT display applications. Unique character sets. Unusual graphics. Difficult interfacing. Custom keyboards. Special packaging. You name it.

Standard or custom, *every* terminal produced is based on a field-proven Ann Arbor engineering concept. DESIGN III desktop terminals to complement any office decor. Compact, rugged Series 200 modular terminals that defy industrial environments. Or barebones board sets for OEMs who prefer to roll their own.

Many companies sell CRT terminals. But Ann Arbor sells creative solutions to CRT display problems, as well.

Probably at lower cost than anyone else in the business.

Contact us at 6107 Jackson Road, Ann Arbor, MI 48103. Tel: 313-769-0926 or TWX: 810-223-6033. Or see our catalog in EEM, Volume One.

ANN ARBOR TERMINALS, INC

. . . creating new ways to communicate

CIRCLE 106 ON INQUIRY CARD

Programmers Systems Analysts

Openings currently exist at all levels for software personnel possessing a background in the following areas:

- **Microprocessors**
- **Minicomputers**
- **Operating Systems**
- **Distributed Processing Networks**
- **Systems Simulation**
- **Systems Constructors & Generators**
- **8080 Assembly**
- **Assembly & COBOL Languages**

Requires a BS/MS in CS, EE, or Math.

We welcome responses from new graduates as well as experienced personnel.

The above positions are located at NCR's Terminal Systems Division in Dayton, Ohio. Our Engineering Staff is a leader in the design and implementation of Financial Terminal Systems. Dayton is a progressive midwestern area, small enough to be friendly but large enough to offer outstanding communities with excellent housing, educational facilities and cultural activities.

Submit your resume and salary requirements to:

NCR

Employment Department, CD-11
Terminal Systems Division
NCR Corporation
Dayton, Ohio 45479

An Equal Opportunity Employer

CIRCLE 61 ON INQUIRY CARD

PRODUCTS

SEND/RECEIVE OPTION FOR HIGH SPEED TAPE UNITS

Data communications diagnostics are aided by the send/receive option for the T-511 portable high speed tape unit. All traffic is recorded on both sides of a data link for later replay and analysis. Data recorded on tape by the Datascope D-601 or a tape unit may be transmitted between two high speed tape units equipped with the option; data are sent in simplex operation (not simultaneously). Information on the tape cartridge is read by the tape unit in blocks, and presented to the modem in EIA levels. **Spectron Corp,** 344 New Albany Rd, Moorestown, NJ 08057.

Circle 238 on Inquiry Card

OFFLINE RECORDER



ANSI-compatible cassette recording system model 2146 is a write-only recorder that records offline and plays back directly on Texas Instruments "Silent 700" terminals. Operating at remote sites and times to free up a terminal, it accepts serial data at five selectable rates up to 1200 baud and records in ANSI/ECMA format. It also accepts parallel data. Std Philips cassettes are used and may also be read back on the company's 3765-8 recorder. **Memodyne Corp,** 385 Elliott St, Newton, MA 02164.

Circle 239 on Inquiry Card

PROGRAMMABLE I/O CONTROLLER

PIO4800, a 6-port PIO controller, interfaces the computer to printers, keyboards, or other parallel devices with or without handshaking strobes. It may be operated with or without interrupts, in either isolated I/O or memory-mapped mode. Data transfer is parallel; a single input or output is accomplished by executing one processor instruction. Compatible with the S-100 bus, the 5 x 10″ (12.7 x 25.4-cm) PC board contains two channels with three different modes of each channel. **I O R,** Box 28823, Dallas, TX 75228.

Circle 240 on Inquiry Card

Just Delivered:

Elexon's Spanking New Switcher

This new 8 pound baby has really arrived. You couldn't ask for more (or less) in a 250 Watt Switching Power Supply. It's got just about everything. Full rated operation up to 50° C (Derated to 70° C). Complete built-in protection against overload, short circuit, or over voltage with foldback current limiting. And state-of-the-art design utilizing IC controls to minimize component count...which maximizes reliability.

It's next to impossible to get this switcher down. Forget about brownouts. It's full-rated in the worst. Temperature rise? Don't worry! It's protected with a unique self cooling design. And it's quiet with its super efficient 20KHZ switching frequency.

Ideal for complex digital and memory systems, this new Elexon Switcher really delivers.

What you need. When you need it. Efficiently. Quietly. Reliably. A light weight little package with a great big heart!

Another Ugly™ Made Beautifully by ELPAC.



CIRCLE 107 ON INQUIRY CARD

ELPAC ELECTRONICS, INC.
ELPAC Power Systems
3131 So. Standard Avenue
Santa Ana, Calif. 92705
(714) 979-4440
TWX 910-595-1513





NOW THE Z-80 IS CONNECTED TO
THE MOST POPULAR BUS IN TOWN

The first member of the **U**nibus **M**icro **C**hannel family is a Zilog* Microprocessor interfaced to the UNIBUS* for custom interfacing applications.

The UMC-Z80/2.5 interface includes the following:

- 400 nsec Z-80* Microprocessor (250 nsec optional)
- 4K bytes of semiconductor RAM memory
- 1K bytes of PROM with diagnostic firmware
- 16x16 bit registers shared by both processors
- DMA access to all 128K words of UNIBUS address space
- Z-80 bus connector for custom interfaces
- Expansion to 64K bytes of RAM and PROM
- Ability to generate interrupts to the PDP-11
- Mounts in one Hex SPC slot

The UMC-Z80/2.5 allows the sophisticated user or OEM to easily build custom interfaces using the speed and power of the Z-80 Microprocessor without the need of detailed knowledge of UNIBUS interfacing. Applications including data acquisition, protocol handling, data formatting and serial line interfacing can be off-loaded into the Z-80 with data transfers to and from the PDP-11 in DMA mode. Custom interfaces and software are also available. Single unit price is $2495 with delivery in 90 days. Call ACC for further information or quantity pricing.

ACC HAS CONNECTIONS

*registered trademark

Associated **C**omputer **C**onsultants, 228 East Cota Street, Dept. A, Santa Barbara, CA 93101. Phone (805) 963-8801. TWX 910 334-4907

CIRCLE 108 ON INQUIRY CARD

At Power/Mate, fast delivery of open frame power supplies is an open-and-shut case.

Power/Mate can deliver open frame supplies faster than anyone else in the business.

And that's a fact!

Our Econo/Mate II series is available in single, dual and triple output models with all the built-in reliability you've come to expect from Power/Mate.

But for all its quality features, a Power/Mate open frame supply is still, most of all, economical.

We wouldn't call it Econo/Mate if it wasn't.

Our Econo/Mates are stocked in-depth, along with our switching-regulated, miniature, modular, sub-modular and lab supplies.

All ready for immediate delivery from our East or West Coast plants.

And Power/Mate stands behind each and every power supply we make.

We've been doing it for fifteen years.

So if you're looking for a power supply today, from a company who will still be here tomorrow, look no further.

Call Power/Mate.



PMC
POWER/MATE CORP.

514 S. River St./Hackensack, New Jersey 07601/(201) 343-6294/TWX (710) 990-5023
17942 Skypark Circle/Irvine, California 92714/(714) 957-1606/TWX (910) 595-1766

The world's largest supplier of quality power supplies.

PRODUCTS

PUSHBUTTON SWITCH ASSEMBLY

An interlocking/momentary pushbutton switch assembly with master-on control module has applications in the instrumentation and controls market. Engaging the master-on module interlocks all switches, while disengaging reverts the switches to momentary contact mode. Features include lighted or nonlighted assemblies, and multiple switch configurations. Devices are available for use in an interlock assembly with lockout. **Centralab Electronics Div, Globe-Union Inc,** PO Box 858, Hwy 20 W, Fort Dodge, IA 50501.

Circle 241 on Inquiry Card

CONTINUOUS CURVE PLOTTER

The Spectra-Sensor adds plotting capability to ACS-500 or 600 color control systems. Its buffer memory enables it to execute its plot routine while the scanning portion of the ACS system simultaneously measures the next sample. Total time for std and batch measurements is 45 s max. An electrostatic paper hold-down feature facilitates paper changing and accommodates many paper sizes and weights. Plotter is accurate to 0.005″ (0.127 cm). **Applied Color Systems, Inc,** PO Box 5800, U.S. Hwy No 1, Princeton, NJ 08540.

Circle 242 on Inquiry Card

TTY AUXILIARY EQUIPMENT ADAPTER

For use with model 33 Teletype[R] terminals, adapter facilitates expansion by providing an auxiliary I/O port which permits disc/tape cassette unit, X-Y plotter, punched card reader, or other auxiliary terminal device to function as an integral part of the teleprinter. Mode of online communications is determined by the external signal line wiring. **United Data Services Co, Inc,** 3024 N 33rd Dr, Phoenix, AZ 85017.

Circle 243 on Inquiry Card

20-MHz DUAL TRACE SCOPE

A 20-MHz dual channel, dual trace oscilloscope, model LBO-508 has a 10-mV/cm sensitivity and features add and subtract modes on CH-1 and CH-2 to facilitate rapid checkout for industrial, laboratory, and service applications. The scope automatically triggers from CH-1 or 2 to eliminate adjusting of trigger level at every setting. It triggers on the smallest signal levels, and has a bright, stable display at all sweep speeds. Rise time is 17.5 ns. **Leader Instruments Corp,** 151 Dupont St, Plain-View, NY 11803.

Circle 244 on Inquiry Card

CIRCLE 109 ON INQUIRY CARD

When you're big on quality but short on space Ball measures up.



Our ready-to-run monitor-pack helps you save dollars as well as room in custom terminal installations.

If you haven't got the room for a full size chassis, or if you just plain insist on adding Ball performance to your own electronics, size up our flexible TVX-Series monitors.

We fully assemble, test and align our 9″ and 12″ direct drive sets then ship them to you securely mounted on money-saving, disposable baseboards. Just slide four components — tube, PC board, vertical and horizontal transformers — into whatever room you've got. Hook-up a single edge connector for both DC power and signal input, and you're fully operational.

You're assured of peak performance, too. Complete electronic controls, including horizontal and vertical linearity, allows us to precisely align each set to your particular requirements.

It's that easy to add field proven Ball monitors with do-it-yourself savings.

Compare life cycle costs. You'll have a Ball.

If you need a monitor for compact installations, you need Ball quality more than ever. Crowded component layouts and reduced air circulation make Ball's conservative engineering and careful component selection important factors in reliability.

Your Ball representative would be pleased to give you full information. After all, helping customers in or out of tight spots is a big part of his job.

Ball Brothers Research Corporation **Electronic Display Division**
P.O. Box 3376, St. Paul, Mn. 55165 (612) 786-8900. TWX: 910-563-3552

General Sales Offices:

Addison, Illinois (312) 279-7400
Ocean, New Jersey (201) 922-2800
Santa Clara, California (408) 244-1474
Upland, California (714) 985-7110

Ball Electronic Display Division

CIRCLE 110 ON INQUIRY CARD

PRODUCTS

FLEXIBLE, STATIC SEMICONDUCTOR MEMORY



The in-7000 offers from 16k to 256k words of memory capacity and word sizes from 6 to 96 bits. The system uses only a single 5-V power supply, needs no refresh, and comes as a basic card or in a chassis. Available in four 16k configurations—16k x 12, 16, 20, or 24 bits, card may be changed to the corresponding 32k x 6-, 8-, 10-, or 12-bit configuration by merely operating the byte control input line. Read and write cycle times are 250 ns (7000 version), 350 ns (7001), and 500 ns (7002). **Intel Memory Systems,** 1302 N Mathilda Ave, Sunnyvale, CA 94086.
Circle 245 on Inquiry Card

HALL-EFFECT ELECTRONIC SWITCH

Serving as a replacement for mechanical switches for a higher degree of system reliability, the TL170 is a bipolar magnetically-activated electronic switch that uses the Hall effect for sensing a magnetic field. It performs electrical switching with hysteresis. Each circuit, offered in a 3-pin TO-92 SILECT™ plastic package, consists of a silicon Hall sensor, signal conditioning and hysteresis function, and an output stage integrated onto a monolithic chip. **Texas Instruments, Inc,** PO Box 5012, Dallas, TX 75222.
Circle 246 on Inquiry Card

TWX-DDD DATA MODEM

Combining a TWX and DDD modem with touch-tone or rotary dialing, modem interfaces to any 0- to 300-baud data terminal or computer. A 20-mA current loop and RS-232-C interface are std; outputs from both interfaces may be used simultaneously. Active filters, CMOS logic, and MSI ICs are employed in the unit. Also featured is automatic answer on TWX or DDD lines without operator intervention. Device operates over the TWX and DDD telephone network at data rates up to 300 baud. **Westwood Associates, Inc,** Bloomfield, NJ 07003.
Circle 247 on Inquiry Card

MINIATURE DIP SOLID-STATE RELAY

Packaged in a low profile hermetically sealed DIP enclosure, model 682-1 is optically coupled and utilizes thick-film hybrid microcircuit construction. Input voltage range is 3 to 16 Vdc with TTL and HiNIL compatibility. Output rating is 1 A/250 V rms, with synchronous zero voltage turnon to minimize emi. Designed to meet requirements of MIL-R-28750/9, relay has an operating amb temp range of −55 to 110°C. **Teledyne Relays,** 3155 W El Segundo Blvd, Hawthorne, CA 90250.
Circle 248 on Inquiry Card

MINIATURE 100-LED COLUMN DISPLAY

Model MC-100 miniature LED column display consists of a line of 100 LEDs with lit length proportional to the input voltage. The compact unit requires ±5-V power supply and is TTL-compatible. Four terminal pins are voltage input, 5 V, −5 V, and ground. Input range is 0 to 2.5 V for zero to full scale reading. Resolution and accuracy are better than 1%. Unit is free from flicker and resistant to mechanical stresses and vibration. Available color options are red, green, yellow, or infrared. **Digital Components Corp,** 19 Grant St, Linden, NJ 07036.
Circle 249 on Inquiry Card

When RFI problems get sticky, try sticky fingers®

Attaches faster, shields better than anything else!



SERIES 97-500 The original Sticky Fingers with superior shielding effectiveness.



SERIES 97-520 A smaller size strip; highly effective in less space.



SERIES 97-555 New Single-Twist Series for use when space is at a premium. Measures a scant ⅜" wide.



SERIES 97-560 New ½" wide Double-Twist Series, ideal for panel divider bar cabinets.

Now you can specify the exact type beryllium copper gasket that solves just about every RFI/EMI problem. Perfect for quick, simple installation; ideal for retro-fitting. Self-adhesive eliminates need for special tools or fasteners. Write for free samples and catalog.

INSTRUMENT SPECIALTIES COMPANY, Dept. CD-57
Little Falls, N.J. 07424
Phone—201-256-3500 • TWX—710-988-5732

CIRCLE 111 ON INQUIRY CARD

NEW KEMET® CERAMIC CAPACITORS GUIDE!



Complete selection data on all KEMET Monolithic Ceramics. CK05-CK16, CKR05-CKR16, MIL-C-20, or Dipped. "Solder Guard", "Gold Guard", or Established Reliability Chips. Ultra-Stable NPO, Stable BX or General-Purpose Z5U dielectric. Radial or axial leads. Write today. Components Department, Union Carbide Corporation, Box 5928, Greenville, SC 29606.

UNION CARBIDE
COMPONENTS DEPARTMENT
KEMET is a registered trademark of Union Carbide Corporation

CIRCLE 112 ON INQUIRY CARD

A software development breakthrough.

FORTRAN compiler and relocatable macro assembler in a new custom software system for micros.

Now it's easier than ever to create smooth running custom software for PCS SuperPac 8080 A-*based microcomputers. And it takes less time, too. With SPDS. The SuperPac development system.

SPDS has resident software you'd expect to find only in minis. Like a FORTRAN compiler option for fast, easy programming in a language your programmers already know (look for BASIC soon). A cross-reference generator that lists constants, labels and addresses and really saves time when you're moving segments around. A relocatable assembler with full macro capability. And an up-down loader for directly loading software into a target system up to 1,000 feet away and calling it back to the development system whenever you need it.

Choose the hardware tools you need. A desk console and dual floppy are standard. From there it's up to you. EPROM programmer, CRT terminal, choice of two line printers and paper tape reader are optional.

SPDS for SuperPac microcomputers. It's a software development breakthrough. From Process Computer Systems, of course. The full service microcomputer manufacturer.

*And, soon, for our new Z-80 based micros.

Tell me more. ■ SPDS ■ SuperPac ■ Please have salesman call.

Attach your business card here.

PCS **Success is PCS.**

Process Computer Systems, Inc.
750 North Maple Road, Saline, Michigan 48176
313-429-4971 TWX 810-223-8153

CIRCLE 113 ON INQUIRY CARD

PRODUCTS

POWER LINE DISTURBANCE MONITOR



Model FDM-2 monitors voltage and frequency on single- or 3-phase power lines and prints out exact time and duration of a fault, as well as other information. Features include battery standby, adjustable thresholds, testpoints for oscilloscope display, and alarm. Front panel contains optional digital clock display, nominal line voltage selector, and self-check button. Rear panel contains alarm buzzer, Delta/Wye selection, testpoints, instrument power on-off, and power input connector. **Consultronics Ltd,** 38 Le Page Ct, Downsview, Ontario M3J 1Z9, Canada.
Circle 250 on Inquiry Card

LIGHTED PUSHBUTTON SWITCHES

The A3P series of compact lighted pushbutton switches offers mechanical contacts or solid-state outputs in momentary or alternate action formats. Devices with dimensions of <2" (5 cm) have a service life rated at 5M mechanical operations (min). Interchangeable lens panels permit choice of color. A clear lens cover permits field changes of legends. Solid-state contacts use a Hall-effect IC to produce an output of 50 mA at 5 Vdc in either pulse or continuous operation. **Omron Electronics, Inc, Control Components Div,** 233 S Wacker Dr, Chicago, IL 60606.
Circle 251 on Inquiry Card

ROTARY/PUSHBUTTON SWITCH

Three Blue Line rotary/pushbutton switches are assembled from modules called "stages," which each contain two isolated double-break silver-alloy, cam operated contacts. The D10 is designed for motor control, instrumentation, and std rated control circuits. Virtually corrosion resistant cross wire contacts of the D11 gear it for dry circuitry down to 30 mV. D12, designed for reliability in low voltage circuits, has a higher interrupting capacity than the D11. **American Solenoid Co, Inc,** 245 E Inman Ave, Rahway, NJ 07060.
Circle 252 on Inquiry Card

BIDIRECTIONAL INTERFACE MODULE

The model 417 bidirectional interface module offers Data General computer users compatibility with instruments operating on the IEEE-488/1975 std digital interface for programmable instrumentation. Occupying one I/O slot in computer or expansion chassis, it communicates with the CPU using std Busy/Done logic. Hardware includes interrupt transfer to and from CPU, 3-wire handshake, and parallel and serial poll. An IEEE-488 cable and software are included. **RBI Systems,** 13123 Valleywood Dr, Wheaton, MD 20906.
Circle 253 on Inquiry Card

PUSHBUTTON THUMBWHEEL SWITCH

The T56 series bidirectional pushbutton thumbwheel is available in six codes—decimal, BCD, BCD plus complement and 1 common, BCD complement only, BCD with diode provision, and single-pole repeating. Wheel indexing is controlled by two plungers. A transparent plastic window covers the legend opening. Operating force is 400 g, and contact resistance is 0.1 Ω max. It is intended for use in logic level circuits with a rating not to exceed 50 V, 0.1 A. **Cherry Electrical Products Corp,** 3600 Sunset Ave, Waukegan, IL 60085.
Circle 254 on Inquiry Card

The probes for the PRO!

4 of the 25 reasons you should be using the new KK600 Series Logic Probes

1 Pulse – will capture and display a single 5NS (200 MHZ) Pulse.

2 Single or Dual Threshold®

3 "I" or "Hi" full time – DC to 200 MHZ

4 "O" or "Lo" full time – DC to 200 MHZ

Kurz-Kasch, Inc.

ELECTRONICS DIVISION
BOX 1246
1501 WEBSTER STREET
DAYTON, OHIO 45401
(513) 223-8161

CIRCLE 114 ON INQUIRY CARD

Your answer to line-voltage problems



Variac® Automatic Voltage Regulators

- Regulation to 0.2%
- Up to ±20% correction
- Models range from 8.7A to 85A
- Input: 50, 60 or 400 Hz; 120 or 240V

Contact your nearest GenRad sales office or write for descriptive catalog. 300 Baker Avenue, Concord, MA 01742, Telephone: (617)369-8770.

GenRad

CIRCLE 115 ON INQUIRY CARD

Now you have a choice of DEC®-compatible floppy disk systems.

The DEC RX01.
It costs ~~$4,095.~~ $4,300.
You can wait months for it.

The DSD 210.
It costs $3,295.
You can have it in weeks.





YES	PDP®-8, PDP®-11, LSI-11 plug compatible	YES
YES	Software compatible with all DEC operating systems	YES
YES	IBM 3740 Format	YES
NO	Write protect switches	**YES**
YES	Automatic head unload	YES
YES	Ceramic read/write head	YES
YES	Holds 256,256 bytes per diskette	YES
NO	Diskette formatting capability	**YES**
1 OR 2	Drives per controller	**1, 2, OR 3**
NO	Interchangeable 50/60 Hz operation	**YES**
YES	Digital phase-lock-loop data separation circuit	YES
NO	Front panel activity LED lights	**YES**
NO	Front panel system status indicators	**YES**
PARTIAL	Modular construction	**COMPLETE**
MINIMAL	Self-testing microcode	**EXTENSIVE**
NO	Field-proven Shugart drives	**YES**

Our DSD 210 floppy disk system is 100% hardware, instruction set, and media compatible with all DEC PDP-8, PDP-11 and LSI-11 systems. It costs $1,000 less than DEC's RX01, has a far shorter delivery time, and has more useful features.

Data Systems

For an expanded comparison and complete technical details, phone or write Data Systems Design, Inc., 3130 Coronado Drive, Santa Clara, CA 95051, 408/249-9353.

®registered trademark of Digital Equipment Corporation

CIRCLE 116 ON INQUIRY CARD

INTEGRATED COMPUTER SYSTEMS, INC.

MICROPROCESSO

CHICAGO	WASHINGTON, D.C.	LOS ANGELES	HOUSTON	DETRO
December 5-9	December 12-16	January 16-20	January 23-27	February

Similar courses being offered in EUROPE. Write or Call:
Integrated Computer Systems Publishing Co., Inc.
Boulevard Louis Schmidt 84, Bte 6
1040 Brussels, Belgium
Telephone: (02) 735 60 03 Telex: 62473

3 or 4 Day Engineer

2 Day Project Management Series

COURSE 111: One Day—MONDAY

Microprocessor Project Management

From design through manufacture, QA and field service

MICROPROCESSORS: HOW CAN YOU GO WRONG ? ? ?
WHAT ABOUT . . . ?

Underestimating software costs and time?
Inadequate software documentation?
Selecting the wrong microprocessor?
Software development equipment($14000!)?
Manufacturing problems? Hardware/software testing? Reliability? Obsolescence? . . .

A microprocessor project is different from anything you've managed before. This one efficient day of organized, expert guidance will save you literally months of wasted time, re-invented wheels, and costly oversights.

This unique course synthesizes the experience of hundreds of project managers (who learned the hard way) into a practical field-proven methodology for managing all phases of a microprocessor application. The course emphasizes high-risk, high-cost and time-critical problems unique to microprocessors. Concrete real-world case studies illustrate the methods presented, and these step-by-step methods can be immediately applied to your own project.

This course will benefit every manager and engineer concerned with microprocessors. Teams from engineering, manufacturing, QA, and field service are encouraged to attend (team discounts available).

KEY TOPICS

1. **Fundamental concepts, definitions and jargon.**
2. **Avoiding pitfalls and "technical tunnel-vision."**
3. **Planning and specifying the project — the PERT/flowchart.**
4. **How to select personnel and evaluate performance.**
5. **How to select the right microprocessor — what's really important?**
6. **Software development and test equipment — what's really needed?**
7. **How to estimate overall project costs and schedule.**
8. **How to manage software design and development.**
9. **Software documentation — a practical methodology.**
10. **Verifying that the software works.**
11. **Manufacturing, testing and QA — both software and hardware.**
12. **Component & product reliability — planning μP field service.**
13. **How to prepare for the future today . . . and avoid obsolescence tomorrow.**

SPECIAL LATE-AFTERNOON WORKSHOP

A unique opportunity to discuss your application-oriented problems in a productive shirtsleeves atmosphere. Immediately after Course 111 from 4:30 until 6:00pm with snacks and refreshments.

COURSE 102s: One Day—TUESDAY

Microprocessors and Microcomputers:

A Comprehensive Technical Introduction and Survey

This course provides a comprehensive unbiased introduction to microcomputer hardware/software development and integration. The course emphasizes the factors affecting key design and development decisions including: processor selection, I/O and software design, software implementation steps, development and test equipment, and most important pitfalls to be avoided when getting started. Throughout the course, applications examples provide concrete illustrations of concepts presented and are drawn from the following application areas: military, communications, consumer, instrumentation, industrial control, and biomedical systems.

This course is *vital* (1) to all engineers and managers who want a quick, unbiased, cost-effective introduction to microprocessors (2) to those engineers attending this as the first day of the "Engineering Design" series (Course 102s, 125A and 136) and (3) to managers attending this course as the second day of "Project Management" series (Course 111 and 102s).

COURSE OUTLINE

1. **INTRODUCTION**
   • What is a microprocessor (μp)? a microcomputer (μc)? • Identifying suitable and unsuitable applications
2. **FUNDAMENTAL MICROCOMPUTER CONCEPTS**
   • Terminology • Software (SW) — how it works; how it's developed • Hardware (HW) — Basic μc configurations • The μc design cycle
3. **THE HARDWARE**
   • μp architectures (4, 8, 16-Bit and slices) • Memory systems design — ROM, PROM, RAM, CORE • Input/output organization (programmable I/O, interrupts, DMA) • Build or buy?
4. **INTERFACING TO THE EXTERNAL WORLD**
   • I/O port design • Programmable LSI I/O chips • Interfacing to: analog devices, keyboards, displays, cassettes, etc.
5. **SOFTWARE DESIGN & IMPLEMENTATION**
   • Four implementation methods • Editors, assemblers, compilers • Assembly vs. high level languages (FORTRAN, BASIC, PL/M)
6. **INTEGRATING AND TESTING THE HW AND SW**
   • What really useful tools are available? • What tools should you build yourself? • Isolating and fixing HW and SW bugs
7. **TECHNICAL SURVEY OF μP'S AND μC'S**
   • Intel, Fairchild, Motorola, National, Rockwell, Signetics, Texas Instruments, Zilog, and others including the new LSI minicomputers • Board-level μc systems — PROLOG, PCS, CONTROL LOGIC, WARNER/SWASEY, and others • A systematic, application-oriented approach to selecting the right microprocessor family.
8. **UTILIZING DEVELOPMENT AND TEST EQUIPMENT**
   • Logic analyzers • SW simulators • Specialized μc debugging equipment • μc development systems • Peripherals to buy
9. **HOW TO GET STARTED**
   • What equipment to buy first • Pitfalls to avoid • Good information sources

R EDUCATION

10	DENVER February 13-17	BOSTON March 6-10

Design Series

COURSE 125A: Two Days — WEDNESDAY & THURSDAY

Hands-On Microcomputer Programming Workshop (for the beginner)

LEARN-BY-DOING EACH STUDENT RECEIVES A COMPLETE 8080 MICROCOMPUTER SYSTEM FOR HIS PERSONAL USE THROUGHOUT THE COURSE.

This highly efficient, intensive short-course combines expert teachers and detailed course materials with unique opportunity to learn by *immediately* implementing on *your personal microcomputer* each new programming concept as it is developed by the instructor.

COURSE OUTLINE [with exercises in brackets]

1. **INTRODUCTION TO THE ICS 8080 μC TRAINING SYSTEM**
   - Hardware configuration • How to use the keyboard/display and built-in commands • [Loading and executing a simple program]
2. **SOFTWARE FUNDAMENTALS AND BASIC TECHNIQUES**
   - CPU Register Instructions [Counting] • Memory Instructions [Storing & Retrieving Data] • Basic I/O [Controlling LED segments] • Jumps and Loops [Time delay program] • Bit Testing [Binary Decoding] • Subroutines & Stacks [Keyboard Input]
3. **ADVANCED PROGRAMMING TECHNIQUES**
   - Arithmetic [A multi-precision calculator] • Data Organization [Table Look-up] • Block I/O Transfers [Real-Time I/O] • Controller Programs [Traffic Control]
4. **PROGRAM DESIGN METHODOLOGY**
   - Systems analysis • Specifying the program • Design approaches (top-down, structured programming, modular design)

OPTIONS: KEEP THE MICROCOMPUTER SYSTEM

Course 125B: Includes 125A PLUS attendee receives a microcomputer & a 650-page Self-Study Text to take home.
Course 125C: Includes 125A PLUS microcomputer to take home.

NEW! NEW! NEW!

COURSE 136: One Day — FRIDAY

Hands-On Interfacing Workshop

(Limited to current or former attendees of Course 125.)

Utilizing the ICS training microcomputers and additional Interfacing hardware, students will learn both software and hardware for interfacing to the real-world.

In-Class Projects include:

1. Real-Time Interrupt programming (w/Intel 8253 timer)
2. A/D Conversion — A Digital Thermometer
3. DC Motor Control (Open and closed loop)
4. Other (student-option) Interfacing projects

COURSE ENROLLMENT FORM

COURSE HOURS:

Registration: 8:15am
Course Lecture: 9:00am—4:30pm
Special Events: 4:30—6:00pm

In addition to the extensive hands-on exercises of Course 125A and 136, informal microcomputer hardware activities are organized at every course for valuable hands-on experience.

COURSE FEE:

Management Series: (2 days: 111 + 102s)—**$390**
3-day Design Series: (102s + 125A)—**$495***
4-day Design Series: (102s + 125A + 136)—**$595***
Complete Series: (111 + 102s + 125A + 136)—**$695***
Individual Courses: 111 or 102s or 136 —**$195**; 125A—**$395***
*Option 125B—add **$445**; Option 125C—add **$350**

Course Fee Includes: lectures, lecture-coordinated notes, extensive reference materials, luncheon & coffee breaks.
Team/Group Discounts: 10% reduction for three or more participants from the same organization, if invoiced at the same time.

TO ENROLL:

Please fill out, detach and return coupon. A confirmation with complete course details will be forwarded to you.

MAIL TO: **Integrated Computer Systems, Inc.**
4445 Overland Avenue
P.O. Box 2368
Culver City, California 90230

For immediate confirmation, CALL: **(213) 559-9265**

☐ PLEASE ENROLL ME in the following courses:

	2 Day Project Management Series		3 or 4 Day Engineering Design Series	
COURSE	111	102s	125A	136
CHICAGO	☐ Dec 5	☐ Dec 6	☐ Dec 7-8	☐ Dec 9
WASHINGTON D.C.	☐ Dec 12	☐ Dec 13	☐ Dec 14-15	☐ Dec 16
LOS ANGELES	☐ Jan 16	☐ Jan 17	☐ Jan 18-19	☐ Jan 20
HOUSTON	☐ Jan 23	☐ Jan 24	☐ Jan 25-26	☐ Jan 27
DETROIT	☐ Feb 6	☐ Feb 7	☐ Feb 8-9	☐ Feb 10
DENVER	☐ Feb 13	☐ Feb 14	☐ Feb 15-16	☐ Feb 17
BOSTON	☐ March 6	☐ March 7	☐ March 8-9	☐ March 10

NAME _____

JOB TITLE _____

COMPANY _____

MAILSTOP _____

ADDRESS _____

CITY _____

STATE _____ ZIP CODE _____

TELEPHONE (___) _____ Ext _____

PAYMENT: Please indicate method of payment.

☐ Check/M.O. enclosed ☐ P.O. included ☐ Please invoice me

☐ Please put me on your mailing list to receive future Course Schedules.

☐ Please send information on ICS Self-Study Courses.

☐ Please contact me with regard to On-Site Courses.

CIRCLE 117 ON INQUIRY CARD

PRODUCTS

STATIC ELIMINATOR BRUSH

Static charges which build up as a result of paper movement in a computer printer are controlled and eliminated by the static eliminator brush. The self-energized, induction-type device collects all static charges and bleeds them directly to ground to prevent static-caused paperjams. It does not have to be renewed, poses no health hazard for personnel, and is mechanically safe as it cannot damage the computer or moving paper. **Texwipe Co,** Hillsdale, NJ 07642.
Circle 255 on Inquiry Card

DISC AND MAG TAPE CARTRIDGE DRIVES



First of two components for model 4000 series interactive timesharing systems, the 4460 disc drive replaces the 7.5M-byte drive previously incorporated in the 4000/15 and provides 10M bytes of nonremovable formatted storage. The 4560 mag tape cartridge drive provides 10M bytes of storage on a compact 3M-type cartridge, using a recording density of 6400 bits/in. Cartridge drive allows programmatic backup of disc data to tape, and recovery of tape data to disc unit. **Basic Timesharing Inc,** 870 W Maude Ave, Sunnyvale, CA 94086.
Circle 256 on Inquiry Card

BELL-COMPATIBLE ACOUSTIC COUPLER/MODEM

AJ 1245, a Bell-compatible 103 and 202 mode coupler and modem in one unit, is designed to optimize the transfer of low and medium speed data over normal voice grade telephone lines using an ordinary telephone handset. It interfaces with any EIA terminal and communicates acoustically at 0 to 450 baud in 103 mode and 0 to 1200 baud in 202 mode. The coupler automatically adjusts baud rate and interface protocol so that the user may switch select between these two modes. **Anderson Jacobson, Inc,** 521 Charcot Ave, San Jose, CA 95131.
Circle 257 on Inquiry Card

I/O BUS INTERFACE LINE PRINTER CONTROLLER

Capable of driving three printers simultaneously, the S-10 controller is designed for DECsystem-10 to operate with printers from 600 to 1500 lines/min. The 5.25" (13.34-cm) high unit can be installed in unused space in the computer. No special programming is necessary. Compatible with KA, KI, and KL processors, the controller is also software compatible with all operating systems. Power supply, mounting brackets, printer cables, and operations and maintenance guide are included. **Southern Systems, Inc,** Fort Lauderdale, FL 33308.
Circle 258 on Inquiry Card

1⅛" DIAMETER FAN

Minimax™ 9-frame cooling fan for high density electronic packages measures 1.125" (28.57 mm) diam and approx 1.5" (38.1 mm) thick, with a capacity of 12 ft^3/min (0.34 m^3/min) at free delivery. Impeller and correctional vanes are of airfoil construction for max aerodynamic efficiency and min noise level. It is applicable to small air moving devices capable of delivering required air flows at high back pressures. It operates in amb temps from −55 to 100°C. **Rotron, Inc, an EG&G Co, Custom Products Div,** Woodstock, NY 12498.
Circle 259 on Inquiry Card

Smallest industrial direct digital readout Elapsed Time Indicator?



The only big thing about it is its easily read 4-digit hourly display

Our Series 49200 Elapsed Time Indicator is the smallest industrial direct digital readout ETI we've ever made. It may be the smallest anyone has ever made. It measures a mere 3⅞" sq. x 1¼" long—a real space-saving way to monitor operating time in business machines, computers, peripherals and other equipment where space is limited. Despite its small size, it's exceptionally accurate, and the .075" high 4-digit hourly display is readily legible. An automatic tamper-proof latching memory stores elapsed time indications that can't be lost in event of power failure. Where size is important, the Series 49200 can be one of your best values ever. It's powered by a 1W synchronous motor, 115V ac, 60 Hz. Front or side readout. Surface or through-panel mount.

Send for information today!

NORTH AMERICAN PHILIPS CONTROLS CORP.
Cheshire, Conn. 06410 • (203) 272-0301

You've been looking for a more reliable solid-state relay.

Just look at this one.

A unique combination of dv/dt snubber, fusible-link protection in the trigger circuit, plus an overdesigned triac—all combine to protect against catastrophic system failure should the triac fail to turn on.

Either zero-voltage or non-zero-voltage switching, both types rated for maximum ac load currents of 5A or 10A. Any control voltage from 3 to 32V dc; all models compatible with TTL, DTL, CMOS logic. Solder-pin, quick-on, or screw terminals.

Call (609-882-4800) or write for further information. Heinemann Electric Company, Brunswick Pike, Trenton, NJ 08602.

HEINEMANN

We keep you out of trouble.



©Heinemann 6961

Suffering from temporary loss of memory?

Try the Fabri-Tek core remedy.

If you're like some people who've been on a straight semiconductor memory diet, you've probably been experiencing severe complications. Loss of memory when power is removed. "Soft" random errors that can't be diagnosed. Temperature sensitivity. Added cost and complexity of error detection and correction schemes and battery back up.

For no added cost, core memories provide greater reliability, maintainability, non-volatility and 20 years of proven technology. They're relied upon in process control and a lot of other demanding applications where a failure could be catastrophic. Take our Model 698: 64K bytes of 650 nsec cycle time and 250 nsec access time. You can build a system up to 512K bytes. (Micro 3000 compatible, too). Maybe its time you kicked the semiconductor habit. We're ready to help.



TELL ME MORE

☐ Model 698-32K X18 System ☐ Model 696-16K X18 System ☐ Future requirement
☐ Bulk Core Systems ☐ 30-90 day requirement ☐ Send literature
☐ Special memory needs ☐ Have salesman call

Name and Title

Company

Address

City, State, Zip

Phone

FABRI-TEK INC.
COMPUTER SYSTEMS

5901 South County Road 18 • Minneapolis, MN 55436 • (612) 935-8811

Boston, MA (617) 969-5077
Chicago, IL (312) 437-4116
Hawthorne, CA (213) 973-0484
San Jose, CA (408) 246-8391
Dallas, TX (214) 234-8438
Houston, TX (713) 467-4373
United Kingdom Maidenhead 37321-4

CIRCLE 121 ON INQUIRY CARD

PRODUCTS

SMALL COMPUTER HARD DISC



A hard disc for small computers, the C-D74 provides a 35-ms avg access time to any of 74M bytes of information. With 12 tracks on a cylinder without reseeking, the disc can access any of 220k bytes of information in 5 ms. Winchester technology allows the drive to run 24 h/day without disc wear. Unit has a 10-ms single-track seek and data transfer rate of 7.3M bits/s. A nonremovable, sealed chamber drive features a rotary arm positioner. **Ohio Scientific,** Hiram, OH 44234.
Circle 260 on Inquiry Card

TIME DIVISION MULTIPLEXER

A bit-leaved time division multiplexer meets requirements of both national and international Telex, as well as national data networks. For Telex operations, the B101 provides typ configurations of 46 channels operating at 50 to 300 baud. A universal card interfaces with terminals or Telex exchanges, using any char code. It can handle three independent high speed lines, and provides aggregate rates from 1.2k to 9.6k bits/s. In data networks, the unit operates as fast as 64k bits/s over the three independent lines. **Timeplex, Inc,** 100 Commerce Way, Hackensack, NJ 07601.
Circle 261 on Inquiry Card

INTELLIGENT MULTIPURPOSE PRINTER

For applications requiring both printing and computing capabilities, the IPS-7200[R] microcomputer-based intelligent printing system generates variable-sized char without requiring host computer programming. It can function as a label printer, general-purpose output printer, or programmable microcomputer. Combining a 120-char/s serial printer and 8-bit microcomputer system, the unit includes an RS-232-C asynchronous communications interface; a 20-mA current loop interface is optional. **Dataroyal, Inc,** 235 Main Dunstable Rd, Nashua, NH 03060.
Circle 262 on Inquiry Card



WIREWRAPPABLE INTERFACE BOARDS

Series CIP4 and CIP4/11 wirewrappable boards for interfacing with DEC LSI-11 microprocessor and PDP-8/11 minicomputers plug directly into, and are bus-compatible with, std DEC Omnibus and Q-Bus systems. Boards provide 32 col of 60 low profile socket terminals/col, with alternate rows of committed ground and voltage wirewrappable terminals. Up to 110 16-position IC chips or an equivalent mix of 14-, 16-, 18-, 22-, 24-, 28-, 36-, or 40-position IC chips are accommodated. Boards are available in dual, quad, and hex sizes. **Garry Manufacturing Co,** 1010 Jersey Ave, New Brunswick, NJ 08902.
Circle 263 on Inquiry Card

RIGID TORQUE* FLEXIBLE COUPLINGS
for mechanical and electromechanical precision rotary control.
(actual sizes)



- 500 Models
- Low Cost
- Long Life
- Disc & Oldham Type Couplings in all Sizes and Combinations
- Smooth Shaft Rotation
- *No Energy Storage

FREE CATALOG

RENBRANDT, INC.
659 Massachusetts Ave.
Boston, Ma. 02118
617-445-8910

CIRCLE 122 ON INQUIRY CARD

Buzzzz.
(Write for new catalog.)

Solid state electronic MICRO-BUZZER from CITIZEN: High reliability, competitively priced with immediate delivery.

A complete range: **SMB** 1.5, 6, 12, 24, VDC
RMB 3, 6, 12, 24, VDC
IMB (Intermittent) 6, 12, VDC

CITIZEN
CITIZEN AMERICA CORPORATION
1710 - 22nd St.
Santa Monica, CA 90404
Toll Free (800) 421-6516
In Calif. (213) 829-3541
TWX: (910) 343-6450

Name
Company
Address
City State
Zip Phone

CIRCLE 123 ON INQUIRY CARD

Our first SBC 80 compatible systems for 1977!

Visit us in Booth 121-123, Mini/Micro 77 December 6-8, Anaheim, CA

4K to 64K RAM Up to 8K EPROM on one board

Now you can have RAM and EPROM on the same board and buy as much or as little memory as you need. And because our memories use 16 pin memory element sockets you can change your memory when you change your mind.

Speaking of changing your mind, when you want to change address locations of either RAM or EPROM, it's done with two, on-board switches—providing 16 possible start locations for each memory.

Compare these features with our much improved read, write and refresh cycle times and you'll choose MSC first.

16K RAM Version

Up to 16K × 8 of RAM and up to 8K × 8 of EPROM on the same board.

RAM expandable in 4K × 8 increments and EPROM expandable in 1K × 8 or 2K × 8 increments.

On-board DIP switches to select any of 16 address start locations for RAM and 16 address start locations for EPROM.

Cycle times:
Read, 350 nsec.
Write, 500 nsec.
Refresh, 500 nsec.

Totally SBC 80 and Intellec MDS hardware and software compatible.

Limited one year warranty on parts and labor.

Delivery 30 days ARO.



MSC 4602

64K RAM Version

Up to 64K × 8 of RAM and up to 8K × 8 of EPROM on the same board.

RAM expandable in 16K × 8 increments and EPROM expandable in 1K × 8 or 2K × 8 increments.

On-board DIP switches to select any of 16 address start locations for RAM and 16 address start locations for EPROM.

Cycle times:
Read, 350 nsec.
Write, 500 nsec.
Refresh, 500 nsec.

Totally SBC 80 and Intellec MDS hardware and software compatible.

Limited one year warranty on parts and labor.

Delivery 30 days ARO.



MSC 4502

Beginning firsts

Beginning with compatible memories, Monolithic Systems will continue to introduce SBC 80 systems with features which are firsts.

First to take advantage of the latest technology. And first in reliability, value and delivery.

You can be among the first, when you call us for SBC 80 compatible systems.

SBC 80 compatible systems... from the first.

Monolithic Systems corp.

14 Inverness Drive East
Englewood, CO 80110
303/770-7400

Intellec is a registered trademark of Intel Corporation.

©1977, Monolithic Systems Corp.

PRODUCTS

PROXIMITY-OPERATED ACCESS CONTROL SYSTEM

Model 414 operates by proximity; credit-card-sized command key cards activate access doors when held within 4" (10 cm) of a concealed sensor. The system controls access for up to eight locations; it includes electronic control unit, sensors, system programmer, command keys, and optional printer. Program unit has memory capacity for more than 1000 individual key codes. System can be reprogrammed to prevent use of lost key card. System printer can log all accesses. **Schlage Electronics,** 1135 E Arques Ave, Sunnyvale, CA 94086.

Circle 264 on Inquiry Card

THUMBWHEEL SWITCHES

Suited to programming of data processing, numerical machine control, and manufacturing process control systems requiring readily-altered digital input information, the Metal-Mite thumbwheel switches feature one to 20 stations; 8-, 10-, 12-, and 16-position modules; and large, easy-to-read thumbwheel nomenclature. Typ codes offered are decimal, BCD, octal, BCO, and hexadecimal. Four types of rear mounting are switch modules only, without bezel, with bezel, and with escutcheon. **Switchcraft, Inc,** 5555 N Elston Ave, Chicago, IL 60630.

Circle 265 on Inquiry Card

REAL-TIME DIGITAL LOGIC ANALYZER

Model RK 778 8-channel logic timing display works with any triggered oscilloscope to catch and display on all channels pos or neg going glitches <13 ns. Glitch width display control is adjustable. Eight channels of input are sampled by internal adjustable or external clock. It can be used in an alternate mode self-triggered. Features include 8-channel combinatorial trigger for jitter-free display, Schottky buffered inputs, and regulated supply. **Kenmark Development Group, Inc,** 6 Meadowlark Dr, East Northport, NY 11731.

Circle 266 on Inquiry Card

BASIC I/O DRIVER

I/O driver controls up to four cassette recorders, allowing BASIC programs to read records from and write records to cassette tape under program control. Patched to/from BASIC, the driver handles all I/O to either cassette operating system or console. The controller, which plugs into a single Tarbell interface board, is available as a 4- or 2-port kit. Software includes cassette operating system, BASIC I/O driver and listing, and assembler with patches to assemble large programs from tape. **Ro-Che Systems,** 7101 Mammoth Ave, Van Nuys, CA 91405.

Circle 267 on Inquiry Card

DC RECORDER WITH EDGE PRINTER

For use in portable systems to be powered from 12 Vdc and for systems where electronic isolation from line power is required, the M1-50 DCM recorder module has a 50-mm chart width, power consumption of <8 W, and four chart speeds of 5, 10, 25, and 50 mm/s std. Frequency response is dc to 110 Hz at 10 mm pk-pk. It is available as a mechanical recorder or with electronics, and can be equipped with optional alphanumeric edge printer with a 5 x 7 dot matrix. **MFE,** Keewaydin Dr, Salem, NH 03079.

Circle 268 on Inquiry Card

FREE

The New Minicomputer Accessories CATALOG

40 pages loaded with hundreds of standard (but hard to find) products needed to support your minicomputer installation—Disk Cartridges, Mag Tape, Floppy Disks, Carrying Cases, Binders, I/O Connectors and Cables, Racks and a great deal more.

IMPROVE ORGANIZATION AND EFFICIENCY with ideas found on every page . . . money and time-saving products and ideas that help you beat the high cost of repetitive tasks and misplaced data.

Call **(415) 969-5678** or write for MCA Catalog.

A FULL, NO-NONSENSE GUARANTEE on all MCA products assures your satisfaction or we'll take it back. And every MCA product is field-proven before we offer it in our catalog. Only by providing products of the highest quality are we able to offer a no-strings guarantee.

SAME DAY SHIPMENT of many of our products gets them to you within 24 hours. Last year MCA met a New York customer's need for custom cables with delivery and installation by 7 a.m. the next morning.

Write or call for your free catalog **(415) 969-5678.** Please advise minicomputer make and model.

MCA MINICOMPUTER ACCESSORIES

1015 Corporation Way, P.O. Box 10056-M, Palo Alto, CA 94303

D-C GEARMOTOR RELIABILITY • PERFORMANCE • ECONOMY

Pittman miniature gearmotors are built in two series having gearbox diameters of 1⅜" and 2" with overall body lengths from under 3" to 3¾", depending on choice of motor section. Gears are sintered iron to precision tolerances, providing low backlash for computer peripheral, instrumentation, and other demanding applications.

Many possible combinations of armature windings and gear ratios permit tailoring of outputs to a wide range of performance requirements.

Call or write now for detailed specification sheets or a specific recommendation for your design.

959

PITMO

THE PITTMAN CORPORATION

A Subsidiary of Penn Engineering & Manufacturing Corp.
HARLEYSVILLE, PENNSYLVANIA 19438
Phone: (215) 256-6601 TWX: 510-661-8696 c 1977

CIRCLE 126 ON INQUIRY CARD

CIRCLE 127 ON INQUIRY CARD

If you wait until 1978, you'll see some new 150 and 300 lpm band printers.

If you order a field-proven Printronix impact matrix line printer today, you'll get unbeatable print quality plus full plotting capability for the same price...or less.

And we'll ship it tomorrow.

Read about the new 150 and 300 lpm band printers scheduled for delivery sometime next year? Supposedly, they'll be in the same low price range as Printronix 150 and 300 lpm impact matrix line printers. But good as they might be, they'll never be able to match the utility and value of Printronix Printer/Plotters.

In the first place, you can't plot with a band printer. A Printronix can plot anything that can be displayed on a CRT. You get this extra capability at no extra cost. Printing and plotting for the same price as a band printer.

What's more, a Printronix gives you a 160 character capacity with no slowdown in print speed. A standard 96 character ASCII set plus your choice of an optional 64 character computer selectable set. No time lost changing bands to print different languages or character styles. And since a Printronix has fewer parts than a band printer, you can count on higher reliability.

Since mid 1975, we have shipped more than 3,000 units. They're field proven. And we are tripling our production capacity. So you won't have to wait 6 to 9 months to get the best buy in printers. Order one today and we'll ship it tomorrow!

Printronix, Inc., 17421 Derian, Irvine, California 92714
Call us at (714) 549-8272

CIRCLE 128 ON INQUIRY CARD





PRINTRONIX...

Your chance to beat the band.



THE GREAT 4K STATIC RAM RACE

In a world of claims and counter-claims, one thing is clear. EMM SEMI is still in the lead. Of course, we not only had a healthy head start, but we field a whole family of 4K static RAMs.

We *delivered* the industry's first 4K static RAM in 1975, a full year and a half before anyone else. We are now delivering 7 basic static RAM types with many versions of each, and producing them at a greater monthly rate than our nearest competitors combined.

By now we have more 4K static RAMs operating in a wider range of customer equipment than anyone else in the semiconductor memory business — from 10 Megabyte IBM add-on memory systems to hobbyist microprocessor kits.

Whatever your application, from mass storage to telecommunications, from medical electronics to toys and games, chances are there's an EMM SEMI static RAM just right for you. Please call or write today for full details — and ask about our byte oriented RAMs, too.

Memory at work EMM SEMI, Inc.

a subsidiary of Electronic Memories & Magnetics Corporation • 3883 N. 28th Avenue, Phoenix, Arizona 85107 • (602) 263-0202

CIRCLE 129 ON INQUIRY CARD

PRODUCTS

AUTOMATIC μP-BASED RLC TESTER



An automatic impedance component tester with keyboard control and internal microprocessor, the 1658 Digibridge™ measures R, L, C, D, and Q of resistors, capacitors, coils, and other components at a selectable frequency of 1 kHz or 120 Hz. Basic accuracy is 0.1%. No calibration is required. Ten limit comparison bins are available for sorting; either symmetrical or asymmetrical limits can be entered through the keyboard. Three different test speeds up to 7 measurements/s are selectable. Test modes are continuous for repetitive measurements, single, and average. Providing a running average of 10 successive measurements, average mode smooths noise or slight variations due to unstable components from one measurement to another. **GenRad, Inc,** 300 Baker Ave, Concord, MA 01742.
Circle 269 on Inquiry Card

MEMORY MANAGEMENT CONTROL PROCESSOR

MM CP400 contains hardware for dynamic memory mapping and an architectural design which offers convenient memory expansion to 128k. Designed for use with the company's LN5400 process control computer systems, the equipment is based on the the CP400 control processor. Features include dual processing units, CPU and IOP; control storage to support high speed operation of CPU and IOP; modular architecture; general-purpose registers, real-time clocks, and direct I/O interface; and programmer's control panel. The IOP processor's high data transfer rate permits large quantities of data to be processed and transmitted without taking time away from real-time control. **Leeds & Northrup Co, Systems Group,** Dickerson Rd, North Wales, PA 19454.
Circle 270 on Inquiry Card

MINI/MICROCOMPUTER STANDALONE PRINTER

Suited for terminal applications or as standalone printers, DP-1000 series digital printers feature a dot-matrix impact printing element capable of producing 64 alphanumeric and special symbols in 40-char lines at 1.25 lines/s on std single or multiple-copy paper rolls.



Three basic ASCII configurations, conforming generally to EIA RS-232-C, allow interfacing to most minicomputers, modems, and the current drive mode of Teletype® printers. Std baud rates from 110 to 2400 are available. All models have internal storage. Single or double-width characters may be selected via an external control line, allowing either 6 or 12 char/in (2.4 or 4.7/cm) to be intermixed on a line. **Anadex,** 9825 DeSoto Ave, Chatsworth, CA 91311.
Circle 271 on Inquiry Card

business machine **clutches & brakes**

Warner Electric business machine clutches and brakes are specifically designed for high cycle rate duty, fast response and long life.

Applications include: • copying machines • automatic currency changers • sorting equipment • printers • photographic equipment • document handling.

Warner has the capability to provide a single prototype design or the highest volume production requirement at competitive prices.

NEW! holding brakes



Warner Electric also offers a new, complete line of electrically released, spring set brakes in a wide range of torque capacities, operating voltages and mounting configurations. Typical application use: spindle/disc brake for disc pack drives.

Send for catalog and technical information.

WARNER ELECTRIC
Brake & Clutch Company
Beloit, WI 53511 • Telephone: 815/389-3771

WARNER ELECTRIC

CIRCLE 131 ON INQUIRY CARD

Raymond

will ship over 10,000 small digital tape drives this year. To more than 100 customers!

We manufacture:

Model 6406 Raycorder

for Philips cassettes — the industry standard for more than 6 years.



Model 6409 Mini-Raycorder

for ANSI X3B5/77-22 Mini-Data cassettes — the first in the industry. Now added features make it even better — the runaway leader in its class.



Model 6413 Cartridge Raycorder

for ¼-inch data cartridges. A new offering this year from Raymond — a new package with a proven track record.



Shouldn't you be buying the best? From the small tape drive experts —

Raycorder Products Division

Raymond Engineering Inc.

217 Smith Street, Middletown, Connecticut 06457, (203) 632-1000

a subsidiary of Raymond Precision Industries

CIRCLE 132 ON INQUIRY CARD

PRODUCTS

POCKET-SIZED PROGRAMMABLE CALCULATOR WITH BUILT-IN PRINTER



Keystroke programmable HP-19C features 98 fully merged program steps, continuous memory, full editing and programming functions, 30 data storage registers, and a quiet thermal printer. Editing and programming functions include backstep, insert/delete, single step, pause, and a total of 10 decision tests. The printer records the contents of program memory, data storage, and operational registers; and is useful in program debugging. User may select from three operating modes—manual: printer operates only when print x key or list function is operated; normal: all entered data and functions are recorded; and trace: step number, function, each step of executing program, and results of manual calculation are printed. **Hewlett-Packard Co,** 1507 Page Mill Rd, Palo Alto, CA 94304.

Circle 272 on Inquiry Card

10-CHANNEL PROBE POD LOGIC ANALYZER ACCESSORY

A high performance active probe pod which detects combinational triggers from up to 36 signals when used with the company's logic analyzers, the 10-TC is particularly useful for troubleshooting microprocessor-based circuits. Ultraminiature clips can be connected to IC pins without the need for DIP clips; leads between pod and clips are light, flexible, and color-coded. By connecting the pod between analyzer and circuit, high input impedance, combinational trigger with qualifiers, clock qualifying, and independent threshold detection are combined. Power is provided by the analyzer. Device may be used to form a convenient signal interface or to expand combinational trigger capability up to 36 channels. **Biomation,** 10411 Bubb Rd, Cupertino, CA 95014.

Circle 273 on Inquiry Card

FULL FEATURE PROGRAMMABLE CONTROLLER

The 484 includes typical capabilities of relay logic, timing, and counting, and provides 1.0-, 0.1-, and 0.01-s time base timers. Other features are full arithmetic capability (including add, subtract, multiply/divide), internal coils, 16-bit binary registers, ability to generate reports to hierarchical computers, and two built-in 128-step sequencers which enable the unit to be used where drum-type programmers or stepping switches have previously been used. I/O expansion is possible in increments of four points from 8 to 512 I/O points. The expanded version has a memory capacity of 4096 words. The controller's 5" CRT multinode panel can display up to 77 circuit contacts at a time; up to seven complete ladder diagram rungs can be shown at once. **Gould Inc, Modicon Div,** PO Box 83, SVS, Andover, MA 01810.

Circle 274 on Inquiry Card

NEW!

...the MSC-300



The MSC-300...now available in the same simple, trouble-free design as the other clutches in our MSC Series.

Size for size the PSI Magnetic Spring Clutch (MSC) offers considerably more torque than conventional electric clutches.

features:

- A complete package ready for immediate installation
- Low cost
- Availability of standard D.C. voltages
- Self-lubricating powdered metal parts
- Wide range of applications

also:

- Bore sizes up to 1"
- 3¼" maximum O.D.
- Torque ratings to 250 lb. in. (static)

WARNER ELECTRIC

PSI DIVISION
WARNER ELECTRIC
Brake & Clutch Company
Pitman, N.J. 08071 • Telephone: 609-589-0815

CIRCLE 133 ON INQUIRY CARD

Low Profile...

LED lighted keys give visual indication of status function. Or choose unlighted keyboard.



10, 12, or 16 station. Square or round keys. Attractive color selection. Clear, sharp key top or decal marking.



Universal circuit and pin-outs interface with most logic. Easy front mount. Standard units available from stock.



Design your own keyboard. Single station modules mount on PC or prepunched boards with .100 center holes.



STACOSWITCH
a STACO, INC. company
1139 BAKER STREET, COSTA MESA, CALIF. 92626
(714) 549-3041 TWX: 910/595-1507

Other STACO Company products: Custom Transformers, STACO, INCORPORATED, Richmond, Indiana; Variable Transformers, STACO, INCORPORATED, Dayton, Ohio.

PRODUCTS

120-CHAR/S SERIAL DOT MATRIX PRINTER

A 132-col bidirectional, logic-seeking, impact printer, model 702 features a standard 7 x 7 dot matrix pattern (5 x 7, 9 x 7, 7 x 9, and 9 x 9 are options), and prints at 120 char/s. Printed data format consists of 10 char/in horizontally and operator selectable 6 or 8/in vertical spacing with either a 2-, 8-, or 12-channel electronic vertical format unit. Forms handling is tractor feed for rear or bottom feed forms. Paper widths range from 4" (102 mm) to 17.3" (439 mm). The system uses a cartridge containing a continuous ribbon 0.56" (14 mm) wide, 10 yd (9.1 m) long; a mobius loop allows printing on upper and lower portion on alternate passes. Data input is 7- or 8-bit ASCII parallel. **Centronics Data Computer Corp,** Hudson, NH 03051.



Circle 275 on Inquiry Card

CALCULATOR CONTROLLED PROCESS MONITORING SYSTEM

The Digitrend 240 scans and measures up to 1000 points of thermocouples, RTDs, voltages, or process transmitter signals. Each point is automatically digitized, linearized, and converted into engineering units for printing, recording, or passing on to the calculator. Four alarm setpoints may be individually set for each point. With the HP 9825A calculator as control terminal for the monitor, averages, integrals, trends, projections, deviations, and other calculations may be made using measured data. The monitor's control terminal interface is directly compatible with the calculator's RS-232-C interface module. Operation at 1200 baud allows low level analog multiplexing and digitizing rates up to approximately 10 points/s. Calculator keyboard allows entry of monitor commands such as function assignments, setpoint values, and operational commands. **Doric Scientific Div, Emerson Electric Co,** 3883 Ruffin Rd, San Diego, CA 92123.

Circle 276 on Inquiry Card

OFFLINE TERMINAL TESTER

A full-duplex unit that offers split-speed capability (ie, both character generator and receiver can operate at different speeds), the PMK04 can be carried to remote locations for testing a single asynchronous ASCII terminal or can be used at large installations. In testing, the unit exercises all printer/display functions at all transmit/receive speeds; in troubleshooting a fault, each function is tested at each speed until the fault is found. Data selected by front-panel switches are generated, converted to serial data format, parity added if selected, and transmitted to the serial terminal, via EIA voltage levels or the 20-mA DEC-compatible current loop. Characters can be received from the terminal keyboard, parity checked, the ASCII code displayed on the front-panel indicator, and then echoed back to the terminal. **Atlantic Research Corp,** 5390 Cherokee Ave, Alexandria, VA 22314.

Circle 277 on Inquiry Card

GRAPHICS AND IMAGING VIDEO PROCESSOR

Self-contained on a 15 x 15" (38 x 38-cm) PC board that fits into any std Data General Nova or Eclipse computer, the 200-D generates raster-scanned, refresh, graphics, and imaging displays up to 512 x 512 pixels in B/W monochrome or 256 x 256 pixels in 16-level gray scale or color. A writable control store enables all image processing and data formatting routines to be modified under program control from the host computer. This allows instantaneous reallocation of refresh memory between the size of display and levels of intensity displayed. The unit incorporates a high speed bipolar video microprocessor with a cycle time of 100 ns; either the host computer or processor-resident 32k bytes of memory is used to refresh the display. **Lexidata Corp,** 215 Middlesex Tpk, Burlington, MA 01803.

Circle 278 on Inquiry Card

TOUCH SENSITIVE KEYBOARD SWITCHING SYSTEM



Using thick-film techniques to provide a flat, sealed data entry surface for such equipment as electronic POS terminals and scales, the TIP™ (touch-in-panel) system replaces traditional pushbutton switches with a smooth Mylar surface. The entire switching assembly is sealed. Assembly consists of panel, with keyboard printed on the top and contact surface on the reverse side. A circuit isolation mask is sandwiched between the Mylar and a substrate circuit carrier. This subassembly is laid on the end product's housing so that depressing an imprinted button on the Mylar forces the contact material on the back to touch the substrate, making an electrical connection through metal pins to the logic board. **Oak Industries Inc, Switch Div,** Crystal Lake, IL 60014.

Circle 279 on Inquiry Card

PDP-11/70 COMPATIBLE DISC SYSTEM

The DD70 series consists of the Computroller V, an intelligent microprocessor-based disc controller; 4-board PDP-11/70 interface, which plugs into the computer in place of the DEC RH70 Massbus® controller; and a choice of disc drives ranging in capacity from 80M to 300M bytes/spindle. Controller interfaces directly to the computer and communicates directly with its cache bus controller. Replacing DEC RP04 and RP06 drives, the system uses a microprocessor-based emulation package, and is software transparent to all std DEC operating systems. The disc system supports RSTS RSX11D, RSX11M, Mumps, Unix, and DOS operating systems. Error correction is provided for both header and data fields, and transfer rates of up to 1209k bytes/s are supported. **Diva, Inc,** 607 Industrial Way W, Eatontown, NJ 07724.

Circle 280 on Inquiry Card

Stepmotors



Warner Electric, the leading manufacturer of Variable Reluctance step motors, is unique in its capability to respond to the need for a single prototype design or the highest volume production requirement at competitive prices.

Applications include: printers • floppy disc drives • sorting machines • postage systems • photographic equipment • solar panels • paper tape drives • instruments & controls.

Warner VR motors feature high stepping rates, with accuracy within ½°, fast response and high torque-to-inertia ratio.

Standard design models are listed below.

MODEL	STEP ANGLE	STEPS/ REV.	HOLDING TORQUE
SM-024	15°	24	35 to 140 oz. in.
SM-036	10°	36	30
SM-048	7.5°	48	170
SM-060	6°	60	750
SM-072	5°	72	60
SM-080	4.5°	80	750

ROTARY TO LINEAR MOTION TRANSLATION

Warner Electric can also provide a complete range of linear motion devices; high helix screws, ball bearing screws, acme screws and step motor/screw combinations.

Write for catalog and complete technical specifications.

WARNER ELECTRIC
Brake & Clutch Company
Beloit, WI 53511 • Telephone: 815/389-3771

WARNER ELECTRIC

CIRCLE 135 ON INQUIRY CARD

Thinking CRT Cursor Control?



Think Magnetic Trackball.

Librascope's Magnetic Trackball, with integral electronics, provides simultaneous X and Y scalar increments as inputs for digitally driven graphic displays, to position cursors, to add new data, or to modify existing data. Functions are generated by positioning two magnetic encoders with a hand driven ball to generate the orthogonal digital signals.

Designed for harsh environments, Librascope trackballs operate in the temperature range −55°F to +180°F and from sea level to an altitude of 50,000 feet. The unit complies with the environmental specifications of MIL-E-5272, Procedure 1 and MIL-T-5422.

Write or call for complete specifications. The Singer Company, Librascope Division, 833 Sonora Ave., Glendale, California 91201. Telephone (213) 244-6541.

SINGER
AEROSPACE & MARINE SYSTEMS

Librascope's magnetic encoders are the most reliable source of digital signals to represent a shaft angle. They offer long, maintenance free life in the harshest environments. Output signal levels drive TTL integrated circuits without amplification. Special models operate reliably in the temperature range −65°F to +400°F.

CIRCLE 136 ON INQUIRY CARD

PRODUCTS

DIGITIZER INPUT FOR HANDHELD PROGRAMMABLE CALCULATOR



A non-keyboard entry device, SAC® GP-352 consists of a basic Graf/Pen™ TP-3 sonic digitizer, SR-52 calculator, and necessary interface, cabling, and plug-in connector. The system can calculate variables such as area, line length, and volume. In a typical application, a navigation chart is put within the active area of the digitizer's sensor assembly and two points are located on the chart with a handheld stylus or cursor to establish the orientation and scale of the chart. Touching points on the chart with the handheld input device provides automatic scaling and storage. Calculator will display the last position calculation and/or the total of all calculations. **Science Accessories Corp,** 970 Kings Hwy W, Southport, CT 06490.

Circle 281 on Inquiry Card

DATA ACQUISITION ISOLATION AMPLIFIER

Up to eight 286J amps can be driven by a single external synchronizing oscillator; multiple oscillators allow configurations of virtually limitless numbers. An internal isolated dual 15-Vdc at 15-mA supply provides power for external transducers and signal conditioning devices. For industrial data acquisition applications, it provides total ground loop isolation and protection from common-mode voltages of ±2500-V, continuous, or a max ±6500-V pk, 10-ms pulse. Nonlinearity of ±0.05% at 10-V pk-pk output makes the device suitable for systems requiring 10-bit accuracy. Input voltage drift is ±10 μV/°C; gain stability is 0.001%/1000 h and 0.01%/°C. **Analog Devices, Inc,** Rte 1 Industrial Pk, PO Box 280, Norwood, MA 02062.

Circle 282 on Inquiry Card

HIGH OUTPUT p/ROM PROGRAMMER

Delivering programming rates approaching 1M bytes/h, model 16 simultaneously programs 16 EPROMs, and includes a built-in calibration mode. In addition, it provides fault-finding p/ROM continuity tests and includes automatic pretests of programmer voltages. Automatic checksum sequences are used to test data integrity. The unit includes RS-232-C serial I/O with selectable baud rates, and features an interactive display for ease of operation. Both 2708 and 2716 type EPROMs can be programmed. To change programmer personality, simply replace the socket adapter on the programmer's front panel. A 2k-byte x 8-bit expandable RAM is std, along with RS-232-C serial I/O. **Data I/O Corp,** PO Box 308, Issaquah, WA 98027.



Circle 283 on Inquiry Card

LITERATURE

Flat Cables

Providing data on advantages of flat cable systems and on types of flat cables and terminations available, design guide helps identify potential applications. **Institute of Printed Circuits,** Evanston, Ill.
Circle 330 on Inquiry Card

Floppy Discs

Outlining the storage and handling of floppy discs, pamphlet reviews problems encountered with floppys and offers suggestions on how to prevent loss of data. **Advance Access Group,** Westchester, Ill.
Circle 331 on Inquiry Card

AC and DC Motors

Handbook is devoted to technical information and illustrations, with dimensional drawings and connection diagrams of ac motors, plus dc motors for aerospace military and high performance uses. **IMC Magnetics Corp,** Westbury, NY.
Circle 332 on Inquiry Card

Electronic Products

Catalog describes 400 electronic products in kit form, including personal computing systems, software, and peripherals, as well as a variety of assembled products. **Heath Co,** Benton Harbor, Mich.
Circle 333 on Inquiry Card

Printers/Plotters

Brochure covering line of electrostatic printers, plotters, and printer/plotters has 10 sections documenting applications, throughput, interfacing, and software. **Versatec, a Xerox Co,** Santa Clara, Calif.
Circle 334 on Inquiry Card

Uninterruptible Power Systems

Explaining problems and solutions encountered with computer systems involving power deviations, bulletin presents building block approach using static line voltage regulators, static automatic transfer switches, and UPS. **Cyberex, Inc,** Mentor, Ohio.
Circle 335 on Inquiry Card

Minicomputer Breadboards

32-page catalog describing general-purpose breadboards, connectors, and racks also shows minicomputer interface boards which are compatible with other hardware systems. **Douglas Electronics, Inc,** San Leandro, Calif.
Circle 336 on Inquiry Card

Miniature Circular Connectors

Focusing on 3-point bayonet type connectors of the KPT, KPTM, and KPSE line designed to MIL-C-26482, brochure contains drawings, photos, and data on materials and dimensions, and electrical data charts. **ITT Corp, Cannon Electric Div,** Santa Ana, Calif.
Circle 337 on Inquiry Card

Solid-State Lightpens

Catalog contains specs and definitions of specification terminology to aid designer in selecting units according to application needs. **Information Control Corp,** Los Angeles, Calif.
Circle 338 on Inquiry Card

Inductive Proximity Controls

Discussion of proximity sensing, applications, electrical specs, and information on mounting brackets, conduit fittings, and interfacing are highlighted in catalog covering line of solid-state proximity sensors, switches, and control systems. **Turck Multiprox, Inc,** Minneapolis, Minn.
Circle 339 on Inquiry Card

Sealed Component Sockets

Data sheet gives specs, diagrams, and features for NC machine insertable component sockets with silicone rubber seal. **AMP, Inc,** Harrisburg, Pa.
Circle 340 on Inquiry Card

Flat Cable Connectors

PCB, female socket, header, DIP, and card edge connectors for ribbon cable applications along with Cee Wee™ connectors are featured in catalog comprised of selection guide, assembly instructions, dimensional drawings, and specs. **CW Industries, Inc,** Warminster, Pa.
Circle 341 on Inquiry Card

Universal Data Converter

In addition to complete applications data, bulletin provides specs, systems diagram, features, and operation characteristics of DC-6 parallel-to-serial universal data converter. **Science Accessories Corp,** Southport, Conn.
Circle 342 on Inquiry Card

Terminals

Photos illustrate color brochure consisting of specs and features of the Dasher™ 60- and 30-char/s printers and display terminals. **Data General,** Westboro, Mass.
Circle 343 on Inquiry Card

It's What's Inside That Counts



Fenner

Fenner RUSCO BELTING

"40 DP" TIMING BELTS

Recommended for light duty fractional horsepower applications Fenner "40 DP" timing belts offer the ultimate in synchronized engagement and precision performance. These belts have excellent flex as well as resistance to abrasion, ozone and oil. The slip-proof feature provides continuous accuracy and reduces strain on bearings as compared to flat belts or V-belts. Constant pulley gear contact insures smooth drive and minimum wear.

Fenner

FENNER AMERICA
400 East Main St.
Middletown,
Conn. 06457
Tel: 203-346-7721

CIRCLE 137 ON INQUIRY CARD



1024 BYTES ...and it still works

The Kilobyte Card™. Over 1024 8-bit bytes of program/data storage, for microprocessor-based applications from electronic games to intelligent terminals. Fully compatible with Vertel's field proven Reader/Encoders. As small, light, portable, durable and mass-producible as a credit card. Cheaper than a pacifier.

VERTEL

167 Worcester St. • Wellesley Hills, MA 02181 • Tel: (617) 235-0294 • TWX: (710) 383-6519

CIRCLE 138 ON INQUIRY CARD

The Micro Memory product line is still growing!

HERE'S OUR LATEST ADDITION

LSI-11 Dynamic 32K Mos Memory



- Provides 8K, 16K, 24K, or 32K in a single option slot.
- Completely hardware and software compatible with LSI-11 microcomputers.
- Addressable in 4K word increments.
- Available with on board refresh or external refresh.
- Provision for battery backup.
- One year warranty on parts and labor.

micro Memory Inc

9438 Irondale Ave.
Chatsworth, California 91311
Telephone: (213) 998-0070

CIRCLE 139 ON INQUIRY CARD

LITERATURE

Micro/Minicomputers

Highlighting software, system packages, and applications, *PDP-11 Variations On A Theme* presents an overview of the computer family from entry level microprocessors to the "supermini" PDP-11/70. **Digital Equipment Corp,** Maynard, Mass.
Circle 344 on Inquiry Card

A-D, D-A Peripherals

Depicting electrical and mechanical parameters and programming considerations on the SineTrac 800 series, brochure includes block diagrams, details of diagnostic test programs, and programming methods. **Datel Systems, Inc,** Canton, Mass.
Circle 345 on Inquiry Card

Low Profile Switch Modules

Listing features, applications, operating characteristics, and specs, product sheet also provides force displacement curves for current sinking, pulsed, logic scan, and LED modules. **Micro Switch,** div of Honeywell, Freeport, Ill.
Circle 346 on Inquiry Card

Capacitors

Specs, temp characteristic graphs, and dimensional diagrams constitute catalog listing of miniature aluminum electrolytic, metallized polyester film, mylar, ceramic, and tantalum capacitors. **TransCap,** El Cajon, Calif.
Circle 347 on Inquiry Card

ATLAS Syntax Standard

Standard delineates the syntactic structure of the ATLAS test language in Backus Naur format, and offers a formal definition. IEEE Std 416A-1976 is available for $10 ($9 for members) plus $2 for shipping from **IEEE Service Ctr,** 445 Hoes Lane, Piscataway, NJ 08854.

Small Business Computers

All About Small Business Computers serves as a selection guide with comparison charts and detailed specs covering assorted computer systems. Price is $12/copy. **Datapro Research Corp,** 1805 Underwood Blvd, Delran, NJ 08075.

μC Programming and Interfacing

Bugbooks V and VI introduce the basics of 8080A microcomputer programming and instructions, and integrate the concepts into a treatment of 8080A interfacing with lab experiments and text review. Price is $9.50/book. **E & L Instruments, Inc,** 61 First St, Derby, CT 06418.

GUIDE TO PRODUCT INFORMATION

NOTE: The number associated with each item in this guide indicates the **page** on which the item appears—**not** the reader service number. Please do **not** circle the page number on the reader service card.

PAGE

MATERIALS

INSULATING MATERIALS

Glass Coating for Electronics
Glasflex **221**

PLASTICS AND PLASTIC FORMS

Structural Foam
General Electric/Plastics **151**

HARDWARE

BREADBOARDS

Breadboard
A P Products 190

CONNECTORS AND INTERCONNECTION SYSTEMS

Connectors
Amphenol North American/ Bunker Ramo **65**
GTE Sylvania/Connector Products **113**

PC Connectors
Viking Industries **165**

Flat Cable Connector Systems
3M **117**

FANS AND BLOWERS

Miniature Fan
Rotron EG & G/Custom Products 202

INDICATORS; READOUTS; DIGITAL DISPLAYS; LAMPS

LED Displays
Chicago Miniature Lamp Works/ General Instrument 180
Digital Components 196

Gas Discharge Display
Beckman Instruments 182

PANELS AND BACKPLANES

Logic Panels
Mupac **174**

Wirewrappable Interface Boards
Garry Manufacturing 204

Militarized Backpanel System
National Connector/Fabri-Tek 190

PARTS

Flexible Couplings
Renbrandt **204**

Timing Belts
Fenner America **215**

PC BOARDS

Wirewrap PCBs
Artec Electronics 184

SHIELDING

Shielding Components
Instrument Specialties **196**

COMPONENTS AND ASSEMBLIES

CAPACITIVE COMPONENTS

Ceramic Capacitors
Union Carbide/Components **196**

DELAY LINES

Variable Delay Line
Kappa Networks 188

PAGE

MOTORS; ROTATIVE COMPONENTS

Motors
Canon U.S.A./Electronics Components **176**
Micro Switch/Honeywell **128, 129**

Gearmotors
Pittman **206**

Brakes and Clutches
Warner Electric Brake & Clutch **209, 211, 213**

PHOTODEVICES; PHOTODEVICE ASSEMBLIES

Photoelectric Scanner
Banner Engineering 182

POWER SOURCES, REGULATORS, AND PROTECTORS

Power Supplies
ACDC Electronics **189**
Alpha Power 178
Power/Mate **194**
Power One **8, 9**
Standard Power 188

Switching Power Supplies
Elpac Electronics **193**
Gould/Electronic Components ..... **Cover III**

Voltage Regulators
GenRad **198**

AC Line Regulator
Power-Matic 182

Power Line Disturbance Monitor
Consultronics 198

RELAYS

Solid-State Relays
Heinemann Electric **202**
Teledyne Relays 196

SENSORS; TRANSDUCERS

Audio Indicators
Citizen America **204**

SWITCHES

Switches
Micro Switch/Honeywell **128, 129**

DIP Switches
AMP **54, 55**
Stanford Applied Engineering 184

Pushbutton Switches
Grayhill **142**
Micro Switch/Honeywell **37**
Omron Electronics/Control Components 198

Pushbutton Switch Assembly
Centralab Electronics/Globe-Union 194

Rotary-Pushbutton Switch
American Solenoid 198

Pushbutton Thumbwheel Switch
Cherry Electrical Products 198

Thumbwheel Switches
Switchcraft 206

Hall-Effect Electronic Switch
Texas Instruments/Components 196

CIRCUITS

ARITHMETIC CIRCUITS

Microhybrid 2-Quadrant Dividers
SGR 178

PAGE

CIRCUIT CARDS AND MODULES

Microcomputer System Modules
Plessey Microsystems/ Microcomputer Products 134

Microcomputer Auxiliary Modules
Micronics 144

Core Memory Boards
Fabri-Tek **203**
Micro Memory **216**

Semiconductor Memory Boards
Intel Memory Systems **170, 171**, 196
Monolithic Systems **13,** 184, **205**

RAM Board
Processor Technology 184

p/ROM Card
MilerTronics/George Miler 186

Flexible Disc System Card
Micro Systems Development 140

Interface Module
RBI Systems 198

Output Boards
Burr-Brown 134

I/O Controller Board
I O R 192

Printer Controller Boards
MDB Systems **184**

Graphics/Imaging Video Processor
Lexidata 213

Data Acquisition Board
ADAC 188, **190**

Logic Analyzer Board
Paratronics 174

Modular Scanner
San Diego Instrument Laboratory 180

DIGITAL AND INTERFACE INTEGRATED CIRCUITS

IC Design Kit
Interdesign 164

Logic ICs
Harris Semiconductor **83**
Motorola Semiconductor Products **122, 123**

CMOS Processor
Motorola Semiconductor Products 156

Microprocessor
NEC Microcomputers **135**

Microcomputer Chip
Rockwell International/ Microelectronics **154, 155**

Microcomputer Family
Panasonic Electronic Components 134

Multipliers
Monolithic Memories 162
TRW LSI Products **157**

4k RAMs
EMM SEMI/Electronic Memories & Magnetics **208**

p/ROM
Fujitsu America 164

EPROM
Intel 162

D-A Converter
Advanced Micro Devices 158

A-D Converter
Teledyne Semiconductor 156

GUIDE TO PRODUCT INFORMATION

PAGE

Printer Controller IC
Cybernetic Micro Systems 156

HYBRID CIRCUITS

Hybrid Data Acquisition Systems
Datel Systems 172

LINEAR INTEGRATED CIRCUITS

Switching Regulator IC
Ferranti Electric/ Semiconductor Products 162

PAGE

Isolation and Instrument Amplifiers
Analog Devices 214, **218**

Op Amps
Precision Monolithics 164
Signetics 164
Sprague Electric 164

Signal-Current Loop/TTL Adapter
Connecticut Microcomputer 178

Voltage Controlled Filter
Solid State Music 164

If you have trouble isolating your inputs from your outputs read this book.



This FREE book shows you how to stay out of trouble with low cost Analog Devices isolation amplifiers. Including our latest version, the 286J which offers improved performance for applications in instrumentation, industrial and bio-medical applications. This new design features multi-channel capability for applications in multi-channel data acquisition systems ranging from 2 to over 1000 isolated data points. ($37 in 100's)

CD-11

ANALOG DEVICES

P. O. Box 280 Norwood, MA 02062

Please send me your FREE "Isolation and Instrumentation Amplifiers Designers Guide" and 286J data sheet.

Name_____

Title_____ Telephone _____

Company_____

Address_____

City_____ State_____ Zip_____

PAGE

MEMORY/STORAGE EQUIPMENT

FLEXIBLE DISC UNITS

Flexible Disc Drives
PerSci 168
Pertec/Pertec Computer 125
Shugart Associates 96, 97

Flexible Disc Systems
Charles River Data Systems 180
Cyberchron 188
Data Systems Design 199
Ex-Cell-O/Remex 174
Infotek Systems 173
Teleray/Research 186

Flexible Disc System Card
Micro Systems Development 140

Diskette Write Protect Option
Techtran Industries 188

MAGNETIC CORE MEMORIES

Core Memory Systems
Dataram 95
Fabri-Tek 203
Micro Memory 216

MAGNETIC DISC AND DRUM UNITS
(See also Flexible Disc Units)

Disc Drives
Basic Timesharing 202
Diablo Systems/Xerox ..... **Cover IV**

Disc Systems
Diva 213
Ohio Scientific 204
System Industries 175

MAGNETIC TAPE UNITS

Tape Systems
Datum 72

Tape Transports
Cipher Data Products 28, 29
Kennedy 1

Tape Drives
Digi-Data 121
Pertec/Pertec Computer 46, 47
Telex Computer Products 147-149

Cartridge Tape Drives
Basic Timesharing 202
3M/Mincom 160, 161

Cassette Tape Drives
MFE 34, 35

Tape Recorder
Dylon 129

Cassette Recorders
Electronic Processors 152
Raymond Engineering 210

Offline Cassette Recorder
Memodyne 192

Cassette Recorder Controller
Ro-Che Systems 206

Cassette Interface
Wintek 144

OTHER TYPES OF MEMORY/ STORAGE EQUIPMENT

Magnetic Card
Vertel 216

ROM/RAM PROGRAMMERS AND SIMULATORS

p/ROM Programmer
Data I/O 214

SEMICONDUCTOR MEMORIES

4k RAMs
EMM SEMI/Electronic Memories & Magnetics 208

RAM Board Kit
Processor Technology 184

p/ROM
Fujitsu America 164

p/ROM Card
MilerTronics/George Miler 186

EPROM
Intel 162

Semiconductor Memory Systems
Infotek Systems 173
Intel Memory Systems 170, 171, 196
Monolithic Systems 13, 184, 205

INPUT/OUTPUT AND RELATED EQUIPMENT

AUDIO RESPONSE EQUIPMENT

Voice Readout System
Master Specialties 179

COMPUTER PERIPHERALS PAGE

Minicomputer Peripherals
Minicomputer Accessories 206
Plessey Microsystems 138, 139

DATA TERMINALS
(See also Graphic Equipment)

Data Terminals
Perkin-Elmer Data Systems/ Terminals 38, 39, 41

Printer Terminal
Tally ....32 a-h

CRT Display Terminals
Ann Arbor Terminals 192
Applied Digital Data Systems 21
Conrac 181
Wang Laboratories 224

Color CRT Display Terminal
Intelligent Systems 144, 145

Data Terminal Adapter
United Data Services 194

DISPLAY EQUIPMENT
(See also Data Terminals and Graphic Equipment)

Display Monitors
Ball Brothers Research/ Electronic Display 195

Video Display Systems
Micro Systems Development 140

GRAPHIC EQUIPMENT

Graphic Display Terminal
Hewlett-Packard 16, 17

Plasma Graphic Display Terminals
Magnavox Display Systems 169
Interstate Electronics 127

Color Graphic Display Terminals
Industrial Data Terminals 174
Ramtek 69

Graphic Display Systems
Lexidata 222
Ramtek 56, 57

Graphic Digitizers
Science Accessories 214
Talos Systems 105

Coordinate Digitizer
GTCO 224

Position Sensor
Elographics 176

Magnetic Graphic Display Input
Singer/Librascope 214

Light Pens
Information Control 220

Graphics/Imaging Video Processor
Lexidata 213

INTERFACE EQUIPMENT; CONTROLLERS

Intelligent Interface
Associated Computer Consultants 194

Cassette Interface
Wintek 144

Cassette Recorder Controller
Ro-Che Systems 206

Printer Controllers
MDB Systems 184
Southern Systems 202

Printer Controller IC
Cybernetic Micro Systems 156

Line Controller
C. D. Johnson & Associates 190

Data Terminal Adapter
United Data Services 194

Selector Channel Emulation Unit
Information Products Systems 176

KEYBOARD EQUIPMENT

Keyboards
Maxi-Switch 33
Stacoswitch 212

Solid-State Keyboards
Corton/Illinois Tool Works 15
Micro Switch/Honeywell 128, 129

Keyboard Arrays
Grayhill 186

Touch Keyboard Switch Panel
Oak Industries/Switch 213

Keyboard Soundproofing
Gates Acoustinet 68

PLOTTING EQUIPMENT

Digital Plotter
Houston Instrument/Bausch & Lomb 71

Graphic Plotter
Hewlett-Packard 145

Continuous Curve Plotter
Applied Color Systems 194

PRINTING EQUIPMENT PAGE

Printers
Centronics Data Computer 187, 212
Dataproducts 114, 115
Florida Data 98
Lear Siegler/Electronic Instrumentation/ Data Products 163
Teletype 177
Victor Business Products 4

Line Printers
Axiom 141
Houston Instrument/Bausch & Lomb 44
Printronix 207

Chain Printer
C. Itoh Electronics 109

Dot Matrix Printers
Integral Data Systems 186
Syntest 180

Digital Printer PAGE
Anadex 26, 209

Intelligent Printing System
Dataroyal 204

CRT Hard Copy System
Versatec 191

Printer Controllers
MDB Systems 184
Southern Systems 202

Printer Controller IC
Cybernetic Micro Systems 156

Static Eliminator Brush
Texwipe 202

PUNCHED TAPE EQUIPMENT

Paper Tape Equipment
Sweda International/OEM Products 5

Paper Tape Readers
Addmaster 176



THIS BOOK CAN HELP YOU DEVELOP LESS-THAN-PERFECT PRODUCTS

The perfect product satisfies every user's need, and costs nothing to develop, manufacture, or maintain. Less-than-perfect products satisfy some customers and cost something.

Montgomery Phister's new book, ***Data Processing Technology and Economics,*** helps you develop competitive new products having low life-cycle costs.

IT IS A BOOK OF FACTS AND IDEAS.

FACTS ABOUT —

Costs: Manufacturing costs, of electronic assemblies, main memories, peripheral products, and integrated circuits. Preventive and corrective maintenance costs. Hardware and software development costs. User operating costs.

Markets: Populations of computers, peripherals, and data entry equipment. Computer use by various industries. Programming language use. The primary computer applications.

Products: Characteristics and prices for the important computer, peripheral, data entry, data communications, and media products. Hardware and software reliability. System throughput.

IDEAS ON —

Costs: Shows how to set up models to predict development, manufacturing, and maintenance costs. Describes how to break manufacturing costs into component, interconnect, power, and packaging costs. Relates maintenance costs to equipment reliability.

Markets: Discusses the problems of protecting a lease base when introducing a new product line. Provides a new look at the relationship between performance, price, and potential sales — i.e. at market elasticity. Shows how to compare the customer's cost of using a new product with his cost of alternative ways of getting the job done.

Products: Suggests a new way of looking at data processing workloads and system performance. Shows the technological changes which underlie product price/performance improvements.

THESE COMMENTS HELP EXPLAIN WHY THIS BOOK IS SO WIDELY USED BY DEVELOPMENT ENGINEERS AND THEIR MANAGERS:

". . . a vast quantity of information presented in an imaginative series of graphs and charts . . . a veritable gold mine of information." Isaac I. Auerbach, President, Auerbach Corp.

". . . we should all read this book, and have some feeling for the massive collection of data it contains." C. Gordon Bell, Vice-President, D.E.C.

". . . a great product. It is not very often I feel that I got at least ten times my money's worth for a book." Tom Gilb, Consultant.

". . . a magnificent compilation of data. I do not know of any other of comparable scope. Furthermore, the accompanying textual materials are extremely well developed." Carl Hammer, Director, Computer Sciences, Sperry-Univac.

EXAMINE IT FREE!
ORDER A 15-DAY TRIAL COPY TODAY!

Publ. 11/76. 574 + xviii pages, 458 figures, 181 tables with over 65,000 entries. 8½x11", paperback, $19.95 (plus $1.20 tax in Calif.)

SANTA MONICA PUBLISHING COMPANY
Dept. CD-11, PO Box 3543, Santa Monica, CA. 90403

SIRS: Please send me _____ copies of *Data Processing Technology and Economics.* If not satisfied, I may return the book in 15 days for a guaranteed refund. Check enclosed ☐. Bill me, add $1.25 handling ☐.

Name

Address

City/State/Zip

GUIDE TO PRODUCT INFORMATION

PAGE

Decitek/Jamesbury **84**

Punched Tape Reader
EECO **171**

COMPUTERS AND COMPUTER SYSTEMS

AUTOMATIC TEST SYSTEMS

Automatic Logic Test Systems
Fluke Trendar/John Fluke Mfg **49**

COMPUTER AUXILIARY UNITS

Microcomputer Auxiliary Modules
Micronics 144

CONTROL PROCESSORS PAGE

Memory Management Control Processor
Leeds & Northrup/Systems 209

Process Control System
Digitek 182

GRAPHICS PROCESSORS

Graphic Processor
Megatek **182**

MICROCOMPUTERS AND MICROPROCESSORS

Microcomputers
Digital Equipment **10, 11**
General Automation **24, 25**
Pro-Log **140**

Militarized Microcomputer
Norden/United Technologies **59**

Microcomputer Chip
Rockwell International/ Microelectronics **154, 155**

Microcomputer Family
Panasonic Electronic Components 134

Microcomputer Systems
General Robotics 142
muPro **137**
Unicomp 142

Microcomputer System Modules
Plessey Microsystems/ Microcomputer Products 134

Microcomputer Auxiliary Modules
Micronics 144

Microcomputer Development Systems
Futuredata Computer **22, 23**
Process Computer Systems **197**
Zilog 134

Microcomputer Terminal System
Digi-Log Systems 172

Multiprocessing Disystem Series
Systemathica Consulting Group 144

Video Interface Processor Kit
RCA Solid State 136

CMOS Processor
Motorola Semiconductor Products 156

Microprocessor
NEC Microcomputers **135**

Microprocessor Lab
Tektronix **118, 119**

Microprocessor Development System
National Semiconductor/Microcomputer ..136

Microprocessor Tester
Intel **66, 67**

Microprocessor TV Course
Electronic Product Associates 144

Macro Cross Assembler
Xener 144

MULTIPROCESSORS

Multiprocessor System
Siemens AG 182

MINICOMPUTERS; SMALL- AND MEDIUM-SCALE COMPUTERS

Computers and Peripherals
Data General **166, 167**

Computer Systems
Modular Computer Systems **185**

Minicomputers
Computer Automation **50, 51**
Digital Equipment **130, 131**
Interdata/Perkin-Elmer Data Systems **63**
Sperry Univac **153**
Texas Instruments/Digital Systems **60, 61**

Militarized Minicomputers
Rolm **45**

Minicomputers and Multiprocessor System
Siemens AG 182

PROGRAMMABLE CALCULATORS

Pocket-Sized Programmable Calculator
Hewlett-Packard 211

TIMESHARING/DISTRIBUTED PROCESSING COMPUTERS AND SYSTEMS

Distributed Processing System
Systems Engineering Laboratories **18, 19**

DATA COMMUNICATIONS EQUIPMENT

COMMUNICATIONS COUPLERS

Acoustic Coupler/Modem
Anderson Jacobson 202

COMMUNICATIONS MONITORS

Communications Monitor
Epicom **111**

Network Diagnostic Controller
Racal/Milgo **2**

COMMUNICATIONS MULTIPLEXERS

Time Division Multiplexer
Timeplex 204

MODEMS; DATA SETS

Data Modem
Westwood Associates 196

Acoustic Coupler/Modem
Anderson Jacobson 202

OTHER DATA COMMUNICATIONS EQUIPMENT

Offline Cassette Recorder
Memodyne 192



ICC. The leader in light pens since 1966. Now offering improved performance. Lower prices too. What are you waiting for? Write for full details or call, today.

INFORMATION CONTROL CORPORATION
9610 Bellanca Ave., Los Angeles, Ca. 90045 (213) 641-8520

Line Controller **PAGE**
C. D. Johnson & Associates 190
Data Communications Send/Receive Option
Spectron 192

DATA ACQUISITION AND CONTROL EQUIPMENT

A-D AND D-A CONVERTERS
A-D Converter
Teledyne Semiconductor 156
D-A Converter
Advanced Micro Devices 158

ANALOG MULTIPLEXERS
Control Multiplexer
Cutler-Hammer 159

ANGLE AND POSITION ENCODERS
Shaft Encoder
Astrosystems 188
Modular Optical Encoder
Litton Systems/Encoder 186

DATA ACQUISITION SYSTEMS
Data Acquisition System
ADAC 188, **190**
Hybrid Data Acquisition Systems
Datel Systems 172

DATA TRANSFER AND INTERFACE EQUIPMENT
Interface Module
RBI Systems 198
Output Boards
Burr-Brown 134
I/O Controller Board
I O R 192

MONITORING AND CONTROL EQUIPMENT
Programmable Controller
Gould/Modicon 211
Process Control Systems
Digitek 182
Doric Scientific/Emerson Electric 212

SCANNERS
Modular Scanner
San Diego Instrument Laboratory 180
Noncontact Gauging System
Gould/Instrument Systems 184

TEST AND MEASUREMENT EQUIPMENT; INSTRUMENTATION

COUNTERS; TIMERS
Elapsed Time Indicator
North American Philips Controls 202

DIGITAL EQUIPMENT TESTERS
Digital Tester
Tektronix **42, 43**
Portable Tester
Bendix **7**
Microprocessor Tester
Intel **66, 67**
Semiconductor Memory Test System
Teradyne **53**
Offline Terminal Tester
Atlantic Research 212
Automatic Logic Test Systems
Fluke Trendar/John Fluke Mfg **49**
Automatic Logic Tester Option
Computer Automation/
Industrial Products 188
Logic Analyzers
Hewlett-Packard ....**Cover II**
Kenmark Development Group 206
Logic Analyzer Board
Paratronics 174
Logic Analyzer Probe
Biomation 211
Logic Probes
Continental Specialties **183**
Kurz-Kasch/Electronics **198**

INSTRUMENTATION RECORDERS
DC Recorder With Edge Printer
MFE 206

PULSE GENERATORS
Data Generator
Moxon 172

OSCILLOSCOPES
Oscilloscope
Leader Instruments 194

OTHER TEST AND MEASUREMENT EQUIPMENT
Automatic RLC Tester **PAGE**
GenRad 209

OTHER PRODUCTS; SERVICES

EDUCATION
Seminars
Integrated Computer Systems **200, 201**
Microprocessor TV Course
Electronic Product Associates 144

EMPLOYMENT OPPORTUNITIES
Employment Opportunities
Boeing **178**
General Dynamics/Electronics **20**
NCR/Terminal Systems **152, 192**
Tektronix **190**

EQUIPMENT BUYING, SELLING, & LEASING
Electronic Equipment Rentals
Rental Electronics **31**

EXHIBITIONS **PAGE**
Conference/Exhibition
Mini/Micro Conference & Exposition **70**

OTHER NONDIGITAL PRODUCTS
Security Equipment
Motorola Government Electronics **223**
Access Control System
Schlage Electronics 206

PUBLICATIONS
Data Processing Book
Santa Monica Publishing **219**

SOFTWARE
Macro Cross Assembler
Xener 144
Word Processing Formatting Program
Ortronics 144
High Speed Verifier
Ungermann Associates/
RRC International 140

ANY WAY YOU LOOK AT IT...

647-4100

GLASFLEX "NON-GLARE" IS THE ANSWER.



Glasflex matte finish is a cell-cast acrylic sheet and should not be confused with chemically coated extruded sheets. It is a material which effectively reduces glare on instrument panel faces, microfiche, readout screens, CRT screens, rear view screens, computer back plates, instrument dials and gauges and digital instrument readouts.

Matte finish is available in clear or tint with different degrees of light diffusion to meet your specifications. It can be supplied in sheets or fabricated in sizes, shapes, and thicknesses to suit your requirements.

Matte finish can be used wherever there are light-diffusing and non-glare surface applications.

You can count on Glasflex's 40+ years of experience and expertise to clear up your most glaring instrument panel problems. Phone or write today.

glasflex CORPORATION

18 Stirling Road
Stirling, New Jersey 07980
(201) 647-4100



Raster scan high resolution refresh graphics

at a price you can't ignore

Now you can have a system
to meet your unique computer-graphics applications

System-sophistication made practical for the OEM and end-user

- Full refresh, flicker-free, raster scan display
  - -up to 1280 x 1024 pixels in 16-levels of grayscale
  - -display 1024 simultaneous colors from color look-up table
  - -up to 16 bits of intensity or overlay data per pixel
- Interfaces for most minicomputers
- Gamma-corrected and composite video output
- High-speed, variable image processing
  - -pixel update as fast as 45 nsec per pixel
  - -random and sequential update
  - -dynamic memory allocation
  - -writeable control store
- User can program the alphanumeric generator and define the cursor
- Nondestructive functions to highlight image displayed
  - -vector and alphanumeric overlays on image
  - -zoom with continuous 4-directional scrolling
- Command I/O and DMA to host computer
- Peripheral options

A versatile graphics-system to meet your widely diverse needs that you'll want to know more about. Just write Lexidata Corporation, 215 Middlesex Turnpike, Burlington, MA 01803 or faster yet, call us at 617 273-2700, and ask for Martin Duhms.

Best in graphics, year after year

Lexidata Corporation

215 Middlesex Turnpike, Burlington, MA 01803
617 273-2700 • TWX 710-332-1381

ADVERTISERS' INDEX

ACDC Electronics 189
ADAC Electronics Corp. 190
AMP, Inc. 54, 55
Amphenol North American Div., Bunker Ramo Corp. 65
Anadex Corp. 26
Analog Devices, Inc. 218
Ann Arbor Terminals 192
Applied Digital Data Systems, Inc. 21
Associated Computer Consultants 194
Axiom Corp. 141

Ball Brothers Research Corp., Electronic Display Div. 195
Bendix Corp., Test Systems Div. 7
The Boeing Co. 178

Canon U.S.A., Inc. 176
Centronics Data Computer Corp. 187
Charles River Data Systems, Inc. 180
Citizen America Corp. 204
Cipher Data Products 28, 29
Computer Automation, Inc. 50, 51
Conrac Corp. 181
Continental Specialties Corp. 183
Cortron, a div. of Illinois Tool Works, Inc. 15
Cutler-Hammer, Inc. 159
Cyberchron Corp. 188

Data General Corp. 166, 167
Dataproducts 114, 115
Dataram Corp. 95
Data Systems Design, Inc. 199
Datum, Inc. 72
Decitek, a div. of Jamesbury Corp. 84
Diablo Systems, Inc., a Xerox Co. ..... Cover IV
Digi-Data Corp. 121
Digital Equipment Corp. 130, 131
Components Group 10, 11
Dylon Corp. 129

EECO 171
EMM SEMI, Inc., a sub of Electronic Memories & Magnetics Corp. 208
Electronic Processors, Inc. 152
Elpac Electronics, Inc. 193
Epicom, Inc. 111

Fabri-Tek, Inc. 203
Fenner America 215
Ferranti Electric, Inc., Semiconductor Products Div. 162
Florida Data Corp. 98
John Fluke Manufacturing Co., Inc. 49
Futuredata Computer Corp. 22, 23

Gates Acoustinet, Inc. 68
General Automation, Inc. 24, 25
General Dynamics, Electronics Div. 20
General Electric Co., Plastics Div. 151
GenRad 198
Glasflex Corp. 221
Gould Inc., Electronic Components Div. ..... Cover III
Grayhill, Inc. 142
GTCO Corp. 224
GTE Sylvania, PMG Parts Div. 113

Harris Corp., Semiconductor Products Div. 83
Heinemann Electric Co. 202
Hewlett-Packard Co. ..... Cover II, 16, 17, 145
Houston Instrument, Div. of Bausch & Lomb 44, 71
Integrated Computer Systems 200, 201
Information Control Corp. 220
Infotek Systems 173
Instrument Specialties Co, Inc. 196
Intel Corp. 66, 67
Intel Memory Systems 170 171
Intelligent Systems Corp. 144, 145
Interdata, Inc., a unit of Perkin-Elmer Data Systems 63
Interstate Electronics 127
C. Itoh Electronics, Inc. 109

Kennedy Co. 1
Kurz-Kasch, Inc. 198

Lear Siegler, Inc. 163
Lexidata Corp. 222

3M Co. 117
Mincom Div. 160, 161
Magnavox 169
Master Specialties Co. 179
Maxi-Switch Co. 33
MDB Systems, Inc. 184
Megatek Corp. 182
MFE Corp. 34, 35
Micro Memory, Inc. 216
Micro Switch, a div. of Honeywell 37, 128, 129
Minicomputer Accessories 206
Mini/Micro Computer Conference and Exposition 70
Modular Computer Systems, Inc. 185
Monolithic Systems Corp. 13, 205
Motorola Inc., Government Electronics Div. 223
Semiconductor Products Div. 122, 123
Mupac 174
muPro, Inc. 137

NCR Corp., Terminal Systems Div. 152, 192
NEC Microcomputers, Inc. 135
Norden Div., United Technologies Corp. 59
North American Philips Controls Corp. 202

Perkin-Elmer Data Systems, Terminals Div. 38, 39, 41
Pertec Computer Corp. 46, 47, 125
Pittman Corp. 206
Plessey Microsystems 138, 139
Power/Mate Corp. 194
Power-One, Inc. 8, 9
Printronix, Inc. 207
Process Computer Systems 197

Racal-Milgo, Inc. 2
Ramtek Corp. 56, 57, 69
Raymond Engineering, Inc., Raycorder Products Div. 210
Ramtek Corp. 56, 57, 69
Renbrandt, Inc. 204
Rental Electronics, Inc. 31
Research, Inc. (See Teleray) 186
Rockwell International, Microelectronics Div. 154, 155
Rolm Corp 45

Santa Monica Publishing Co. 219
Shugart Associates 96, 97
Singer Co., Librascope Div. 214
Sperry Univac 153
Stacoswitch 212
Sweda International, Inc., OEM Products Div. 5
Systems Engineering Laboratories, Inc. 18, 19
Systems Industries 175

Talos Systems, Inc. 105
Tally Corp. 32a-h*
Tektronix, Inc. 42, 43, 118, 119, 190
Teleray, Div. of Research, Inc. 186
Teletype Corp. 177
Telex Computer Products, Inc. 147-149
Teradyne, Inc. 53
TEXAS INSTRUMENTS INCORPORATED,
Digital Systems Div. 60, 61
TRW LSI Products 157

Union Carbide Corp. 196

Versatec, a Xerox Co. 191
Vertel, Inc. 216
Victor Business Products 4
Viking Industries 165

Wang Laboratories, Inc. 224
Warner Electric Brake & Clutch Co. 209, 211, 213

*Appearing in selected copies

STOP THIEF!



Electronic Info-guard™ stops computer thieves

Computer-information thieves are among the most sophisticated of all white-collar criminals. Data transmission, processing, and storage are all open to the potential threat. Whether you are using small, medium, or large-scale computers or shared-resource networks.

Motorola's Info-guard system protects data against unauthorized access.

All Info-guard systems provide hardware, not software, protection for your computer information using the National Bureau of Standard's algorithm . . . an encryption code adopted by the U.S. Government to make it virtually impossible for information thieves to electronically crack your system.

OEM compatible, or simply added on to interface with operating computer systems.

Info-guard's designed-in protection is based on decades of experience in building secure communications for national defense.

If you're interested in making your computer data electronically safe, you need copies of the free booklets, "Computer Threats" and "The Info-guard Security Kit." Then we can talk about hardware prices and delivery. Call James Booth, 602/949-4111 or write to him at Motorola Government Electronics Division, Dept. F-3, P.O. Box 2606, Scottsdale, AZ 85252.

MOTOROLA

CIRCLE 145 ON INQUIRY CARD

DATATIZER...

"the new digitizing tablet standard"

Accurately digitize to **0.001 inch resolution** with GTCO's precision printed circuit grid tablet DATATIZER.

The unparalled stability and reliability provided by the precision printed circuit grid, coupled with a unique electromagnetic ranging principle ensures a lifetime of high accuracy digitizing with **no adjustments, no preventive maintenance** and **no detrimental environmental effects.**

Standard low profile tablet sizes: 11" x 11", 11" x 17", 14" x 14" and 20" x 20" active area; other sizes to 42" x 60" are available. Controllers are available as complete systems and in single PC board OEM configurations.

Don't delay. Contact GTCO for additional information on DATATIZER, the low cost, absolute coordinate digitizer setting industry standards.



GTCO Corporation
1055 First Street, Rockville, Md. 20850
Telephone (301) 279-9550 or (301) 424-7077

CIRCLE 146 ON INQUIRY CARD

WANG TERMINAL PRODUCTS

THE ONLY INTELLIGENT CHOICE.

Intelligent terminal? Standalone System? With Wang you don't have to make a choice. Wang terminals deliver both capabilities for less than the price of most *ordinary* intelligent terminals—just $9,200 including 50K memory, dual minidiskette drives and bisynchronous communications.

Hungry for more intelligence?
Mail this coupon to Wang Terminal Products Division, Dept. 66, Wang Laboratories Inc., One Industrial Ave., Lowell, MA 01851.

I'm hungry; send information on Wang Terminal Products
CDES 117
Name _____
Title _____ Phone _____
Company _____
Address _____
City _____ State _____ Zip _____

CIRCLE 147 ON INQUIRY CARD

SALES OFFICES

NEW ENGLAND, NEW YORK STATE

Lindsay H. Caldwell
129 Cedar Hill Road
East Dennis, MA 02641
phone: (617) 385-2533

MIDDLE AND SOUTH ATLANTIC STATES

Hajar Assoc., Inc.
Emile H. Hajar
Paul Hajar
Silvio Mandino
521 5th Avenue
New York, NY 10017
phone: (212) 682-5844

MIDWESTERN STATES

Hajar Assoc., Inc.
Emile H. Hajar
Paul Hajar
Silvio Mandino
664 North Michigan Avenue
Suite 1010
Chicago, IL 60611
phone: (312) 337-8008

SOUTHWESTERN STATES

Lindsay H. Caldwell
129 Cedar Hill Road
East Dennis, MA 02641
phone: (617) 385-2533

WEST COAST STATES

Buckley Boris Assoc.
Terry Buckley—Tom Boris
912 South Barrington Avenue
Suite 202
Los Angeles, CA 90049
phone: (213) 826-4621